SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE: 90% FEDERAL, 10% STATE — 0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	100% ISTHA — 0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	100% LOCAL NTFPD 0021 SAFETY
*87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	574			574					
*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4,656			4,656					
*87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	490			490					
*87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	2,056			2,056					
*87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	7			7					
*87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1			1					
*87700140	STEEL MAST ARM ASSEMBLY AND POLE, 20 FT.	EACH	1			1					
*87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1			1					
87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1			1					
87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	1			1					
87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	1			1					
*87800100	CONCRETE FOUNDATION, TYPE A	FOOT	32			32					
*87800150	CONCRETE FOUNDATION, TYPE C	FOOT	12			12					
*87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10			10					

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

* SPECIALTY ITEMS