

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD		
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	50			50						
87900200	DRILL EXISTING HANDHOLE	EACH	6			6						
87900205	DRILL EXISTING HEAVY DUTY HANDHOLE	EACH	1			1						
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	10			10						
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	9			9						
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	1			1						
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1			1						
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	11			11						
88500100	INDUCTIVE LOOP DETECTOR	EACH	14			14						
88600700	PREFORMED DETECTOR LOOP	FOOT	1,050			1,050						
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2			2						
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	4,225			250				3975	▲	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	3			3						
89502380	REMOVE EXISTING HANDHOLE	EACH	7							7	▲	

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

* SPECIALTY ITEMS

FILE NAME - #FILES#	USER NAME - default	DESIGNED - JMG	REVISED -
		DRAWN - JMG	REVISED -
PLT SCALE - 1/8"=1'-0" 1/4"=5'		CHECKED - RGR	REVISED -
PLT DATE - 6/19/2012		DATE - 6/19/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 18 OF 29 SHEETS STA. NA TO STA. NA

F.A. RTE. 94	SECTION 49-1-R-1	COUNTY LAKE	TOTAL SHEETS 677	SHEET NO. 21
CONTRACT NO. 60L77			ILLINOIS FED. AID PROJECT	

▲ Rev. 7-23-12

S:\18105-CAD\0501\077-1L-173\08-27-Sheets\05IBEL-77-18-18-000.dgn