

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE								
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD		
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY	
X8950115	RELOCATE LIGHT DETECTOR	EACH	5			5						
X8950120	RELOCATE LIGHT DETECTOR AMPLIFIER	EACH	2			2						
*XX005940	REMOTE-CONTROLLED VIDEO SYSTEM	EACH	1			1						
*XX007952	TERMINAL SERVER	EACH	1			1						
*XX008253	VIDEO ENCODER	EACH	1			1						
Z0004552	APPROACH SLAB REMOVAL	SO YD	408	408								
Z0005216	HOT-MIX ASPHALT STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SO YD	1,221	1,221								
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.3				0.7				
Z0018010	DRAINAGE SCUPPERS, DS-33	EACH	6			6						
Z0018800	DRAINAGE SYSTEM	L SUM	1						1			
Z0023500	FILLING EXISTING CULVERTS	CU YD	100	91				9				
Z0026407	TEMPORARY SHEET PILING	SO FT	1,330						1,330			
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	12	12								
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	10	4				6				

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbadainc.com

• SPECIALTY ITEMS

FILE NAME * 4FILES4	USER NAME * dofault	DESIGNED - JMG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE. 94	SECTION 49-1-R-1	COUNTY LAKE	TOTAL SHEETS 677	SHEET NO. 25
		DRAWN - JMG	REVISED -		SCALE: NA	SHEET NO. 22 OF 29 SHEETS	STA. NA	TO STA. NA	CONTRACT NO. 60L77				
		CHECKED - ROR	REVISED -		[ILLINOIS] FED. AID PROJECT								
		DATE - 6/19/2012	REVISED -										