

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE								
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD		
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY	
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2			2						
J1312020	STABILIZED SUBBASE - HOT-MIX ASPHALT 3"	SO YD	34,265					34,265				
J1420005	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	6,131					6,131				
J1481110	AGGREGATE SHOULDERS WITH FILTER FABRIC, TYPE B 6"	TON	2,416					2,416				
J1602010	CATCH BASIN, TYPE B	EACH	6					6				
J1602115	CATCH BASINS, TYPE G-2, TYPE G-2 FRAME AND GRATE	EACH	1					1				
J1602740	DRAINAGE STRUCTURES, TYPE 4 WITH TWO TYPE 20A FRAME AND GRATE	EACH	1					1				
J1606010	GUTTER, TYPE G-2	FOOT	1,457					1,457				
J1606020	GUTTER, TYPE G-3	FOOT	10					10				
*J1630002	GALVANIZED STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1237.5							1237.5		
*J1630004	GALVANIZED STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	475.4							475.4		
*J1631135	TRAFFIC BARRIER TERMINAL, TYPE T6B	EACH	3							3		
*J1631140	TRAFFIC BARRIER TERMINAL, TYPE T10	EACH	2							2		
*J1637001	CONCRETE BARRIER BASE	FOOT	160							160		

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

* SPECIALTY ITEMS

FILE NAME - #FILES#	USER NAME - default	DESIGNED - JMG	REVISED -
		DRAWN - JMG	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 6/19/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 24 OF 29 SHEETS STA. NA TO STA. NA

F.A. RTE. 94	SECTION 49-1-R-1	COUNTY LAKE	TOTAL SHEETS 677	SHEET NO. 27
CONTRACT NO. 60L77			ILLINOIS FED. AID PROJECT	

S:\181805_000\60L77 IL 49-1-R-1 Sheets\60L77-27.dwg