EARTHWORK SCHEDULE			STAGE 1						STAGE 2						STAGE 3					
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
MAINLINE I-94			CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
3978+89.91	TO	3979+00.00	9.68	8.23	0.00	8.23	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3979+00.00	TO	3979+20.42	28.84	24.52	0.00	24.52	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3979+20.42	TO	3980+00.00	167.01	141.96	0.00	141.96	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3980+00.00	TO	3981+00.00	236.37	200.91	0.00	200.91	21.56	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3981+00.00	TO	3982+00.00	263.20	223.72	1.56	222.17	54.07	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3982+00.00	TO	3983+00.00	262.46	223.09	11.72	211.37	62.15	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3983+00.00	TO	3984+00.00	198.22	168.49	57.24	111.25	95.41	5.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3984+00.00	TO	3985+00.00	170.31	144.77	158.00	-13.23	216.48	44.89	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3985+00.00	TO	3986+00.00	183.46	155.94	190.24	-34.30	297.69	80.78	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3986+00.00	TO	3987+00.00	195.13	165.86	153.59	12.27	293.72	81.72	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3987+00.00	TO	3988+00.00	216.76	184.25	138.48	45.76	307.46	84.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3988+00.00	TO	3989+00.00	271.19	230.51	113.63	116.88	331.09	90.83	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3989+00.00	TO	3989+50.00	125.08	106.32	60.91	45.41	117.84	29.44	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3989+50.00	TO	3990+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	106.81	90.78	72.61	18.17	118.17	29.29
3990+00.00	TO	3991+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	364.76	310.05	174.85	135.19	388.56	109.13
3991+00.00	TO	3992+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	482.74	410.33	214.76	195.57	427.02	121.20
3992+00.00	TO	3993+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	338.07	287.36	163.41	123.96	251.57	64.28
3993+00.00	TO	3994+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	227.67	193.52	50.67	142.85	42.09	5.52
3994+00.00	TO	3995+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	239.91	203.92	119.24	84.68	177.20	46.24
3995+00.00	TO	3996+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	218.70	185.90	221.76	-35.86	323.56	85.67
3996+00.00	TO	3997+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	272.07	231.26	207.74	23.52	337.74	93.76
3997+00.00	TO	3998+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	287.83	244.66	201.24	43.42	311.11	84.74
3998+00.00	TO	3999+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	220.59	187.50	192.20	-4.70	263.70	68.83
3999+00.00	TO	4000+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	182.91	155.47	204.33	-48.86	289.74	77.59
4000+00.00	TO	4001+00.00	179.59	152.65	223.94	-71.29	300.44	81.52	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4001+00.00	TO	4002+00.00	175.63	149.29	257.63	-108.34	304.67	83.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4002+00.00	TO	4003+00.00	172.91	146.97	254.04	-107.07	267.94	70.39	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4003+00.00	TO	4004+00.00	178.13	151.41	250.54	-99.13	249.89	64.06	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4004+00.00	TO	4005+00.00	166.04	141.13	270.78	-129.65	253.31	65.24	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4005+00.00	TO	4006+00.00	162.15	137.83	283.33	-145.51	245.50	62.65	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4006+00.00	TO	4007+00.00	161.41	137.20	309.69	-172.49	278.30	73.54	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4007+00.00	TO	4008+00.00	156.50	133.03	308.72	-175.70	273.15	71.65	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4008+00.00	TO	4009+00.00	160.69	136.58	316.11	-179.53	237.98	59.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4009+00.00	TO	4010+00.00	171.44	145.73	317.37	-171.64	248.30	63.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4010+00.00	TO	4011+00.00	175.85	149.47	289.00	-139.53	278.31	72.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4011+00.00	TO	4012+00.00	187.52	159.39	288.57	-129.18	320.24	86.39	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4012+00.00	TO	4013+00.00	191.94	163.15	298.69	-135.53	323.65	87.44	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4013+00.00	TO	4014+00.00	175.87	149.49	322.54	-173.05	321.37	86.91	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4014+00.00	TO	4015+00.00	174.87	148.64	347.81	-199.18	339.96	93.33	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4015+00.00	TO	4016+00.00	179.44	152.53	325.35	-172.82	327.52	89.65	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4016+00.00	TO	4017+00.00	182.56	155.17	301.00	-145.83	291.61	78.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4017+00.00	TO	4018+00.00	168.00	142.80	414.15	-271.35	290.70	77.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4018+00.00	TO	4019+00.00	213.74	181.68	510.09	-328.41	339.93	94.17	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4019+00.00	TO	4020+00.00	265.07	225.31	488.56	-263.24	375.72	106.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4020+00.00	TO	4021+00.00	266.69	226.68	415.70	-189.02	368.69	103.50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4021+00.00	TO	4022+00.00	287.63	244.49	374.56	-130.07	361.35	100.93	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4022+00.00	TO	4023+00.00	245.72	208.86	354.24	-145.38	352.80	98.17	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4023+00.00	TO	4024+00.00	193.20	164.22	226.30	-62.07	254.44	65.59	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4024+00.00	TO	4025+00.00	187.02	158.97	140.15	18.82	157.76	33.31	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4025+00.00	TO	4026+00.00	181.26	154.07	143.31	10.76	153.30	31.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4026+00.00	TO	4027+00.00	174.20	148.07	168.19	-20.11	211.00	51.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4027+00.00	TO	4028+00.00	175.93	149.54	208.44	-58.91	244.94	62.37	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4028+00.00	TO	4029+00.00	184.11	156.49	289.52	-133.02	221.17	54.26	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4029+00.00	TO	4030+00.00	190.28	161.74	316.74	-155.00	257.61	66.43	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4030+00.00	TO	4031+00.00	208.26	177.02	365.56	-188.54	319.59	87.17	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4031+00.00	TO	4032+00.00	232.04	197.23	436.63	-239.40	336.43	91.54	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4032+00.00	TO	4033+00.00	211.83	180.06	432.07	-252.02	319.26	85.17	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4033+00.00	TO	4034+00.00	183.83	156.26	361.54	-205.28	265.89	68.24	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4034+00.00	TO	4035+00.00	181.76	154.50	268.78	-114.28	242.39	60.67	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4035+00.00	TO	4036+00.00	224.20	190.57	226.02	-35.45	293.87	79.44	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4036+00.00	TO	4037+00.00	293.81	249.74	223.15	26.59	340.50	96.09	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4037+00.00	TO	4038+00.00	299.04	254.18	283.93	-29.74	356.87	100.37	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4038+00.00	TO	4039+00.00	271.44	230.73	351.96	-121.24	337.74	92.48	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4039+00.00	TO	4040+00.00	286.80	243.78	408.48	-164.70	318.28	84.33	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4040+00.00	TO	4041+00.00	328.54	279.26	423.02	-143.76	362.65	97.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4041+00.00	TO	4042+00.00	340.06	289.05	405.22	-116.18	355.87	93.96	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4042+00.00	TO	4043+00.00	400.15	340.13	364.94	-24.82	316.56	79.31	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4043+00.00	TO	4044+00.00	438.87	373.04	340.24	32.80	357.11	91.30	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4044+00.00	TO	4045+00.00	348.00	295.80	351.02	-55.22	355.04	89.15	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4045+00.00	TO	4046+00.00	290.46	246.89	306.80	-59.90	301.06	70.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

FILE NAME - $FILES$	USER NAME - default	DESIGNED -	REVISED 1 7/17/12 RGR
		DRAWN -	REVISED -
	PLOT SCALE - H:1"=10' V:1"=5'	CHECKED - RGR	REVISED -
	PLOT DATE - 7/16/2012	DATE - 6/19/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CIVIL SCHEDULE

SCALE: NA | SHEET NO. 2 OF 8 SHEETS | STA. NA TO STA. NA

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1-R-1	LAKE	677	45

CONTRACT NO. 60L77

ILLINOIS FED. AID PROJECT

S:\1201\39.C\00-SK.77 IL 173-68.77 Sheets\0680_77-earthcivil schedule.dgn