

EARTHWORK SCHEDULE	STAGE 1						STAGE 2						STAGE 3					
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
MAINLINE I-94	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
4046+00.00 TO 4047+00.00	342.50	291.13	217.80	73.33	313.59	74.63	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4047+00.00 TO 4048+00.00	477.98	406.28	174.37	231.91	346.31	86.67	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4048+00.00 TO 4049+00.00	750.28	637.74	201.02	436.72	393.98	113.20	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4049+00.00 TO 4050+00.00	589.17	500.79	158.89	341.90	328.37	95.85	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4050+00.00 TO 4051+00.00	215.78	183.41	141.48	41.93	187.63	42.85	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4051+00.00 TO 4052+00.00	192.43	163.56	299.96	-136.40	190.20	43.26	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4052+00.00 TO 4052+61.46	138.09	117.38	291.07	-173.69	168.17	44.80	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

EARTHWORK SCHEDULE	STAGE 1						STAGE 2						STAGE 3					
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
MAINLINE I-94 (NORTHBOUND)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
4052+61.49 TO 4053+00.00	40.36	34.30	113.59	-79.29	72.13	19.95	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4053+00.00 TO 4054+00.00	81.35	69.15	193.48	-124.33	151.44	39.70	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4054+00.00 TO 4055+00.00	75.15	63.88	85.80	-21.92	94.15	21.43	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4055+00.00 TO 4055+79.30	53.01	45.06	109.74	-64.68	92.75	24.82	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4055+79.30 TO 4056+00.00	10.86	9.23	36.83	-27.60	31.88	9.46	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4056+00.00 TO 4056+50.01	20.92	17.78	36.09	-18.31	41.91	11.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4058+47.74 TO 4059+00.00	32.89	27.96	235.39	-205.43	149.78	45.44	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4059+00.00 TO 4060+00.00	56.37	47.91	342.96	-295.05	237.41	65.52	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4060+00.00 TO 4061+00.00	57.93	49.24	151.70	-102.47	128.07	26.91	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4061+00.00 TO 4062+00.00	55.72	47.36	86.69	-39.32	82.74	15.09	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4062+00.00 TO 4063+00.00	51.76	44.00	45.41	-1.41	49.91	8.67	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4063+00.00 TO 4063+09.98	5.12	4.35	3.08	1.27	3.72	0.62	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4063+09.98 TO 4063+50.82	20.13	17.11	5.07	3.04	11.43	1.63	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4067+60.87 TO 4068+00.00	15.41	13.10	46.03	-32.93	71.08	21.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4068+00.00 TO 4069+02.05	47.53	40.40	43.05	-2.63	80.73	19.16	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4069+02.05 TO 4070+00.00	39.83	33.86	84.47	-50.61	75.80	12.64	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4070+00.00 TO 4071+00.00	30.93	26.29	122.06	-95.77	101.06	16.46	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4071+00.00 TO 4072+00.00	32.81	27.89	797.44	-769.55	187.83	43.57	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4072+00.00 TO 4073+00.00	40.67	34.57	1366.80	-1332.23	72.26	68.50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4073+00.00 TO 4074+00.00	52.65	44.75	1192.13	-1147.38	262.06	81.09	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4074+00.00 TO 4074+18.37	9.67	8.22	205.88	-197.66	47.35	10.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4074+18.37 TO 4075+00.00	52.93	44.99	1224.88	-1179.89	237.50	55.06	145.28	123.49	36.39	87.10	48.39	10.72	50.28	42.74	0.00	42.74	0.00	0.00
4075+00.00 TO 4075+18.37	11.44	9.73	344.18	-334.46	59.30	14.02	34.13	29.01	5.60	23.41	9.16	2.74	10.76	9.14	0.00	9.14	0.00	0.00
4075+18.37 TO 4076+00.00	44.37	37.71	1244.62	-1206.90	240.84	54.00	147.55	125.42	18.88	106.54	35.80	9.77	47.22	40.14	0.00	40.14	0.00	0.00
4076+00.00 TO 4077+00.00	34.74	29.53	1237.44	-1207.91	276.56	58.67	161.44	137.23	21.78	115.45	37.02	11.96	47.56	40.42	0.00	40.42	0.00	0.00
4077+00.00 TO 4078+00.00	46.69	39.66	1296.35	-1256.67	292.81	62.93	128.83	109.51	23.37	86.14	34.41	11.96	34.43	29.26	0.00	29.26	0.00	0.00
4078+00.00 TO 4079+00.00	68.63	58.34	1274.70	-1216.37	305.24	66.81	120.20	21.74	80.43	27.19	7.06	31.93	27.14	0.00	27.14	0.00	0.00	0.00
4079+00.00 TO 4080+00.00	46.59	39.60	1170.70	-1131.10	304.15	66.96	120.52	102.44	17.69	84.76	19.83	2.07	28.24	24.26	0.00	24.26	0.00	0.00
4080+00.00 TO 4081+00.00	17.13	14.56	1070.61	-1056.05	282.04	60.50	113.63	96.59	18.57	78.01	25.46	2.44	24.63	20.94	0.00	20.94	0.00	0.00
4081+00.00 TO 4082+00.00	17.07	14.51	945.48	-930.97	275.30	59.35	126.33	107.38	24.02	83.36	38.04	4.72	27.31	23.22	0.00	23.22	0.00	0.00
4082+00.00 TO 4083+00.00	20.57	17.49	740.22	-722.73	242.78	51.63	141.61	120.37	17.46	102.91	35.61	3.28	31.20	26.52	0.00	26.52	0.00	0.00
4083+00.00 TO 4084+00.00	18.85	16.02	514.65	-498.62	185.28	36.06	122.13	103.81	34.85	68.96	43.56	6.22	28.87	24.54	0.00	24.54	0.00	0.00
4084+00.00 TO 4085+00.00	39.59	33.65	295.37	-261.72	142.59	26.54	113.93	96.84	50.15	46.69	53.04	9.69	30.11	25.59	0.00	25.59	0.00	0.00
4085+00.00 TO 4086+00.00	134.31	114.17	98.72	15.45	74.04	12.69	133.69	113.63	30.80	82.84	40.26	5.24	35.07	29.81	0.00	29.81	0.00	0.00
4086+00.00 TO 4087+00.00	157.17	133.50	23.76	109.84	50.83	2.22	91.03	77.37	27.70	39.67	4.83	40.96	34.82	0.00	34.82	0.00	0.00	0.00
4087+00.00 TO 4088+00.00	63.65	54.10	115.30	-61.20	110.15	13.61	85.69	72.83	34.61	36.22	46.57	7.02	39.59	33.65	0.00	33.65	0.00	0.00
4088+00.00 TO 4089+00.00	51.61	43.87	293.13	-249.26	149.20	25.80	82.50	70.13	26.52	43.61	41.37	5.11	39.04	33.18	0.00	33.18	0.00	0.00
4089+00.00 TO 4090+00.00	44.50	37.83	455.70	-417.88	173.69	32.48	75.65	64.30	250.07	-185.77	88.83	19.61	36.06	30.65	0.00	30.65	0.00	0.00
4090+00.00 TO 4091+00.00	36.69	31.18	755.76	-724.58	277.15	45.09	66.19	56.26	316.09	-259.84	128.30	31.19	31.15	26.48	0.00	26.48	0.00	0.00
4091+00.00 TO 4092+00.00	33.91	28.82	947.02	-918.20	240.74	51.63	64.91	55.17	123.28	-68.11	99.22	21.06	28.33	24.08	0.00	24.08	0.00	0.00
4092+00.00 TO 4093+00.00	42.70	36.30	834.72	-798.42	238.85	49.17	68.76	58.45	86.91	-28.46	81.28	14.70	31.15	26.48	0.00	26.48	0.00	0.00
4093+00.00 TO 4094+00.00	45.22	38.44	690.24	-651.80	219.85	41.15	60.17	51.14	72.56	-21.41	75.67	11.33	31.67	26.92	0.00	26.92	0.00	0.00
4094+00.00 TO 4095+00.00	36.35	30.90	387.59	-356.69	205.87	34.96	48.76	41.45	53.02	-11.								