

EARTHWORK SCHEDULE	STAGE 1							STAGE 2							STAGE 3				
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT		EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
IL-173	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
2016+08.15 TO 2017+00.00	135.34	115.04	142.78	-27.73	120.85	27.84		143.32	121.82	417.95	-296.13	180.38	48.90	0.00	0.00	0.00	0.00	0.00	0.00
2017+00.00 TO 2018+00.00	156.81	133.29	505.98	-372.69	209.72	55.54		177.06	150.50	813.72	-663.23	241.67	69.00	0.00	0.00	0.00	0.00	0.00	0.00
2018+00.00 TO 2019+00.00	158.04	134.33	1,238.26	-1,103.93	299.06	84.56		196.04	166.63	874.46	-707.83	249.83	72.20	0.00	0.00	0.00	0.00	0.00	0.00
2019+00.00 TO 2020+00.00	123.39	104.88	1,643.56	-1,538.68	325.98	112.78		176.11	149.69	1,399.98	-1,250.29	304.98	108.22	0.00	0.00	0.00	0.00	0.00	0.00
2020+00.00 TO 2021+00.00	80.65	68.55	1,456.13	-1,387.58	305.56	131.59		109.24	92.85	2,191.17	-2,098.31	374.65	155.13	0.00	0.00	0.00	0.00	0.00	0.00
2021+00.00 TO 2022+00.00	35.15	29.88	998.20	-968.33	246.59	124.02		46.83	39.81	2,790.26	-2,750.45	406.41	175.70	0.00	0.00	0.00	0.00	0.00	0.00
2022+00.00 TO 2023+00.00	6.43	5.46	1,324.41	-1,318.95	284.81	141.28		15.59	13.25	3,770.70	-3,757.45	452.57	197.54	0.00	0.00	0.00	0.00	0.00	0.00
2023+00.00 TO 2024+00.00	0.00	0.00	2,741.81	-2,741.81	366.57	168.39		0.35	0.30	4,414.09	-4,413.79	476.15	213.15	0.00	0.00	0.00	0.00	0.00	0.00
2024+00.00 TO 2025+00.00	0.00	0.00	4,083.39	-4,083.39	388.70	176.19		0.00	0.00	4,600.24	-4,600.24	470.39	216.04	0.00	0.00	0.00	0.00	0.00	0.00
2025+00.00 TO 2026+00.00	0.00	0.00	4,920.69	-4,920.69	426.00	187.41		0.00	0.00	4,185.50	-4,185.50	438.26	201.89	0.00	0.00	0.00	0.00	0.00	0.00
2026+00.00 TO 2026+50.00	0.00	0.00	2,633.36	-2,633.36	223.84	97.22		0.00	0.00	1,067.17	-1,067.17	123.73	67.90	0.00	0.00	0.00	0.00	0.00	0.00
2026+50.00 TO 2027+00.00	0.00	0.00	2,675.39	-2,675.39	225.94	75.54		0.00	0.00	364.85	-364.85	77.30	21.12	0.00	0.00	0.00	0.00	0.00	0.00
2027+00.00 TO 2027+50.00	0.00	0.00	2,741.35	-2,741.35	226.92	53.39		0.00	0.00	512.03	-512.03	112.94	12.99	0.00	0.00	0.00	0.00	0.00	0.00
2027+50.00 TO 2028+00.00	0.00	0.00	2,824.72	-2,824.72	227.78	53.76		0.00	0.00	861.93	-861.93	135.41	32.12	0.00	0.00	0.00	0.00	0.00	0.00
2028+00.00 TO 2029+00.00	0.00	0.00	4,443.20	-4,443.20	412.61	91.70		0.00	0.00	3,079.41	-3,079.41	351.87	91.61	0.00	0.00	0.00	0.00	0.00	0.00
2029+00.00 TO 2030+00.00	0.00	0.00	2,174.41	-2,174.41	283.35	57.69		0.00	0.00	4,639.30	-4,639.30	423.98	114.37	0.00	0.00	0.00	0.00	0.00	0.00
2030+00.00 TO 2030+05.58	0.00	0.00	65.89	-65.89	11.06	2.24		0.00	0.00	295.06	-295.06	25.23	6.82	0.00	0.00	0.00	0.00	0.00	0.00
2033+147.95 TO 2034+00.00	0.00	0.00	1,888.20	-1,888.20	195.90	89.01		0.00	0.00	2,226.56	-2,226.56	222.58	107.27	0.00	0.00	0.00	0.00	0.00	0.00
2034+00.00 TO 2035+00.00	0.00	0.00	3,562.94	-3,562.94	377.94	171.69		0.00	0.00	2,796.85	-2,796.85	387.52	193.19	0.00	0.00	0.00	0.00	0.00	0.00
2035+00.00 TO 2036+00.00	5.17	4.39	3,543.54	-3,539.15	379.50	172.31		6.61	5.62	1,080.07	-1,074.45	288.56	160.19	0.00	0.00	0.00	0.00	0.00	0.00
2036+00.00 TO 2037+00.00	24.06	20.45	2,680.85	-2,660.40	331.24	115.28		44.65	37.95	179.35	-141.40	157.19	66.74	0.00	0.00	0.00	0.00	0.00	0.00
2037+00.00 TO 2037+50.00	19.17	16.29	640.23	-623.94	120.75	43.99		44.40	37.74	67.26	-29.52	65.06	22.32	0.00	0.00	0.00	0.00	0.00	0.00
2037+50.00 TO 2038+00.00	18.14	15.42	258.65	-243.23	84.31	53.62		39.21	33.33	266.96	-233.63	91.21	53.03	0.00	0.00	0.00	0.00	0.00	0.00
2038+00.00 TO 2039+00.00	46.44	39.48	193.56	-154.08	142.91	56.59		42.00	35.70	726.94	-691.24	196.74	79.67	0.00	0.00	0.00	0.00	0.00	0.00
2039+00.00 TO 2040+00.00	74.94	63.70	118.52	-54.82	154.89	19.44		45.28	38.49	577.11	-538.63	180.09	36.52	0.00	0.00	0.00	0.00	0.00	0.00
2040+00.00 TO 2041+00.00	121.19	103.01	130.96	-27.96	153.57	20.74		167.15	142.08	279.50	-137.42	170.57	39.80	0.00	0.00	0.00	0.00	0.00	0.00
2041+00.00 TO 2042+00.00	144.20	122.57	211.59	-89.02	141.31	19.72		247.78	210.61	69.52	141.09	169.94	42.51	0.00	0.00	0.00	0.00	0.00	0.00
2042+00.00 TO 2043+00.00	132.78	112.86	265.59	-152.73	142.31	22.04		178.74	151.93	137.28	14.65	180.37	42.74	0.00	0.00	0.00	0.00	0.00	0.00
2043+00.00 TO 2044+00.00	112.98	96.03	224.96	-128.93	152.69	24.56		445.48	378.66	98.94	279.71	198.80	47.72	0.00	0.00	0.00	0.00	0.00	0.00
2044+00.00 TO 2045+00.00	110.91	94.27	201.24	-106.97	151.83	22.80		798.65	678.85	2.89	675.96	192.00	45.81	0.00	0.00	0.00	0.00	0.00	0.00
2045+00.00 TO 2046+00.00	129.26	109.87	89.96	19.91	126.31	20.54		484.76	412.05	4.44	407.60	113.76	21.37	0.00	0.00	0.00	0.00	0.00	0.00
2046+00.00 TO 2047+00.00	120.76	102.65	9.91	92.74	87.85	10.57		114.70	97.50	107.57	-10.08	87.54	14.09	0.00	0.00	0.00	0.00	0.00	0.00
2047+00.00 TO 2048+00.00	107.09	91.03	43.57	47.45	68.69	6.41		114.98	97.73	113.91	-16.17	82.07	17.98	0.00	0.00	0.00	0.00	0.00	0.00
2048+00.00 TO 2049+00.00	104.67	88.97	63.26	25.71	69.26	14.06		116.06	98.65	29.96	68.68	56.06	11.33	0.00	0.00	0.00	0.00	0.00	0.00
2049+00.00 TO 2050+00.00	101.74	86.48	38.87	47.61	68.09	16.09		98.85	84.02	78.48	5.54	68.54	13.30	0.00	0.00	0.00	0.00	0.00	0.00
2050+00.00 TO 2051+00.00	98.78	83.96	31.65	52.31	67.30	18.09		130.30	110.75	57.67	53.09	35.02	7.17	0.00	0.00	0.00	0.00	0.00	0.00
2051+00.00 TO 2051+71.59	75.10	63.84	21.17	42.67	48.44	14.42		93.69	79.64	15.29	64.35	16.01	1.68	0.00	0.00	0.00	0.00	0.00	0.00

EARTHWORK SCHEDULE	STAGE 1					
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
IL-173 (RAMP B)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
151+00.00 TO 151+67.45	3.24	2.75	1,343.72	-1,340.97	258.70	68.55
151+67.45 TO 152+00.00	6.81	5.79	344.13	-338.34	102.64	29.55
152+00.00 TO 153+00.00	122.28	103.94	495.22	-391.29	278.76	81.83
153+00.00 TO 154+00.00	321.28	273.09	25.93	247.16	254.69	75.17
154+00.00 TO 155+00.00	448.07	380.86	18.04	362.83	257.15	76.52
155+00.00 TO 156+00.00	394.41	335.25	18.24	317.01	209.20	61.39
156+00.00 TO 157+00.00	273.00	232.05	23.81	208.24	134.87	36.69
157+00.00 TO 158+00.00	206.83	175.81	24.69	151.12	115.07	31.17
158+00.00 TO 158+98.66	184.57	156.88	24.12	132.77	96.10	26.35

EARTHWORK SCHEDULE	STAGE 1					
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
IL-173 (RAMP A)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
53+40.00 TO 54+00.00	117.26	99.67	23.17	76.50	54.48	16.07
54+00.00 TO 55+00.00	218.44	185.68	122.07	63.60	190.09	54.76
55+00.00 TO 56+00.00	204.19	173.56	317.11	-143.55	264.39	70.30
56+00.00 TO 57+00.00	183.46	155.94	604.43	-448.48	299.74	74.00
57+00.00 TO 58+00.00	246.93	209.89	772.83	-562.95	336.52	80.24
58+00.00 TO 58+50.00	166.19	141.27	384.18	-242.91	185.17	44.74
58+50.00 TO 59+00.00	163.73	139.17	355.56	-216.39	207.88	53.02
59+00.00 TO 59+65.00	148.83	126.50	552.63	-426.13	259.71	51.34

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbendainc.com

FILE NAME - #FILES#	USER NAME - default	DESIGNED -	REVISED - 7/17/12 RGR
		DRAWN -	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 6/19/2012	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

CIVIL SCHEDULE			
SCALE: NA	SHEET NO. 5 OF 8 SHEETS	STA. NA TO STA. NA	

F.A. RTE. 94	SECTION 49-1-R-1	COUNTY LAKE	TOTAL SHEETS 677	SHEET NO. 48
CONTRACT NO. 60L77				
ILLINOIS FED. AID PROJECT				

S:\111135.CADD\60L77\111135.dwg

</