

EARTHWORK SCHEDULE			STAGE 2					
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT		
SB I-94 TO SB US-41	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
2001+00.00 TO 2002+00.00	199.76	169.80	22.17	147.63	43.13	7.06		
2002+00.00 TO 2003+00.00	178.61	151.82	18.61	133.21	35.61	4.24		
2003+00.00 TO 2004+00.00	206.06	175.15	17.81	157.33	48.52	9.91		
2004+00.00 TO 2005+00.00	259.31	220.42	15.76	204.66	69.04	10.98		
2005+00.00 TO 2005+66.48	198.73	168.92	5.02	163.89	34.63	6.57		
2005+66.48 TO 2006+00.00	130.73	111.12	2.11	109.01	20.40	9.84		
2006+00.00 TO 2007+00.00	429.63	365.19	7.02	358.17	49.87	32.67		
2007+00.00 TO 2008+00.00	318.56	270.77	3.09	267.68	5.54	18.54		
2008+00.00 TO 2008+02.35	5.51	4.68	0.03	4.65	0.00	0.39		
2008+02.35 TO 2009+00.00	135.72	115.36	76.31	39.05	57.60	22.42		
2009+00.00 TO 2010+00.00	32.02	27.22	319.50	-292.28	163.89	45.59		
2010+00.00 TO 2011+00.00	15.37	13.06	767.31	-754.25	280.76	74.00		
2011+00.00 TO 2011+11.19	2.24	1.90	115.35	-113.44	38.22	9.25		

EARTHWORK SCHEDULE			STAGE 1					
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT		
NB US-41 TO NB I-94	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
99+71.77 TO 100+00.00	59.31	50.41	93.22	-42.81	36.32	10.66		
100+00.00 TO 100+51.27	102.90	87.47	308.67	-221.21	125.07	38.31		
100+51.27 TO 101+00.00	103.79	88.23	230.18	-141.95	117.76	35.94		
101+00.00 TO 102+00.00	219.52	186.59	292.33	-105.74	224.17	68.09		
102+00.00 TO 103+00.00	193.17	164.19	196.41	-32.22	186.76	56.13		
103+00.00 TO 104+00.00	129.24	109.85	368.39	-258.53	194.78	59.20		
104+00.00 TO 105+00.00	61.37	52.16	589.83	-537.67	219.35	67.44		
105+00.00 TO 106+00.00	20.98	17.83	892.57	-874.74	235.65	72.31		
106+00.00 TO 107+00.00	8.28	7.04	1,352.31	-1,345.28	273.46	84.22		
107+00.00 TO 108+00.00	4.44	3.78	1,584.87	-1,581.09	287.13	88.96		
108+00.00 TO 108+63.47	6.06	5.16	972.01	-966.85	177.57	49.94		

EARTHWORK SCHEDULE			STAGE 1					
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT		
SB OLD US-41 TO SB I-94	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
180+30.54 TO 181+00.00	606.12	515.20	92.52	422.68	212.43	66.58		
181+00.00 TO 182+00.00	914.93	777.69	171.54	606.15	475.37	152.26		
182+00.00 TO 183+00.00	667.37	567.26	158.31	408.95	487.48	156.59		
183+00.00 TO 184+00.00	373.72	317.66	57.39	260.28	263.50	83.81		
184+00.00 TO 185+00.00	302.65	257.25	21.31	232.94	145.52	45.00		
185+00.00 TO 185+95.00	203.21	172.73	31.91	140.82	89.02	24.45		

EARTHWORK SCHEDULE			STAGE 2					
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT		
DETENTION BASIN*	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
4073+67.50 TO 4074+00.00	7.94	6.75	9.09	-2.35	48.39	16.13		
4074+00.00 TO 4075+00.00	347.65	295.50	62.85	232.65	440.09	146.69		
4075+00.00 TO 4076+00.00	918.11	780.39	52.94	727.45	722.33	240.78		
4076+00.00 TO 4077+00.00	1,318.80	1,120.98	7.80	1,113.18	750.80	250.28		
4077+00.00 TO 4078+00.00	1,476.43	1,254.96	39.54	1,215.43	770.13	256.85		
4078+00.00 TO 4079+00.00	1,375.20	1,168.92	77.31	1,091.61	793.72	264.87		

*DETENTION BASIN SECTIONS USE MAINLINE I-94 (NORTHBOUND) STATIONING

EARTHWORK SCHEDULE			PRESTAGE					
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT		
MAINTENANCE OF TRAFFIC	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
TEMPORARY PAVEMENT	0.00	0.00	816.00	-816.00	0.00	0.00		

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com

FILE NAME - #FILES#	USER NAME - default	DESIGNED -	REVISED - 7/17/12 RGR
		DRAWN -	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 6/19/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CIVIL SCHEDULE

F.A. RTE. 94	SECTION 49-1-R-1	COUNTY LAKE	TOTAL SHEETS 677	SHEET NO. 49
SCALE: NA			SHEET NO. 6 OF 8 SHEETS	
STA. NA TO STA. NA			CONTRACT NO. 60L77	
[ILLINOIS] FED. AID PROJECT				

S:\INFO\60L77\60L77_Sheets\60L77-1\60L77-1.dwg