

EARTHWORK SUMMARY BY STAGE	PRESTAGE			STAGE 1				STAGE 2					STAGE 3				
	EARTH EXCAVATION	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-)
LOCATION	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
MAINLINE I-94	-	-	15,758.43	-3,984.70	17,556.39	4,519.99	12,836.39	0.00	0.00	0.00	0.00	0.00	2,942.06	877.94	2,930.46	286.25	2,144.21
MAINLINE I-94 (NORTHBOUND)	-	-	2,652.31	-24,331.36	8,740.36	1,873.21	6,867.15	3,437.13	1,419.23	1,455.23	236.03	1,219.21	1,272.32	1,081.47	0.00	0.00	0.00
MAINLINE I-94 (SOUTHBOUND)	-	-	9,244.32	1,232.11	5,079.09	999.46	4,079.63	6,328.73	-2,228.02	3,445.19	834.93	2,610.26	2,237.32	1,901.72	0.00	0.00	0.00
IL-173	-	-	2,243.18	-48,926.06	7,650.45	2,573.09	5,077.35	4,077.82	-41,728.24	7,805.37	2,828.94	4,976.43	0.00	0.00	0.00	0.00	0.00
IL-173 - (RAMP B)	-	-	1,960.48	-651.48	1,707.20	487.21	1,219.99	-	-	-	-	-	-	-	-	-	-
IL-173 - (RAMP A)	-	-	1,449.03	-1,900.31	1,797.98	444.46	1,353.52	-	-	-	-	-	-	-	-	-	-
SB I-94 TO SB US-41	-	-	-	-	-	-	-	2,112.23	425.30	847.19	251.46	595.73	-	-	-	-	-
NB US-41 TO NB I-94	-	-	909.07	-6,108.09	2,078.02	631.23	1,446.79	-	-	-	-	-	-	-	-	-	-
OLD US-41 TO SB I-94	-	-	3,067.99	2,071.80	1,673.32	528.70	1,144.62	-	-	-	-	-	-	-	-	-	-
DETENTION BASIN	-	-	-	-	-	-	-	5,444.12	4,377.97	3,525.46	1,175.59	2,349.87	-	-	-	-	-
MAINTENANCE OF TRAFFIC	-	-816.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	0	-916	36,785	-82,578	46,083	12,057	34,025	21,400	-37,734	17,078	5,337	11,752	6,452	3,661	2,930	786	2,144

EARTHWORK SUMMARY	20200100	20400800	21101505
	EARTH EXCAVATION	FURNISHED EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT
STAGE	(CU YD)	(CU YD)	(CU YD)
PRESTAGE	0	816	0
STAGE 1	36,785	82,578	46,083
STAGE 2	21,400	37,734	17,078
STAGE 3	6,452	0	2,930
	64,637	121,128	66,092

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com



FILE NAME - #FILES*	USER NAME - default	DESIGNED -	REVISED - 7/17/12 RGR	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CIVIL SCHEDULE			F.A. RTI 94	SECTION 49-1-R-1	COUNTY LAKE	TOTAL SHEETS 677	SHEET NO. 50
	PLT SCALE = 1/8" = 1'-0"	DRAWN -	REVISED -		SCALE: NA	SHEET NO. 7 OF 8 SHEETS	STA. NA TO STA. NA	CONTRACT NO. 60L77				
	PLT DATE = 7/16/2012	CHECKED - RGR	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE - 6/19/2012	REVISED -									

S:\2012\05\60L77\11-17-12\05-60L77-INT-CIVIL-SCHEDULE.DWG