SCHEDULE OF QUANTITIES - ROADWAY SIGNING

SIGN DESIGNATION PANEL LEGEND / DESCRIPTION	SIGN NO.	STATION	SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	SIGN PANEL - TYPE 3	REMOVE SIGN PANEL ASSEMBLY-TYPE A	REMOVE SIGN PANEL ASSEMBLY-TYPE B	REMOVE SIGN PANEL-TYPE 1	REMOVE SIGN PANEL- TYPE 2	REMOVE SIGN PANEL-TYPE 3	MILE POST MARKER ASSEMBLY	STRUCTURAL STEEL SIGN SUPPORT-BREAKAWAY					WOOD SIGN SUPPORT			OVERHEAD SIGN STRUCTURE - SPAN TYPE III-A (5'-0" X 7'-0")	CONCRETE FOUNDATIONS	DRILLED SHAFT CONCRETE FOUNDATIONS	REMOVE OVERHEAD SIGN STRUCTURES - SPAN	REMOVE GROUND MOUNTED SIGN SUPPORT	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	REMOVE CONCRETE FOUNDATION - OVERHEAD	OVERHEAD SIGN STRUCTURE, CANTILEVER TYPE (STEEL) (30 FT)	FOUNDATION FOR OVERHEAD SIGN STRUCTURE, CANTILEVER TYPE V-BR	RELOCATE SIGN PANEL - TYPE 3
			SQ FT	SQ FT	SQ FT	EACH	EACH	SQ FT	SQ FT	SQ FT	EACH	POST SZ.	P1 (L.F.)	P2 (L.F.)	P3 (L.F.)	POUND	P1 (L.F.)	P2 (L.F.)	FOOT	FOOT	CU YD	CU YD	EACH	EACH	EACH	EACH	FOOT	CU YD	SQ FT
			72000100	72000200	72000300	72400100	72400200	72400310	72400320	72400330	72600100					72700100			73000100	73300300	73400100	73400200	73600100	73700100	73700200	73700300	JS733B30	JS734B10	72400730
ROSECRANS RD / 1 MILE / EXIT ONLY	NB-194-CL-01	SEE PLAN								236.25																			
ROSECRANS RD / 1 MILE	NB-194-CL-01	SEE PLAN			175																								
E1-5P (EXIT 2)	NB-194-CL-01	SEE PLAN		23.75																									
ROSECRANS RD / EXIT ONLY	NB-194-CL-02	SEE PLAN								192.5																			
ROSECRANS RD / 1/2 MILE	NB-194-CL-02	SEE PLAN			175																								
E1-5P (EXIT 2)	NB-194-CL-02	SEE PLAN		23.75																									
ROSECRANS RD / EXIT ONLY	NB-194-TR-03	3979+00								192.5																			
E1-5P (EXIT 2)	NB-194-TR-03	3979+00		23.75																									
ROSECRANS RD	NB-194-TR-03	3979+00			187																								
W3-1 (STOP SIGN AHEAD)	NB-194-LP-04	3980+91							16																				
E5-1a (EXIT 2)	NB-194-WP-05	3982+50			32.5					30							18	18	36					1					
R2-1 (SPEED LIMIT 65 MPH)	NB-194-WP-06	3986+29		20					20								22		22					1					
R2-1102 (MINIMUM 45 MPH)	NB-194-WP-06	3986+29		12					12																				
SPEED LIMIT TRUCK RESTRICTION	NB-194-WP-07	3989+46		20					20								17	18	35					1					
MILE MARKER 2 1/2	NB-194-TS-08	3990+23						5			1													1					
MILE MARKER 2 1/4	NB-194-TS-09	4003+42						5			1													1					
MILE MARKER 2	NB-194-TS-10	4016+44						3.75			1													1					
MILE MARKER 1 3/4	NB-194-TS-11	4029+67						5			1													1					
RUSSELL RD 1 MILE	NB-194-BS-12	4031+68								99														2	2				
E1-5P (EXIT 1)	NB-194-BS-12	4031+68		23.75																									
LAKE COUNTY A1 / RUSSELL RD / 1 MILE	NB-194-BS-12	4031+68			150							W14x30	24	24		1440					3.8								
THANK YOU FOR USING THE TOLLWAY	NB-194-BS-13	4040+59			0					144		W10x22	20	21		902					2.4			2	2				144
MILE MARKER 1 1/2	NB-194-TS-14	4042+78						5			1													1					
LEFT LANE ENDS / 1 MILE	NB-194-CL-15	4044+78			77																						26.5	16.3	
E1-5P (EXIT 1)	NB-194-BS-16	4052+40		23.75																									
RUSSELL RD NEXT RIGHT	NB-194-BS-16	4052+40								101														2	2				
LAKE COUNTY A1 / RUSSELL RD / 1/2 MILE	NB-194-BS-16	4052+40			150							W14x38	25	27		1976					4.2								
MILE MARKER 1 1/4	NB-194-TS-17	4056+00						5			1													1					
MILE MARKER 1	NB-194-TS-18	4070+00						3.75			1													1					
BRISTOL RENAISSANCE FAIR THIS EXIT	NB-194-WP-19	4070+40		20					20								17	18	35					1					
W4-3 (ADDED LANE)	NB-194-WP-20	4071+64		16					16								19		19					1					
WINTHROP HARBOR	NB-194-BS-21	4074+52			32.5					28		W8x18	19	21		720					1.4			1					
NORTH POINT MARINA	NB-194-BS-21	4074+52			58.5																								
EXIT 1 / RUSSELL RD / RIGHT LN / EXIT ONLY	NB-194-BS-22	4076+38								132														2	2				
E1-5P (EXIT 1)	NB-194-BS-22	4076+38		23.75																									
A1 / RUSSELL RD / RIGHT LANE / EXIT ONLY	NB-194-BS-22	4076+38			180							W14x38	28	32		2280					4.2								
LEFT LANE ENDS / 1/4 MILE	NB-194-TR-23	4081+75			77															123	48.0								
E1-5P (EXIT 1)	NB-194-TR-24	4081+75		23.75																									
I-94 W / US-41 N / MILWAUKEE / RUSSELL RD	NB-194-TR-24	4081+75			819.25																								
I-94 WEST / US-41 NORTH / MILWAUKEE	NB-194-TR-25	4083+11								144													1			2			
D8-1 (WEIGH STATION 1 MILE)	NB-194-TR-26	4083+11								48																			
EXIT 1 / RUSSELL RD / EXIT ONLY	NB-194-TR-27	4083+11								119																			
MILE MARKER 3/4	NB-194-TS-28	4083+78						3.75			1													1					
MILE MARKER 3/4	NB-194-LP-29	4083+78						3.75			1													1					
W4-2L (LANE ENDS)	NB-194-WP-30	4085+50		16													20		20										
E5-1a (EXIT 1)	NB-194-WP-31	4088+07			32.5					32.5							19	20	39					1					
M3-4 (WEST)	NB-194-WP-32	4089+07	4.5				1										19	20	39					1					
M1-1 (I-94)	NB-194-WP-32	4089+07	9																										
M3-1 (NORTH)	NB-194-WP-32	4089+07	4.5																										
M1-4 (US-41)	NB-194-WP-32	4089+07	9																										
D8-1 (WEIGH STATION 1 MILE)	NB-194-WP-33	4090+07			48												20	21	41										
R2-1 (SPEED LIMIT 65 MPH)	NB-194-WP-34	4091+82		20					20								19		19					1					
R13-1 (TRUCKS OVER 4 TN STOP AT WEIGH STA)	NB-194-BS-35	4093+57		0	75				0	60		W6X15	19	20		585					1.4			2					
MILE MARKER 1/2	NB-194-TS-36	4097+84						3.75			1													1					
MILE MARKER 1/2	NB-194-TS-37	4097+84						3.75			1													1					
W4-1 (MERGE)	NB-194-WP-38	4098+38							16															1					

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

FILE NAME = $FILES$	USER NAME = default	DESIGNED - TF	REVISED - 7/17/2012 JMG
		DRAWN - TF	REVISED -
	PLOT SCALE = Hs'=10' Vs'=5'	CHECKED - RGR	REVISED -
	PLOT DATE = 7/17/2012	DATE - 6/19/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING SCHEDULE

SCALE: NA | SHEET NO. 1 OF 4 SHEETS | STA. NA TO STA. NA

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1-R-1	LAKE	677	264

CONTRACT NO. 60L77

ILLINOIS FED. AID PROJECT

S:\121105_CADD\68L77 IL 173\68L77 Sheets\B168L77-sht-signing schedule.dgn