

SUMMARY OF QUANTITIES

CONSTRUCTION CODE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD		
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY	
• JS811032	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	244								244	
JS813001	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STURCTURE, 20" X 12" X 8"	EACH	1								1	
• JS813022	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	10								10	
• JS813073	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	1								1	
• JS814001	HANDHOLE, TOLLWAY	EACH	10								10	
• JS816074	UNIT DUCT, WITH 2-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (XLP-TYPE USE), 2" DIAMETER <i>COILABLE NonMETALLIC CONDUIT</i>	FOOT	891								891	
• JS816078	UNIT DUCT, WITH 4-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (XLP-TYPE USE), 2" DIAMETER <i>COILABLE NonMETALLIC CONDUIT</i>	FOOT	2,923								2,923	
• JS817211	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1,356								1,356	
• JS821002	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	10								10	
• JS836001	LIGHT POLE FOUNDATION (ROADWAY) STEEL HELIX (7 FT) OR CONCRETE	EACH	18								18	
• JS836005	LIGHT POLE FOUNDATION (ROADWAY) MEDIAN, TYPE 1	EACH	1								1	
• JS842080	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	1								1	
• JS842100	REMOVAL OF UNDERPASS LUMINAIRE	EACH	6								6	
• JS842105	POLE FOUNDATION, REMOVED	EACH	20								20	

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

• SPECIALTY ITEMS

FILE NAME = #FILES#	USER NAME = default	DESIGNED - JMC	REVISED -
		DRAWN - JMC	REVISED -
PLOT SCALE = 1/8"=1'-0"		CHECKED - RGR	REVISED -
PLOT DATE = 6/19/2012		DATE - 6/19/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 26 OF 29 SHEETS STA. NA TO STA. NA

P.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1-R-1	LAKE	677	28A
CONTRACT NO. 60L77			ILLINOIS FED. AID PROJECT	

Rev. 7-23-12

S:\1781\05_CADD\98L77_IL_173166_77_Sheets\CIBR_77-INT-130.dgn