

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD		
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY	
JT780JH1	GROOVING FOR RECESSED PAVEMENT MARKINGS, LETTERS, NUMBERS AND SYMBOLS - TYPE I	SO FT	254								254	
JT783005	WATERBLAST PAVEMENT MARKING REMOVAL WITH VACUUM RECOVERY	SO FT	28,261								28,261	
JT804001	ELECTRICAL CONNECTION TO LIGHTING CONTROLLER	EACH	1								1	
JT804002	ELECTRIC POWER CONNECTION	EACH	1								1	
JT836010	RTMS POLE FOUNDATION STEEL HELIX (12 FT.)	EACH	3								3	
JT836012	CAMERA POLE FOUNDATION STEEL HELIX (10 FT.)	EACH	2								2	
X8730571	ELECTRIC CABLE IN CONDUIT, COAXIAL	FOOT	76			76						
X8130390	JUNCTION BOX, NON-METALLIC, EMBEDDED IN STRUCTURE, 12"X10"X6"	EACH	4			4						
83050945	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2- 10 FT. DAVIT ARMS	EACH	2			2						
X0327425	RELOCATE WIRELESS INTERCONNECT (COMPLETE)	L SUM	1			1						
J5816025	UNIT DUCT, WITH 4-1C NO. 2 AND 1/C NO.4 GROUND, 600V (XLP-TYPE USE), 2" DIAMETER <i>COILABLE NONMETALLIC CONDUIT</i>	FOOT	836								836	
X0322765	RELOCATE VIDEO VEHICLE DETECTION SYSTEM	EACH	2			2						
83050965	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-15 <i>FT.</i> DAVIT ARMS	EACH	1			1						
	WOOD POLE, 60 FOOT, CLASS 4	EACH	1			1						

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



• SPECIALTY ITEMS

FILE NAME - 4FILE54	USER NAME - default	DESIGNED - JMG	REVISED -
		DRAWN - JMG	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 6/19/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 28 OF 29 SHEETS STA. NA TO STA. NA

F.A. RTE. 94	SECTION 49-1-R-1	COUNTY LAKE	TOTAL SHEETS 677	SHEET NO. 28C
CONTRACT NO. 60L77				
ILLINOIS FED. AID PROJECT				

S:\11010511\00510511\11010511.dwg 11/19/2012 11:11:11 AM