

SUMMARY OF QUANTITIES

CONSTRUCTION CODE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD			
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY		
	<i>URBAN</i>												
87301740	ELECTRIC CABLE, COMMUNICATION, NO. 22 4 PAIR <i>IN CONDUIT</i>	FOOT	942			942							
81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	96								96		
81800330	AERIAL CABLE, 3-1/C NO. 6 WITH MESSENGER WIRE	FOOT	1,452								1,452		
JS804100	ELECTRIC SERVICE INSTALLATION	EACH	2								2		
JS810824	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	81								81		
JS810837	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	96								96		
JS816033	UNIT DUCT, WITH 2-1/C NO. 6 AND 1/C NO. 8 GROUND, (600V) (XLP-TYPE USE), 2" DIA. <i>CNC</i>	FOOT	4,087								4,087		
JS830030	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	5								5		
JS830033	TEMPORARY WOOD POLE, 70 FT., CLASS 3	EACH	1								1		
JS836011	REMOVE/RELOCATE RTMS POLE FOUNDATION (ROADWAY) STEEL HELIX (12 FT.)	EACH	5								5		
JS845012	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2								2		
JT132603	POLE MOUNTED CAMERA ASSEMBLY WITH FOC AND WITHOUT WIRELESS	EACH	4								4		
JT135024	CCTV CAMERA SITE MODIFICATION	EACH	2								2		
JT135002	AC POWERED RTMS ASSEMBLY	EACH	1								1		
JT135046	TRAILER MOUNTED PORTABLE CCTV CAMERA ASSEMBLY	EACH	1								1		
JT135051	POLE MOUNTED RTMS ASSEMBLY	EACH	1								1		
JT135052	REMOVE/RELOCATE POLE MOUNTED RTMS ASSEMBLY	EACH	3								3		
JT135053	REMOVE/RELOCATE POLE MOUNTED CAMERA ASSEMBLY	EACH	3								3		
JT135061	REAIMING RTMS UNITS	L SUM	1								1		
JT836012	CAMERA POLE FOUNDATION STEEL HELIX (10 FT.)	EACH	2								2		
JT836013	REMOVE AND RELOCATE RTMS POLE	EACH	5								5		
JS810842	UNDERGROUND CONDUIT, PVC COATED GALVANIZED STEEL, 2" DIA.	FOOT	18								18		
JS810843	UNDERGROUND CONDUIT, PVC COATED GALVANIZED STEEL 3" DIA.	FOOT	43								43		
XX004339	BIKE PATH APPROACH GUARDRAIL ADJUSTMENT	FOOT	624									624 +	
20076600	<i>TRAINEES</i>	HOUR	3500	3500									
20076604	<i>TRAINEES- TRAINING PROGRAM GRADUATE</i>	HOUR	3500	3500									

+ ITEMS HAVE A 80% STATE/20% LCFPD PARTICIPATION BREAKDOWN

• SPECIALTY ITEMS
0042

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



Rev. 7-23-12

FILE NAME - #FILES#	USER NAME - default	DESIGNED - JMG	REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.S. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLDT SCALE - 1/4"=1'-0"	CHECKED - ROR	REVISIONS -	94			49-1-R-1	LAKE	677	280	
PLDT DATE - 6/19/2012	DATE - 6/19/2012	REVISIONS -	CONTRACT NO. 60177							
						SCALE: NA	SHEET NO. 29 OF 29 SHEETS	STA. NA	TO STA. NA	ILLINOIS FED. AID PROJECT