EARTHWORK SCHEDULE			STAGE 1						STAGE 2						STAGE 3					
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
MAINLINE I-94			CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
3978+89.91	TO	3979+00.00	9.68	8.23	0.00	8.23	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3979+00.00	TO	3979+20.42	28.84	24.52	0.00	24.52	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3979+20.42	TO	3980+00.00	167.01	141.96	0.00	141.96	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3980+00.00	TO	3981+00.00	236.37	200.91	0.00	200.91	21.56	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3981+00.00	TO	3982+00.00	263.20	223.72	1.56	222.17	54.07	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3982+00.00	TO	3983+00.00	262.46	223.09	11.72	211.37	62.15	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3983+00.00	TO	3984+00.00	198.22	168.49	57.24	111.25	95.41	5.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3984+00.00	TO	3985+00.00	170.31	144.77	158.00	-13.23	216.48	44.89	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3985+00.00	TO	3986+00.00	183.46	155.94	190.24	-34.30	297.69	80.78	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3986+00.00	TO	3987+00.00	195.13	165.86	153.59	12.27	293.72	81.72	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3987+00.00	TO	3988+00.00	216.76	184.25	138.48	45.76	307.46	84.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3988+00.00	TO	3989+00.00	271.19	230.51	113.63	116.88	331.09	90.83	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3989+00.00	TO	3989+50.00	125.08	106.32	60.91	45.41	117.84	29.44	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3989+50.00	TO	3990+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	106.81	90.78	72.61	18.17	118.17
3990+00.00	TO	3991+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	364.76	310.05	174.85	135.19	388.56
3991+00.00	TO	3992+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	482.74	410.33	214.76	195.57	427.02
3992+00.00	TO	3993+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	338.07	287.36	163.41	123.96	251.57
3993+00.00	TO	3994+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	227.67	193.52	50.67	142.85	42.09
3994+00.00	TO	3995+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	239.89	203.91	119.24	84.66	154.81
3995+00.00	TO	3996+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	218.69	185.88	221.76	-35.88	301.17
3996+00.00	TO	3997+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	272.07	231.26	207.74	23.52	337.74
3997+00.00	TO	3998+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	287.83	244.66	201.24	43.42	311.11
3998+00.00	TO	3999+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	220.59	187.50	192.20	-4.70	263.70
3999+00.00	TO	4000+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	182.91	155.47	204.33	-48.86	289.74
4000+00.00	TO	4001+00.00	179.59	152.65	223.94	-71.29	300.44	81.52	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4001+00.00	TO	4002+00.00	175.63	149.29	257.63	-108.34	304.67	83.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4002+00.00	TO	4003+00.00	172.91	146.97	254.04	-107.07	267.94	70.39	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4003+00.00	TO	4004+00.00	178.13	151.41	250.54	-99.13	249.89	64.06	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4004+00.00	TO	4005+00.00	166.04	141.13	270.78	-129.65	253.31	65.24	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4005+00.00	TO	4006+00.00	162.15	137.83	283.33	-145.51	245.50	62.65	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4006+00.00	TO	4007+00.00	161.41	137.20	309.69	-172.49	278.30	73.54	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4007+00.00	TO	4008+00.00	156.50	133.03	308.72	-175.70	273.15	71.65	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4008+00.00	TO	4009+00.00	160.69	136.58	316.11	-179.53	237.98	59.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4009+00.00	TO	4010+00.00	171.44	145.73	317.37	-171.64	248.30	63.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4010+00.00	TO	4011+00.00	175.85	149.47	289.00	-139.53	278.31	72.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4011+00.00	TO	4012+00.00	187.52	159.39	288.57	-129.18	320.24	86.39	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4012+00.00	TO	4013+00.00	191.94	163.15	298.69	-135.53	323.65	87.44	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4013+00.00	TO	4014+00.00	175.87	149.49	322.54	-173.05	321.37	86.91	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4014+00.00	TO	4015+00.00	174.87	148.64	347.81	-199.18	339.96	93.33	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4015+00.00	TO	4016+00.00	179.44	152.53	325.35	-172.82	327.52	89.65	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4016+00.00	TO	4017+00.00	182.56	155.17	301.00	-145.83	291.61	78.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4017+00.00	TO	4018+00.00	168.00	142.80	294.52	-151.72	269.11	70.46	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4018+00.00	TO	4019+00.00	177.93	151.24	290.20	-138.97	293.94	78.70	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4019+00.00	TO	4020+00.00	187.37	159.26	289.93	-130.66	281.39	74.43	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4020+00.00	TO	4021+00.00	172.17	146.34	346.44	-200.10	272.33	71.37	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4021+00.00	TO	4022+00.00	184.67	156.97	436.78	-279.81	315.09	85.54	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4022+00.00	TO	4023+00.00	188.96	160.62	409.15	-248.53	301.94	81.17	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4023+00.00	TO	4024+00.00	186.78	158.76	257.26	-98.50	225.76	55.94	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4024+00.00	TO	4025+00.00	187.02	158.97	140.83	18.13	143.50	28.54	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4025+00.00	TO	4026+00.00	181.26	154.07	129.50	24.57	117.39	19.80	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4026+00.00	TO	4027+00.00	173.78	147.71	153.39	-5.68	144.11	28.76	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4027+00.00	TO	4028+00.00	175.50	149.18	182.78	-33.60	173.02	38.41	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4028+00.00	TO	4029+00.00	184.11	156.49	273.31	-116.82	196.80	46.15	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4029+00.00	TO	4030+00.00	190.28	161.74	299.70	-137.97	205.70	49.11	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4030+00.00	TO	4031+00.00	187.80	159.63	357.70	-198.08	252.28	64.70	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4031+00.00	TO	4032+00.00	183.48	155.96	451.04	-295.08	299.93	79.33	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4032+00.00	TO	4033+00.00	177.13	150.56	441.76	-291.20	291.31	75.81	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4033+00.00	TO	4034+00.00	177.22	150.64	360.33	-209.69	248.91	62.57	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4034+00.00	TO	4035+00.00	181.76	154.50	263.11	-108.62	232.26	57.30	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4035+00.00	TO	4036+00.00	185.46	157.64	222.63	-64.99	248.15	64.20	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4036+00.00	TO	4037+00.00	209.98	178.48	227.39	-48.90	271.31	73.11	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4037+00.00	TO	4038+00.00	235.70	200.35	311.78	-111.43	333.44	92.63	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4038+00.00	TO	4039+00.00	253.11	215.14	375.19	-160.04	336.46	92.07	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4039+00.00	TO	4040+00.00	286.70	243.70	411.48	-167.78	316.96	83.93	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4040+00.00	TO	4041+00.00	328.54	279.26	423.02	-143.76	362.65	97.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4041+00.00	TO	4042+00.00	340.06	289.05	405.22	-116.18	355.87	93.96	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4042+00.00	TO	4043+00.00	400.15	340.13	364.94	-24.82	316.56	79.31	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4043+00.00	TO	4044+00.00	438.87	373.04	340.24	32.80	357.11	91.30	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4044+00.00	TO	4045+00.00	348.00	295.80	351.02	-55.22	355.04	89.15	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4045+00.00	TO	4046+00.00	290.46	246.89	306.80	-59.90	301.06	70.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

FILE NAME = $FILES$	USER NAME = default	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = H:1"=10' V:1"=5'	CHECKED - RGR	REVISED -
	PLOT DATE = 6/20/2012	DATE - 6/19/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CIVIL SCHEDULE

SCALE: NA | SHEET NO. 2 OF 8 SHEETS | STA. NA TO STA. NA

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1-R-1	LAKE	677	45

CONTRACT NO. 60L77

ILLINOIS FED. AID PROJECT

S:\110105.CADD\60L77 IL 173\60L77 Sheets\D160L77-sht-civil schedule.dgn