

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD			
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY		
			<i>URBAN</i>										
X0325201	SHOULDER RUMBLE STRIP REMOVAL	SO YD	8,875	2,274					6,601				
X0325734	SLOTTED DRAIN REMOVAL	FOOT	204					204					
X0326337	DRAINAGE CONTROL STRUCTURE	EACH	1	1									
X0327211	RELOCATE SWITCH	EACH	1			1							
X0327392	WOOD POLE, 60 FT, CLASS 4	EACH	1			1							
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	7	7									
X0322936	<i>REMOVE EXISTING FLARED END SECTION</i>	EACH	80	25				55					
X4811410	AGGREGATE SHOULDERS SPECIAL, TYPE C	TON	229					229					
△ X5420624	PIPE CULVERTS TO BE CLEANED 24"	FOOT	126	126									
△ X5420630	PIPE CULVERTS TO BE CLEANED 30"	FOOT	406	205				201					
△ X5420636	PIPE CULVERTS TO BE CLEANED 36"	FOOT	358	270				88					
△ X5420648	PIPE CULVERTS TO BE CLEANED 48"	FOOT	338	338									
△ X5420654	PIPE CULVERTS TO BE CLEANED 54"	FOOT	681	112				569					
X5428836	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36" (SPECIAL)	CU YD	5					5					

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



• SPECIALTY ITEMS
△ 100% STATE

FILE NAME - 4FILES*	USER NAME - default	DESIGNED - JMG	REVISED -
		DRAWN - JMG	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 6/19/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 20 OF 29 SHEETS STA. NA TO STA. NA

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1-R-1	LAKE	677	23
CONTRACT NO. 60L77			ILLINOIS FED. AID PROJECT	

S:\1181\25.CADD\ER.77 IL 173462.77 Sheet\0160L77-23-100.dgn