CIVIL ENGINEERING CONSULTANTS
RVA
Regina Webster & Associates, Inc.
8619 W. Bryn Mawr Ave., Suite 602
Chicago, IL 60631-3551
773-283-2600 Fax: 773-283-2602
www.RWAengineers.com

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35
				TRAFFIC SIGNAL																																			
				0021																																			
				URBAN																																			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																																	
67100100	MOBILIZATION	L SUM	1	1																																	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																																	
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	60			10	10															10	10	10									10				
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	80	9	4	5	6	2	1	3	1	3	2	1	3	2	2	1	1	1	1	1	7	6	1	1	1	1	1	1	1	1	1	7	1			1
85700200	FULL-ACTUATED CONTROLLER AND TYPE 1V CABINET	EACH	1									1																									
86400100	TRANSCEIVER - FIBER OPTIC	EACH	2							1														1													
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	5	4			1																														
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	14	2												1	1	3	2			3		2													
87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	3													2	1																				
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	31	7		2										1	5	2	2	1		2		1	4		4									
87900200	DRILL EXISTING HANDHOLE	EACH	6			1	1														1	1	1										1				
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	41	4		9										3	3	6	4			3		7	2											
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	12	1		1										1	4	2	2			1														

Rev.

FILE NAME = N:\Projects3\12024\Design\CAD\Sheet Files\12-002 Sheets NC Lake Co\60T42 LAKE_S003.dgn	USER NAME = $USER$	DESIGNED - DW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (SHEET 3 OF 6)
		DRAWN - JDH	REVISED -		
	PLOT SCALE = $SCALE$	CHECKED - KMM	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.
	PLOT DATE = 5/16/2012	DATE -	REVISED -		

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2012-004 I	LAKE	97	6
		CONTRACT NO. 60T42		
	ILLINOIS FED. AID PROJECT			