

SUMMARY OF QUANTITIES

| SP | CODE NO. | ITEM   | UNIT  | TOTAL QUANTITY | CONSTRUCTION CODE                   |  |
|----|----------|--|-------|----------------|-------------------------------------|--|
|    |          |  |       |                | CMAQ                                |  |
|    |          |  |       |                | 100% VILLAGE STREETScape 0031 URBAN | 80% FED 20% VILLAGE ROADWAY 0021 URBAN |
|    | 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER)                | UNIT  | 235            |                                     | 235                                    |
|    | 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER)                | UNIT  | 58             |                                     | 58                                     |
|    | 20101000 | TEMPORARY FENCE                                      | FOOT  | 175            |                                     | 175                                    |
| A  | 20101200 | TREE ROOT PRUNING                                    | EACH  | 6              |                                     | 6                                      |
| A  | 20101400 | NITROGEN FERTILIZER NUTRIENT                         | POUND | 53             |                                     | 53                                     |
| A  | 20101500 | PHOSPHORUS FERTILIZER NUTRIENT                       | POUND | 53             |                                     | 53                                     |
| A  | 20101600 | POTASSIUM FERTILIZER NUTRIENT                        | POUND | 53             |                                     | 53                                     |
|    | 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL          | CU YD | 1363           |                                     | 1363                                   |
| A  | 21101615 | TOPSOIL FURNISH AND PLACE, 4"                        | SQ YD | 5024           |                                     | 5024                                   |
| A  | 25200110 | SODDING, SALT TOLERANT                               | SQ YD | 5024           |                                     | 5024                                   |
| A  | 25200200 | SUPPLEMENTAL WATERING                                | UNIT  | 38             |                                     | 38                                     |
|    | 28000610 | INLET FILTERS  | EACH  | 27             |                                     | 27                                     |
|    | 35101500 | AGGREGATE BASE COURSE, TYPE B                        | CU YD | 683            |                                     | 683                                    |
|    | 35501308 | HOT-MIX ASPHALT BASE COURSE, 6"                      | SQ YD | 3              |                                     | 3                                      |
|    | 35501316 | HOT-MIX ASPHALT BASE COURSE, 8"                      | SQ YD | 21             |                                     | 21                                     |
|    | 40201000 | AGGREGATE FOR TEMPORARY ACCESS                       | TON   | 24             |                                     | 24                                     |
|    | 40603336 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50         | TON   | 2              |                                     | 2                                      |
|    | 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH   | SQ YD | 769            |                                     | 769                                    |
|    | 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH             | SQ FT | 31254          |                                     | 31254                                  |
|    | 42400400 | PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH             | SQ FT | 5543           |                                     | 5543                                   |
|    | 42400600 | DETECTABLE WARNINGS                                  | SQ FT | 834            |                                     | 834                                    |
|    | 44000200 | DRIVEWAY PAVEMENT REMOVAL                            | SQ YD | 1410           |                                     | 1410                                   |
|    | 44000500 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL         | FOOT  | 851            |                                     | 851                                    |
|    | 44000600 | SIDEWALK REMOVAL                                     | SQ FT | 17992          |                                     | 17992                                  |
|    | 60256500 | MANHOLES TO BE ADJUSTED                              | EACH  | 5              |                                     | 5                                      |
|    | 60603800 | COMBINATION CONCRETE CURB & GUTTER, TYPE B-8-12      | FOOT  | 793            |                                     | 793                                    |
|    | 63200310 | GUARDRAIL REMOVAL                                    | FOOT  | 14             |                                     | 14                                     |
|    | 63700175 | CONCRETE BARRIER, SINGLE FACE, 42-INCH HEIGHT        | FOOT  | 290            |                                     | 290                                    |
|    | 67100100 | MOBILIZATION   | L SUM | 1              |                                     | 1                                      |
|    | 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601      | L SUM | 1              |                                     | 1                                      |
|    | 70102632 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701602      | L SUM | 1              |                                     | 1                                      |
|    | 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701      | L SUM | 1              |                                     | 1                                      |
|    | 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801      | L SUM | 1              |                                     | 1                                      |
| A  | 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 22             |                                     | 22                                     |
| A  | 66900200 | NON-SPECIAL WASTE DISPOSAL                           | SQ YD | 2000           |                                     | 2000                                   |
| A  | 66900400 | SPECIAL WASTE BILLS AND REPORTS                      | L SUM | 1              |                                     | 1                                      |
| A  | 66900500 | SOIL DISPOSAL ANALYSIS                               | EACH  | 5              |                                     | 5                                      |
| A  | 20076500 | TRAINEES TRAINING PROGRAM GRADUATE                   | Hour  | 500            |                                     | 500                                    |

| SP | CODE NO. | ITEM  | UNIT  | TOTAL QUANTITY | CONSTRUCTION CODE                   |  |
|----|----------|---|-------|----------------|-------------------------------------|--|
|    |          |   |       |                | CMAQ                                |  |
|    |          |   |       |                | 100% VILLAGE STREETScape 0031 URBAN | 80% FED 20% VILLAGE ROADWAY 0021 URBAN |
| A  | 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6"  | FOOT  | 534            |                                     | 534                                    |
| A  | 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24"   | FOOT  | 16             |                                     | 16                                     |
| A  | B2003116 | TREE, MALUS CORALBURST, (CORALBURST CRABAPPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED               | EACH  | 18             |                                     | 18                                     |
| A  | C2009918 | SHRUB, SPIREA X BUMALDA GOLDFLAME (GOLD FLAME BUMALDA SPIREA), 18" HEIGHT CONTAINER                       | EACH  | 5              |                                     | 5                                      |
| A  | C2012824 | SHRUB VIBURNUM TRILOBUM BAILEY COMPACT (BAILEY COMPACT AMERICAN CRANBERRY VIBURNUM), 2' HEIGHT, CONTAINER | EACH  | 10             |                                     | 10                                     |
| A  | C2C15781 | SHRUB, SPIREA JAPONICA NEON FLASH (NEON FLASH JAPANESE SPIREA), 18" HEIGHT, 5 GALLON CONTAINER            | EACH  | 11             |                                     | 11                                     |
| A  | K0012990 | PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT   | UNIT  | 24             |                                     | 24                                     |
|    | K0020830 | SHRUB REMOVAL   | EACH  | 57             | 57                                  |  |
| A  | X0324815 | RELOCATE LIGHTING UNITS AND POLES   | EACH  | 2              | 2                                   |  |
| A  | X000959  | TRASH RECEPTACLES   | EACH  | 4              | 4                                   |  |
| A  | X002133  | RELOCATE SIGN AND BASE  | EACH  | 2              |                                     | 2                                      |
|    | X0006428 | SIDEWALK SPECIAL  | SQ FT | 126            |                                     | 126                                    |
|    | X006898  | STAMPED COLORED PORTLAND CEMENT CONCRETE  | SQ FT | 495            | 495                                 |  |
| A  | 20003850 | BENCHES   | EACH  | 4              | 4                                   |  |
|    | 20013798 | CONSTRUCTION LAYOUT   | L SUM | 1              |                                     | 1                                      |
|    | 20030850 | TEMPORARY INFORMATION SIGNING   | SQ FT | 27             |                                     | 27                                     |
|    | 20052000 | SAW CUTTING   | FOOT  | 1588           |                                     | 1588                                   |
|    | 20076500 | TRAINEES  | Hour  | 500            |                                     | 500                                    |

Construction Type Code 0042  
A SPECIALTY ITEMS

PLAN SHEET NO. 343  
DATE 08-16-2010  
DRAWN BY TWC  
CHECKED BY AWB  
DATE 8-16-2010

PROFILE SHEET NO. 343  
DATE 08-16-2010  
DRAWN BY TWC  
CHECKED BY AWB  
DATE 8-16-2010