

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				HPP FUNDS					
				ATKINSON ROAD & IL ROUTE 120		IL ROUTE 137		-	
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL
		ROADWAY NEW CON. 0001	ROADWAY RECON. 0004	SAFETY 0021	ROADWAY RECON. 0004	SAFETY 0021	TRAINEES 0042		
* X0325134	WIRELESS INTERCONNECT (COMPLETE)	EACH	1	0	0	0	0	1	0
X0326358	STORM WATER TREATMENT SYSTEM	EACH	3	3	0	0	0	0	0
* X0326884	TRAFFIC SIGNAL WOOD POLE, 45 FT, CLASS 5	EACH	5	0	0	5	0	0	0
X0327036	BIKE PATH REMOVAL	SO YD	631	0	631	0	0	0	0
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	500	500	0	0	0	0	0
* X2501800	SEEDING, CLASS 4 (MODIFIED)	ACRE	1.42	1.42	0	0	0	0	0
* X2501820	SEEDING, CLASS 5 (MODIFIED)	ACRE	1.42	1.42	0	0	0	0	0
* X2511630	EROSION CONTROL BLANKET (SPECIAL)	SO YD	712	712	0	0	0	0	0
* XX008290	TEMPORARY DITCH CHECKS (SPECIAL)	EACH	114	82	4	0	28	0	0
X6020096	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1	0	0	0	0	0
* X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	12	3	7	0	2	0	0
* X6026051	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	1	1	0	0	0	0	0
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0	0	1	0	0	0
* X8620200	UNINTERRUPTIBLE POWER SUPPLY SPECIAL	EACH	2	0	0	1	0	1	0
* X8800025	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, SPAN WIRE MOUNTED	EACH	14	0	0	1	0	13	0
* X8800041	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, SPAN WIRE MOUNTED	EACH	4	0	0	0	0	4	0
* X8800046	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, SPAN WIRE MOUNTED	EACH	14	0	0	14	0	0	0
XX003404	TEMPORARY PAVEMENT, 8"	SO YD	907	907	0	0	0	0	0
* XX004046	AERIAL CABLE REMOVAL	FOOT	7,980	0	0	3,865	0	4,115	0
XX006658	FLOCCULATION LOGS	EACH	154	122	4	0	28	0	0
XX006659	FLOCCULATION POWDER	POUND	241	199	12	0	30	0	0
XX006722	TEMPORARY AGGREGATE BERM-COURSE AGGREGATE	TON	210	159	0	0	51	0	0
XX006723	TEMPORARY AGGREGATE BERM-RIPRAP	TON	245	185	0	0	60	0	0
XX006731	LEVEL SPREADER	EACH	1	1	0	0	0	0	0
Z007604	TRAINEES TRAINING PROGRAM GRADUATE	Hour	1,000						1,000
XX008812	STORM SEWER (WATER MAIN REQUIREMENTS), EQUIVALENT ROUND-SIZE 18 INCH	FOOT	114	0	114	0	0	0	0

* = SPECIALTY ITEM



USER NAME: m.jp
 FILE NAME: A2189-ah-SC337.dgn
 PLOT SCALE: 1:2000 1/2 in.
 PLOT DATE: 3/6/2012

DESIGNED: JSM
 DRAWN: JSM
 CHECKED: DNM
 DATE: 02/06/12

REVISED: 7/26/12
 REVISED: -
 REVISED: -
 REVISED: -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: XNTSX SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
198	00-00045-00-PV	LAKE	195	10
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63640	