

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				HPP FUNDS					
				ATKINSON ROAD & IL ROUTE 120		IL ROUTE 137		-	
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL
				ROADWAY NEW CON. 0001	ROADWAY RECON. 0004	SAFETY 0021	ROADWAY RECON. 0004	SAFETY 0021	TRAINEES 0042
60500060	REMOVING INLETS	EACH	1	0	1	0	0	0	0
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	8	0	8	0	0	0	0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	218	198	0	0	20	0	0
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	6,354	4,692	1,369	0	293	0	0
60605300	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (MODIFIED)	FOOT	69	0	0	0	69	0	0
63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	313	0	0	313	0	0	0
63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	2	0	0	2	0	0	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	0	0	0	0	0
67100100	MOBILIZATION	L SUM	1	1	0	0	0	0	0
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1,050	0	0	0	0	1,050	0
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	0	0	0	0	1	0
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	0	0	0	0	2	0
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	20	0	0	10	0	10	0
70300100	SHORT TERM PAVEMENT MARKING	FOOT	6,728	0	0	5,028	0	1,700	0
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	286	0	0	286	0	0	0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16,343	0	0	11,315	0	5,028	0
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1,179	0	0	318	0	861	0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9,838	0	0	7,551	0	2,287	0
72000100	SIGN PANEL - TYPE 1	SQ FT	222	0	0	133	0	89	0
72000200	SIGN PANEL - TYPE 2	SQ FT	93	0	0	93	0	0	0
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	8	0	0	5	0	3	0
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	26	0	0	8	0	18	0
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	693	0	0	456	0	237	0
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	935	0	0	728	0	207	0
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	30,512	0	0	20,062	0	10,450	0
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4,375	0	0	3,356	0	1,019	0
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	173	0	0	0	0	173	0
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,125	0	0	1,498	0	627	0
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	364	0	0	276	0	88	0
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	254	0	0	94	0	160	0
78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	0	0	10	0	0	0
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	0	0	2	0	0	0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	6,015	0	0	4,053	0	1,962	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	176	0	0	68	0	108	0

* = SPECIALTY ITEM



USER NAME = mjg
 FILE NAME = ...2189...shd...dgn
 PLOT SCALE = 1:8000
 PLOT DATE = 5/16/2012

DESIGNED - JSM
 DRAWN - JSM
 CHECKED - DNM
 DATE - 02/06/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: 2NTS% SHEET NO. OF SHEETS STA. TO STA.

F.A.U.:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
198	00-00045-00-PV	LAKE	195	7
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63640	