

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				HPP FUNDS					
				ATKINSON ROAD & IL ROUTE 120			IL ROUTE 137		
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL
			ROADWAY NEW CON. 0001	ROADWAY RECON. 0004	SAFETY 0021	ROADWAY RECON. 0004	SAFETY 0021	TRAINEES 0042	
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	6	0	0	0	0	6	0
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	477	0	0	0	0	477	0
* 88700200	LIGHT DETECTOR	EACH	6	0	0	2	0	4	0
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	2	0	0	1	0	1	0
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	4	0	0	4	0	0	0
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2,344	0	0	490	0	1,854	0
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2	0	0	1	0	1	0
* 89502380	REMOVE EXISTING HANDHOLE	EACH	5	0	0	4	0	1	0
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1	0	0	1	0	0	0
Z0013796	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	445	445	0	0	0	0	0
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	0	0	0	0	0
Z0019600	DUST CONTROL WATERING	UNIT	500	500	0	0	0	0	0
Z0023000	FIELD TILE INSPECTION STRUCTURE	EACH	3	3	0	0	0	0	0
Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE (NLC FILTER CLEANING)	EACH	92	64	28	0	0	0	0
Z0023206	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	5,297	2,528	382	0	2,387	0	0
* Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1	0	0	0	0	1	0
* Z0033072	VIDEO VEHICLE DETECTION SYSTEM	EACH	1	0	0	1	0	0	0
X0324140	POROUS GRANULAR EMBANKMENT, SUBGRADE, SPECIAL	CU YD	4,888	4,597	0	0	291	0	0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0	0	0	0	1	0
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	286	129	157	0	0	0	0
Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	435	290	145	0	0	0	0
Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	75	75	0	0	0	0	0
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1,285	1,285	0	0	0	0	0
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	0	0	1	0	0	0
Z0076600	TRAINEES	HOUR	1,000	0	0	0	0	0	1,000
* A2005024	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 3" CALIPER, BALLED AND BURLAPPED	EACH	11	11	0	0	0	0	0
* A2006420	TREE, QUERCUS ALBA (WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3	3	0	0	0	0	0
* B2004484	TREE, PYRUS CALLERYANA AUTUMN BLAZE (AUTUMN BLAZE CALLERY PEAR), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	12	12	0	0	0	0	0
* B2005532	TREE, PYRUS CALLERYANA ARISTOCRAT (ARISTOCRAT CALLERY PEAR), 4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10	10	0	0	0	0	0
* B2005726	TREE, PYRUS CALLERYANA CHANTICLEER (CHANTICLEER CALLERY PEAR), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	21	21	0	0	0	0	0
X0322924	RETAINING WALL REMOVAL	SQ FT	45	0	0	0	0	45	0
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	3	3	0	0	0	0	0
* X0424085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	2,054	0	0	341	0	1,713	0
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	112	112	0	0	0	0	0

\* = SPECIALTY ITEM