



LEGEND

- TREE REMOVAL (SIZE AS NOTED)
- HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"
- PAVEMENT REMOVAL OR DRIVEWAY PAVEMENT REMOVAL
- REMOVING MANHOLES, CATCH BASINS, OR INLETS
- PIPE CULVERT OR STORM SEWER REMOVAL
- RELOCATE EXISTING LIGHTING UNIT AND REMOVAL OF POLE FOUNDATION
- COMBINATION CURB AND GUTTER REMOVAL
- REMOVE SIGN PANEL ASSEMBLY OR RELOCATE SIGN PANEL ASSEMBLY
- FIRE HYDRANT AND VALVE TO BE MOVED

NOTES:

1. SEE ALIGNMENT, TIES, AND RIGHT-OF-WAY SHEETS FOR PROPOSED R.O.W. AND EASEMENT LOCATIONS, STATION EQUATIONS, AND CURVE INFORMATION.
2. FOR TRAFFIC SIGNAL REMOVAL AND RELOCATION PLANS, SEE TRAFFIC SIGNAL SHEETS.
3. FOR SIGN REMOVAL AND RELOCATION PLANS, SEE PAVEMENT MARKING AND SIGN SHEETS.

ATKINSON ROAD

	USER NAME - eds FILE NAME - \\ns6-removals\2109-sh-1-en07 PLOT SCALE - 20.0000' / 1" = 20' PLOT DATE - 2/2/2012	DESIGNED - JSM DRAWN - JSM CHECKED - DNM DATE - 02/06/12	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ATKINSON ROAD REMOVAL PLAN	F.A.U. RTE. - 198 SECTION - 00-00045-00-PV COUNTY - LAKE TOTAL SHEET SHEETS - NO. 195 27 CONTRACT NO. 63640
	SCALE: 1" = 20' SHEET NO. 7 OF 13 SHEETS STA. 465+50 TO STA. 466+69				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	