



WP-100
PK NAIL
N 2,015,278.00
E 1,028,901.42
ELEV 758.73

POT Sta. 10+00.00
N 2,015,278.04
E 1,028,902.48

WP-101
N 2,015,314.50
E 1,029,268.90
ELEV 757.96

RM-208-4 (FEMA MAP 17097C0208 F)
CUT SQUARE ON NE WINGWALL
N 2,015,346.60
E 1,029,287.27
ELEV 758.52 (SEE NOTE)

WP-103
PK NAIL
N 2,015,355.94
E 1,029,599.73
ELEV 756.66

POT Sta. 17+65.67
N 2,015,379.92
E 1,029,661.33

VERTICAL DATUM NOTE:
ELEVATION IS BASED ON THE NATIONAL GEODETIC VERTICAL DATUM OF 1929, AND HAS BEEN ADJUSTED BY +0.21 FEET TO CONVERT TO NORTH AMERICAN VERTICAL DATUM OF 1988.

McDonough Associates Inc.
 Engineers / Architects
 180 North Stearns Ave., Chicago, Illinois 60601

FILE NAME =	USER NAME = jehrhart
10030-SHT-ATB01.dgn	

DESIGNED - MJT	REVISED -
DRAWN - MJT	REVISED -
CHECKED - E.JG	REVISED -
DATE - 05/14/12	REVISED -

DESIGNED - MJT	REVISED -
DRAWN - MJT	REVISED -
CHECKED - E.JG	REVISED -
DATE - 05/14/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ALIGNMENT, TIES, AND BENCHMARKS
 SCALE: 1"=30' SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	09-00010-00-BR	LAKE	41	9
AT-1			CONTRACT NO. 63716	
ILLINOIS FED. AID PROJECT				