

SUMMARY OF QUANTITIES

SPECIAL PROVISION	PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
					0005	
	25200110	SODDING, SALT TOLERANT	SQ YD	15	15	
	40600200	BITUMINOUS MATERIAL (PRIME COAT)	TON	5	5	
	40600300	AGGREGATE (PRIME COAT)	TON	5	5	
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	60	60	
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	500	500	
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	300	300	
	42300100	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 5 INCH	SQ YD	75	75	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	1,353	1,353	
	42400800	DETECTABLE WARNINGS	SQ FT	25	25	
	44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	3,500	3,500	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	75	75	
	44000800	SIDEWALK REMOVAL	SQ FT	625	625	

SPECIAL PROVISION	PAY ITEM	DESCRIPTION	UNIT	CONST. CODE I-005 TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
					0005	
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2	
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2	
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	
	67100100	MOBILIZATION	L SUM	1	1	
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	152	152	
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	64	64	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	36	36	
X	X3580300	AGGREGATE BASE REPAIR (SPECIAL)	TON	170	170	
X	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	6	6	
X	X6038310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	8	
X	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	500	

* SPECIALTY ITEMS