

DATE	
BY	
NO.	
DATE	
BY	
NO.	
DATE	
BY	
NO.	

DATE	
BY	
NO.	
DATE	
BY	
NO.	

CODE NUMBER	PAY ITEM	UNIT	ROADWAY 80% FEDERAL 20% LOCAL 0005
40800100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2542
40600300	AGGREGATE (PRIME COAT)	TON	64
40800625	LEVELING BINDER (MACHINE METHOD), N50	TON	890
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	623
40803310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1329
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	6
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	15564
44201696	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	1185
46101200	AGGREGATE SHOULDERS, TYPE B	TON	353
67100100	MOBILIZATION	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1950
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	217
△	78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	32
△	78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16335
△	78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1380
△	78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	157
△	78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	69
△	78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	30
△	78100100 RAISED REFLECTIVE PAVEMENT MARKER	EACH	80
	78300100 PAVEMENT MARKING REMOVAL	SQ FT	230
	78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	80
△ *	88600600 DETECTOR LOOP REPLACEMENT	FOOT	50
*	X4401198 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ FT	217
*	X7010216 TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1

△ INDICATES SPECIALTY ITEM.
* SEE SPECIAL PROVISIONS.



HRGreen.com
Since Professional Design Firm
104-00102

USER NAME	- H.Feller
PLOT SCALE	* 1/8"=1'-0"
PLOT DATE	- 5/21/2012
FILE NAME	- 208_surr01.dwg

DESIGNED	- JMR
CHECKED	- JS
DATE	- 4/30/12

REVISED	-
REVISED	-
REVISED	-
REVISED	-

VILLAGE OF OSWEGO

SUMMARY OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3797	11-00043-00-RS	KENDALE	9	3
CONTRACT NO. 87596				