# TOTAL SHEETS = 37 CHICAGO EXECUTIVE AIRPORT WHEELING/PROSPECT HEIGHTS, ILLINOIS CONSTRUCTION PLANS FOR

# CHICAGO EXECUTIVE AIRPORT

# **REHABILITATE RUNWAY 12/30** AND RUNWAY LIGHTING

# ILLINOIS PROJECT: PWK-4552 S.B.G. PROJECT: 3-17-SBGP-133/139/TBD

JUNE 8, 2018



SITE PLAN





THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE ACTUAL LOCATIONS OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES OF HIS OPERATIONAL PLANS, OBTAIN FROM RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR EACULTIES AND THE WORKING SCHEDING OF THE THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION AND THE ONE-CALL NOTICE SYSTEM. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH UTILITY OR SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 811







LOCATION MAP

LAKE FOREST

MORTON GROVE

NORRIDGI

DEERFIELD

NORTHEROOK

(21)

WHEELING

8 PROSPECT

ELK GROVE VILLAGE

WOOD DAI

HIGHLAND

 $\mathbb{N}$ 

PROJECT

LOCATION

16290-04\COVER.DWG



PA061

PROJECT INFORMATION CONTRACTOR: RESIDENT ENGINEER: ORIGINAL CONTRACT AMOUNT: FINAL CONSTRUCTION COST: IDOT LETTING DATE: IDOT AWARD DATE: NOTICE TO PROCEED: START OF CONSTRUCTION SUBSTANTIAL COMPLETION:

LOCAL AGENCY CONTACT INFORMATION VILLAGE OF WHEELING - 847.459.2600 CITY OF PROSPECT HEIGHTS - 847.398.6070

ENGINEER'S PROJECT PERMIT LOG NPDES # FAA AIRSPACE # CCDD LPC-663 DATED 11/16/12 MWRDGC PERMIT # 03-246 & RL 09-063 VILLAGE APP FOR CONSTRUCTION PERMIT # VILLAGE FLOODPLAIN PERMIT # CONTRACTORS REGISTRATION WITH VILLAGE VILLAGE SITE ALTERATION PERMIT # CITY APPLICATION FOR PERMIT # CITY FLOODPLAIN PERMIT # CITY SITE GRADING PERMIT # CONTRACTOR'S REGISTRATION WITH CITY

	INDEX TO SHEETS
Sheet Number	DESCRIPTION
1	COVER SHEET
2	INDEX TO SHEETS, SUMMARY OF QUANTITIES AND GENERAL NOTES
3	SITE PLAN AND PROJECT CONTROL PLAN
4	SEQUENCE OF CONSTRUCTION - SHEET 1
5	SEQUENCE OF CONSTRUCTION - SHEET 2
6	SEQUENCE OF CONSTRUCTION - SHEET 3
7	SEQUENCE OF CONSTRUCTION - SHEET 4
8	SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS - SHEET 1
9	SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS - SHEET 2
10	STORMWATER POLLUTION PREVENTION PLAN
11	STORMWATER POLLUTION PREVENTION PLAN NOTES AND DETAILS - SHEET 1
12	STORMWATER POLLUTION PREVENTION PLAN NOTES AND DETAILS - SHEET 2
13	TYPICAL SECTIONS
14	EXISTING CONDITIONS AND PROPOSED REMOVALS - SHEET 1
15	EXISTING CONDITIONS AND PROPOSED REMOVALS - SHEET 2
16	RUNWAY 12/30 PLAN AND PROFILE - SHEET 1
17	RUNWAY 12/30 PLAN AND PROFILE - SHEET 2
18	RUNWAY 12/30 PLAN AND PROFILE - SHEET 3
19	RUNWAY 12/30 PLAN AND PROFILE - SHEET 4
20	PAVEMENT REHABILITATION DETAILS
21	PAVEMENT JOINT SEALING DETAILS
22	MISCELLANOUS DETAILS
23	INTERSECTION GRADING PLAN - TAXIWAYS A AND E1
24	INTERSECTION GRADING PLAN - TAXIWAY B AND K
25	INTERSECTION GRADING PLAN - TAXIWAYS D, Y AND Z
26	BITUMINOUS MILLING DEPTH TABLE - RUNWAY 12/30
27	PAVEMENT MARKING - SHEET 1
28	PAVEMENT MARKING - SHEET 2
29	PAVEMENT MARKING DETAILS
30	ELECTRICAL IMPROVEMENTS - SHEET 1
31	ELECTRICAL IMPROVEMENTS - SHEET 2
32	RUNWAY 12/30 HOMERUN PLAN
33	ELECTRICAL DETAILS - SHEET 1
34	ELECTRICAL DETAILS - SHEET 2
35	ELECTRICAL DETAILS - SHEET 3
36	VAULT IMPROVEMENTS
37	GROOVING PLAN AND DETAILS

# NOTES

- 1. SPECIAL ATTENTION IS NECESSARY WHEN WORKING NEAR FAA POWER AND CONTROL CABLES. ANY FAA UTILITY THAT IS DAMAGED OR CUT DURING CONSTRUCTION SHALL BE REPAIRED IMMEDIATELY. FAA REQUIRES THAT ANY DAMAGED CABLE BE REPLACED IN ITS ENTIRETY, FROM POWER/CONTROL SOURCE TO THE EQUIPMENT/SERVICE. SPLICES OF ANY KIND WILL NOT BE PERMITTED. EXPOSURES OF ANY FAA CABLES MUST BE DONE BY HAND DIGGING OR HYDRO-EXCAVATION. NO ADDITIONAL COMPENSATION WILL BE MADE FOR LOCATING, REPLACEMENT OR REPAIR OF FAA FACILITIES OR CABLES BUT, SHALL BE INCIDENTAL TO THE CONTRACT.
- 2. WHEN FAA CABLES ARE REQUIRED TO BE LOCATED, OR THE CONTRACTOR IS PLANNING ON WORKING ON OR AROUND FAA CABLES, CONDUITS OR EQUIPMENT, A 10 WORKING DAY ADVANCED NOTICE SHALL BE GIVEN TO THE FAA BEFORE ANY SUCH MARKINGS ARE REQUIRED. ONCE FAA MARKS THE CABLES, THE CONTRACTOR WILL BE REQUIRED TO SURVEY THE FAA UTILITIES SO THEY CAN BE REPLACED DURING CONSTRUCTION WITHOUT REMARKING BY THE FAA. THIS SHALL BE INCIDENTAL TO THE CONTRACT. THE FAA PERSONNEL ARE ONLY AVAILABLE FROM 9 AM TO 3 PM, MONDAY THROUGH FRIDAY WITH ADVANCED NOTICE.
- 3. ALL ELEVATIONS SHOWN ON PLANS ARE IN 1929 DATUM. SUBTRACT 0.24 FEET FROM ELEVATIONS SHOWN TO OBTAIN 1988 NAVD.

# MUNICIPALITIES GENERAL NOTES

- 1. THE CHICAGO EXECUTIVE AIRPORT IS A JOINT OWNERSHIP BY BOTH THE VILLAGE OF WHEELING AND CITY OF PROSPECT HEIGHTS. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH VILLAGE AND CITY CODES, ORDINANCES AND STANDARDS AS APPLICABLE.
- ALL CONTRACTORS AND SUBCONTRACTORS SHALL BE REGISTERED WITH THE VILLAGE AND CITY PRIOR TO THE NOTICE TO PROCEED. ALL REGISTRATION FEES SHALL BE INCIDENTAL TO THE CONTRACT.
- 3. THE CONTRACTOR SHALL WORK WITH THE AIRPORT AND ENGINEER TO SECURE THE REQUIRED VILLAGE AND CITY LOCAL CONSTRUCTION PERMITS PRIOR TO THE NOTICE TO PROCEED.
- 4. THE CONTRACTOR SHALL COORDINATE WITH THE VILLAGE AND CITY AT THE WEEKLY PROGRESS MEETINGS AND SHALL NOTIFY THE CITY OF PROSPECT HEIGHTS (847.398.6700) AND THE VILLAGE OF WHEELING (847.459.2600) A MINIMUM OF 48 HOURS PRIOR TO ANY REQUIRED VILLAGE/CITY INSPECTIONS.
- 5. ALL STORM SEWERS AND SANITARY SEWERS ON THE AIRPORT SITE ARE OWNED, OPERATED AND MAINTAINED BY THE CHICAGO EXECUTIVE AIRPORT UNLESS LABELED OTHERWISE.

	EXISTING CONDITIONS LEGEND
Ø	EXISTING BASE MOUNTED MEDIUM INTENSITY TAXIWAY LIGHT
0	EXISTING STAKE MOUNTED MEDIUM INTENSITY TAXIWAY LIGHT
	EXISTING BASE MOUNTED HIGH INTENSITY RUNWAY LIGHT
	EXISTING STAKE MOUNTED HIGH INTENSITY RUNWAY LIGHT
۵	EXISTING IN PAVEMENT MOUNTED HIGH INTENSITY RUNWAY LIGHT
¤	EXISTING ELEVATED RETROREFLECTIVE MARKER
	EXISTING VISUAL APPROACH SLOPE INDICATOR (VASI)
	EXISTING RUNWAY END IDENTIFIER LIGHT (REIL)
0000]	EXISTING APPROACH LIGHTING SYSTEM
	EXISTING AIRFIELD GUIDANCE SIGN
P	EXISTING WINDCONE
®	EXISTING WINDCONE WITH SEGMENTED CIRCLE
ET	EXISTING ELECTRICAL TRANSFORMER
0	EXISTING ELECTRICAL/STORM/SANITARY/TELEPHONE MANHOLE OR EXISTING WATER VALVE VAULT
	EXISTING ELECTRICAL HANDHOLE
	EXISTING STORM INLET
	EXISTING SLOPE BOX
⊳	EXISTING FLARED END SECTION
)	EXISTING HEADWALL
°0	EXISTING CLEANOUT STRUCTURE
٠Ģ٠	EXISTING FLUSH MOUNTED FIRE HYDRANT
$\bowtie \circ_{V}$	EXISTING WATER VALVE
	EXISTING UTILITY PEDESTAL
	EXISTING CONDUIT/DUCT BANK
——16/34——	EXISTING RUNWAY 16/34 CIRCUIT
12/30	EXISTING RUNWAY 12/30 CIRCUIT
——6/24——	EXISTING RUNWAY 6/24 CIRCUIT
	EXISTING RUNWAY 16 APPROPACH LIGHTING CIRCUIT
G/D	EXISTING TAXIWAY G AND D CIRCUIT
DLMY	EXISTING TAXIWAY D, L, M, N, Y AND Z CIRCUIT
ABEF	EXISTING TAXIWAY A, B, E AND F CIRCUIT
	EXISTING TAXIWAY KILO CIRCUIT
—— HFC ——	EXISTING TAXIWAY HFC CIRCUIT
REIL	EXISTING REIL CABLES
	EXISTING VASI CABLES
—— FAA———	EXISTING FAA CABLES
-FAA COMED-	EXISTING COMED SERVICE TO FAA ILS SYSTEM
-FAA WIND-	EXISTING FAA WIND INSTRUMENT CABLES
	EXISTING PRIESTER AVIATION CABLES
	EXISTING STORM SEWER
— —∪D-⊳— —	
W	EAISTING WATERMAIN
	EXISTING SANTIART SEWER
CATV	EXISTING CABLE TELEVISION LINES

	SUMMARY OF QUAN	TITIES		
SE BID - F	EHABILITATE RUNWAY 12/30			
TEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
R110946	ADJUST ELECTRICAL HANDHOLE	EACH	7	
R110947	ADJUST ELECTRICAL MANHOLE	EACH	1	
R125942	ADJUST BASE MOUNTED LIGHT	EACH	40	
R150510	ENGINEER'S FIELD OFFICE	LS	1	
R150520	MOBILIZATION	LS	1	
R152480	SHOULDER ADJUSTMENT	SY	9800	
R156520	INLET PROTECTION	EACH	6	
R201661	CLEAN & SEAL BITUMINOUS CRACKS	LF	920	
R201663	SAND MIX CRACK REPAIR	LF	455	
R401610	BITUMINOUS SURFACE COURSE	TON	3900	
R401630	BITUMINOUS SURFACE TEST SECTION	EACH	1	
R401640	BITUMINOUS PAVEMENT GROOVING	SY	19200	
R401650	BITUMINOUS PAVEMENT MILLING	SY	26700	
R401655	BUTT JOINT CONSTRUCTION	SY	6275	
R401915	REM & REP BIT PAVEMENT - TYPE A	SY	280	
R401916	REM & REP BIT PAVEMENT - TYPE B	SY	240	
R501900	REMOVE PCC PAVEMENT	SY	22	8
R603510	BITUMINOUS TACK COAT	GAL	4625	
R605540	CLEAN & SEAL JOINTS	LF	5170	
R605542	CLEAN & SEAL EXPANSION JOINTS	LF	594	
R620520	PAVEMENT MARKING-WATERBORNE	SF	36060	
R620525	PAVEMENT MARKING-BLACK BORDER	SF	15081	
R620900	PAVEMENT MARKING REMOVAL	SF	8952	
R705945	ADJUST COLLECTION STRUCTURE	EACH	6	
R901510	SEEDING	ACRE	2	
R908515	HEAVY-DUTY HYDRAULIC MULCH	ACRE	2	
DITIVE AL	TERNATE 1 - REHABILITATE RUNWAY 12/30 LIGHTING			
TEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
S108108	1/C #8 5 KV UG CABLE	LF	17260	
S109210	VAULT MODIFICATIONS	LS	1	
S109321	10 KW REGULATOR, STYLE 1	EACH	1	
S110202	2" PVC DUCT, DIRECT BURY	LF	1125	
S125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	1	
S125453	TAXI GUIDANCE SIGN, 13 CHARACTER	EACH	1	
S125454	TAXI GUIDANCE SIGN, 14 CHARACTER	EACH	3	
S125470	MODIFY EXISTING SIGN PANEL	EACH	4	
S125904	REMOVE TAXI GUIDANCE SIGN	EACH	4	
S125922	REPLACE BASE MOUNTED LIGHT	EACH	60	
S152480	SHOULDER ADJUSTMENT	SY	100	
S620520	PAVEMENT MARKING-WATERBORNE	SF	2724	
S620525	PAVEMENT MARKING-BLACK BORDER	SF	1355	
\$620900	PAVEMENT MARKING REMOVAL	SF	3795	
\$901510	SEEDING	ACRE	0.02	
\$908515	HEAVY-DUTY HYDRAULIC MULCH	ACRE	0.02	

\*DENOTES SPECIALTY ITEM.

UPDATE BY: Kris Salv LAVOUT: Lavout1

IL. CONTRACT: PA061 IL. LETTING ITEM: 10A IL. PROJECT: PWK-4552 S.B.G. PROJECT: 3-17-SBGP-133/139/TBD REVISIONS NUMBER BY DATE 						
0		1	2			
THIS B AT FUI	AR IS LL SCA	EQUAL ALE (34	TO 2" \$X22).			
CHICAGO EXECUTIVE AIRPORT WHEELING/PROSPECT HEIGHTS, ILLINOIS	HEHABILITATE HUNWAY 12/30 AND HUNWAY LIGHTING		INDEX TO SHEETS, SUMMARY OF QUANTITIES AND GENERAL NOTES			
CRAMFORD, MURPHY & TILLY, INC.	CUNSUL ING ENGINEERS License No. 184-000613		CHIGAGO EXECUTIVE AIRPORT			
DESIGN BY:			KWS			
CHECKED B	IY:		DKP			
APPROVED	BY:					
JOB No:		06/08 16290	-04-00			
	FI	NAL				











# GENERAL NOTES

- THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE PROPOSED IMPROVEMENTS WHILE MAINTAINING AIRCRAFT ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT MANAGER AND RESIDENT ENGINEER AND BE APPROVED BY THE DIVISION OF AERONAUTICS AND FEDERAL AVIATION ADMINISTRATION
- ALL OPERATIONS SHALL BE IN CONFORMANCE WITH AC 150/5370-2G (LATEST EDITION) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION"
- CONTRACTOR'S EQUIPMENT SHALL BE STORED IN THE EQUIPMENT AND MATERIAL STORAGE/STAGING AREA WHEN CONSTRUCTION IS NOT IN PROGRESS. NO EXCEPTIONS FOR SLOW MOVING EQUIPMENT SHALL BE ALLOWED
- THE AIRPORT MANAGER SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATION PHASING AND SEQUENCE AS IT RELATES TO PEDESTRIAN, VEHICULAR AND AIRCRAFT SAFETY
- ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS LISED AS A HALL ROAD OR STORAGE AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER. THE COST OF MAINTAINING, REPAIRING OR CONSTRUCTING THESE PAVEMENTS AND AREAS SHALL BE INCIDENTAL TO THE CONTRACT. EXISTING AREAS OUTSIDE THE PROJECT LIMITS WHICH ARE DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE AIRPORT MANAGER
- THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND MATERIALS OFF OF THE EXISTING TAXIWAYS, APRONS AND RUNWAYS OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE ENGINEER AND AIRPORT.
- WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT SHALL CONSIST OF MOVABLE POLE MOUNTED FLOODLIGHTS AND/OB SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE LIGHTING SHALL BE AS APPROVED BY THE ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY CONTRACTOR'S WORK HOURS SHALL BE IN ACCORDANCE WITH LOCAL ORDINANCES.
- ALL AIBEIELD LIGHTING AND LIGHTING GUIDANCE SYSTEMS (NAVAIDS) LOCATED WITHIN AND IMMEDIATELY ADJACENT TO THE CONTRACTORS WORK ZONE SHALL BE CHECKED FOR OPERATIONAL CONDITION PRIOR TO THE DEPARTURE FROM THE AIRPORT WITH THE AIRPORT MANAGER ANY DEFECIENCIES IN THESE SYSTEMS DUE TO HE ACTS OF CONTRACTOR OR HIS SUBCONTRACTORS, SUPPLIERS OR CONSULTANTS SHALL BE REPAIRED IMMEDIATELY
- THE CONTRACTOR WILL BE REQUIRED TO HAVE A SWEEPER AVAILABLE FOR USE AT ALL TIMES. WHEN ACTIVE AIRFIELD PAVEMENTS ARE UTILIZED AS HAUL ROADS BY THE CONTRACTOR. MATERIAL TRACKED ON TO THE PAVEMENT SHALL BE CONTINUALLY REMOVED WITH SAID SWEEPER. THIS SWEEPING SHALL NOT BE PAID FOR SEPERATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- 10. MATERIALS REMOVED FROM THE PROJECT WILL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS NOTED OTHERWISE
- 11. PAYMENT FOR TRAFFIC CONTROL INCLUDING, BUT NOT LIMITED TO BARRICADES, CONSTRUCTION FENCE SIGNING, RUNWAY AND TAXIMAY CLOSED MARKERS, SAFETY AND OBJECT FREE AREAS, LATHE AND RIBBON, ETC. SHALL NOT BE PAID SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. LOW PROFILE BARRICADES SHALL CONFORM TO THE DETAILS IN THE PLANS AND SEQUENCE OF CONSTRUCTION. BARRICADE INSTALLATION WILL BE REQUIRED PRIOR TO ACCESS TO THE WORK AREA BY CONTRACTOR'S WORKERS, EQUIPMENT OR MATERIAL. SIGNS SHALL BE PLACED AT EACH TAXIWAY/RUNWAY CLOSURE LOCATION AND SHALL BE ATTACHED TO THE BARRICADES. EACH BARRICADE LOCATION SHALL CONSIST OF ONE "DO NOT ENTER" SIGN AND ONE "AIRCRAFT MOVEMENT AREA" SIGN. SIGNS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. ALL BARRICADES SHALL BE PLACED OUTSIDE OF ACTIVE SAFETY AREAS AND OBJECT FREE AREAS.
- THE CONTRACTOR SHALL CONTACT THE AIRPORT MANAGER THROUGH THE RESIDENT ENGINEER TEN (10) 12. WORKING DAYS IN ADVANCE OF THE START OF CONSTRUCTION SO THAT THE APPROPRIATE NOTAMS MAY BE ISSUED
- 13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING ALL CONSTRUCTION ACCESS GATES CLOSED DURING NON-WORKING HOURS. THE CONTRACTOR SHALL PROVIDE A SIGN AT THE ACCESS GATE SAYING "AUTHORIZED PERSONNEL ONLY". THE CONTRACTOR SHALL CLOSE AND LOCK THE ACCESS GATE UPON LEAVING THE SITE. THROUGHOUT THE DURATION OF THE CONTRACT, ANY DAMAGES TO THE ACCESS ROAD, ACCESS GATE OR FENCING ADJACENT TO THE PROJECT SHALL BE REPAIRED BY THE CONTRACTOR TO THE SATISFACTION OF THE RESIDENT ENGINEER. ALL COST RELATING TO CONTRACTOR'S ACCESS AND SECURITY SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR
- 14. CONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS OR A WORKING BEACON LIGHT ON ALL EQUIPMENT AT ALL TIMES DURING CONSTRUCTION. SEE FLAG DETAIL
- 15. IN THE CASE OF AN EMERGENCY, CONTRACTOR SHALL NOTIFY AIRPORT MANAGER AND THE RESIDENT ENGINEER
- 16. DURING ADVERSE WEATHER, THE CONTRACTOR SHALL MAKE PROVISIONS FOR ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT. NO EXTENSION OF CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADFOUATE ACCESS TO THE WORK
- 17. THE TALLEST PIECE OF CONSTRUCTION EQUIPMENT IS ANTICIPATED TO BE AN ASPHALT/STONE TRUCK WHICH HAS A MAXIMUM HEIGHT OF 25 FEET IN A DUMP POSITION
- 18. JE BUNWAY NUMERALS ARE PRESENT DURING CONSTRUCTION THEN CONTRACTOR SHALL PLACE CLOSED RUNWAY MARKER OVER NUMERALS AS DETAILED, OTHERWISE PLACE RUNWAY CLOSED MARKER IN TURF AT ENDS OF RUNWAY AS DETAILED.
- 19. CHICAGO EXECUTIVE AIRPORT WILL BE IN OPERATION DURING THE CONSTRUCTION OF THIS PROJECT COORDINATION OF WORK WITH THE AIRPORT IS MANDATORY SO AS TO MINIMIZE IMPACTS ON AIRPORT
- 20. APPROXIMATE LOCATION OF HAUL ROUTES ON THE AIRPORT SITE ARE SHOWN ON THE GENERAL PROJECT LAYOUT AND THE PHASING PLANS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE HAUL BOUTES (STATE HIGHWAYS, COUNTY BOADS OB CITY STREETS) WITH THE APPOPPIATE OWNER WHO HAS JURISDICTION OVER THE AFFECTED ROUTE. ON-SITE ROADS USED AS HAUL ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR AND SHALL BE RESTORED AT THE CONTRACTOR'S EXPENSE TO THEIR ORIGINAL CONDITION UPON COMPLETION OF BEING USED AS A HAUL ROUTE. THE BEFORE AND AFTER CONDITION OF ON-SITE HAUL ROUTES SHALL BE JOINTLY INSPECTED AND DETERMINED BY THE CONTRACTOR AND THE ENGINEER. FENCING, DRAINAGE, GRADING AND OTHER MISCELLANEOUS CONSTRUCTION REQUIRED TO CONSTRUCT TEMPORABY HAUL APPROVED BY THE ENGINEER PRIOR TO THE WORK, ALL ON-SITE ACCESS ROADS TO AIRPORT FACILITIES SHALL BE REMAIN OPEN AND MAINTAINED AT ALL TIMES
- MOBILIZATION/FOLIPMENT STORAGE AREA WILL BE MADE AVAILABLE FOR CONTRACTOR'S MOBILIZATION AND STORAGE AS SHOWN ON THE PLANS. THIS AREA SHALL BE RESTORED TO THE ORIGINAL CONDITION UPON COMPLETION OF THE PROJECT AT THE CONTRACTOR'S EXPENSE.

- 22. LOCATION OF KNOWN EXISTING AIRPORT UNDERGROUND CABLES ARE SHOWN ON THE PLANS AND MUST BE VERIFIED BY THE CONTRACTOR. REPAIR OF DAMAGED CABLE MUST BE STARTED IMMEDIATELY AND CONTINUED UNTIL COMPLETED. ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS, OR AS DIRECTED BY THE OWNER OF THE CABLE OR FACILITY, AND SHALL BE AT THE CONTRACTOR'S EXPENSE. IF FAA CABLES ARE DAMAGED, REPAIRS SHALL BE DONE FROM PREVIOUS EXISTING TERMINATION POINT TO PREVIOUS EXISTING TERMINATION POINT IN ACCORDANCE WITH FAA REQUIREMENTS AND IN THE PRESENCE OF A FAA REPRESENTATIVE. THE OWNER MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHERS IN WHICH CASE THE TRACTOR SHALL BE RESPONSIBLE FOR PAYING THE INCURRED COSTS OF REPAIRS
- 23. COORDINATION MEETINGS THE CONTRACTOR SHALL CONDUCT WEEKLY COORDINATION MEETINGS TO DISCUSS WORK AREAS AND SCHEDULING, ETC. WITH THE ENGINEER, AIRPORT OPERATIONS, FAA, AND OTHER APPROPRIATE OFFICIALS, MINUTES FROM THE WEEKLY MEETINGS SHALL BE PREPARED BY THE CONTRACTOR, FURNISHED TO ALL ATTEMPES PRIOR TO THE SUBSEQUENT MEETINGS OFFICE AT THE FIELD OFFICE. THE COORDINATION MEETING COSTS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
- 24. THE CONTRACTOR SHALL PROVIDE THE PHONE NUMBERS OF THREE PERSONNEL, INCLUDING THE PROJECT SUPERINTENDENT, WHO MAY BE CONTACTED IN AN EMERGENCY. PERSONNEL SHALL BE ON CALL 24 HOURS PER DAY FOR MAINTAINING AIRPORT HAZARD LIGHTING AND BARRICADES.
- 25. DRAINAGE MODIFICATIONS SHALL BE SEQUENCED TO PROVIDE POSITIVE DRAINAGE AT ALL TIMES AT NO DDITIONAL COST TO THE CONTRACT
- 26. VEHICLES AND EQUIPMENT SHALL NOT BE ALLOWED WITHIN THE TAXIWAY OBJECT FREE AREA AND RUNWAY SAFETY AREA OF ACTIVE TAXIWAYS AND BUNWAYS.
- 27. CONTRACTOR SHALL STORE EQUIPMENT AND MATERIALS IN SUCH A MANNER AS NOT TO VIOLATE FEDERAL AVIATION ADMINISTRATION PART 77 IMAGINARY SURFACES OR RUNWAY AND TAXIWAY SAFETY AREAS.
- 28. ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER ELECTRICAL CABLES SHALL REMAIN IN SERVICE AT ALL TIMES. ALL EXISTING LIGHTING AND VAULT EQUIPMENT SHALL REMAIN IN SERVICE UNTIL PROPOSED IMPROVEMENTS ARE INSTALLED AND OPERATIONAL, UNLESS OTHERWISE APPROVED BY THE ENGINEER ANY CABLES DAMAGED BY THE CONTRACTOR SHALL BE IMMEDIATELY BEPAIRED AT HIS EXPENSE. ANY NECESSARY TEMPORARY JUMPER CABLES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- . COORDINATION BY THE CONTRACTOR WITH THE EXISTING UTILITIES SHALL BE COMPLETED BEFORE CONSTRUCTION IS STARTED. CONTRACTOR IS REFERRED TO SECTION 50-17 OF THE SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER OR THE DESIGN ENGINEER ASSUME ANY BESPONSIBILITY WHATSOEVER IN RESPECT TO THE ACCUBACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED THAT THE LOCATIONS, SIZE AND TYPE MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY OF HIS OPERATIONAL PLANS THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY. THE RESIDENT ENGINEER AND THE AIRPORT MANAGER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER

# CONTRACTOR CROSSING RUNWAY SAFETY AREAS (RSA) AND TAXIWAY OBJECT FREE AREAS (TOFA)

- 31 ANYTIME THE CONTRACTOR IS REQUIRED TO UTILIZE OR CROSS ACTIVE AIRFIELD PAVEMENTS FOR ACCESS TO AND FROM THE WORK ZONE, A FUIL TIME CROSSING GUARD IN RADIO CONTACT WITH THE CONTROL TOWER SHALL BE FURNISHED BY THE CONTRACTOR FOR MOVEMENTS OF VEHICLES OR EQUIPMENT TO AND FROM THE WORK ZONE. THE RADIO OPERATOR SHALL BE FAMILIAR WITH AIRPORT GROUND CONTROL PROCEDURES AND DEMONSTRATE KNOWLEDGE OF SAME TO THE AIRPORT. THE AIRPORT RESERVES THE RIGHT TO APPROVE THE CROSSING GUARDS, THE CONTRACTOR SHALL PROVIDE THEIR OWN RADIOS, THIS COST SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYMENT OF MUNICIPAL FINES (\$500 PER OCCURENCE) DUE TO AIRFIELD INCURSIONS BY HIS EMPLOYEES, SUBCONTRACTORS, SUPPLIERS ONSULTANTS AND/OR AGENTS
- 32. ANY PAVEMENT DAMAGED BY CONTRACTOR'S OPERATIONS SHALL BE REPAIRED IMMEDIATELY BY HIM TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER AT NO ADDITIONAL COST TO THE OWNER. PAVEMENT SHALL BE CONTINUALLY SWEPT TO PROVIDE DEBRIS FREE SURFACE DURING ALL HAUL ROAD OPERATIONS. THIS COST SHALL NOT BE PAID SEPERATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE

# LIMITATIONS ON CONSTRUCTION WITHIN RUNWAY SAFETY AREAS (RSA) / RUNWAY OBSTACLE FREE ZONE (OFZ) AND TAXIWAY OBJECT FREE AREAS (TOFA)

RUNWAYS

33. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER TEN (10) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS. ANY WORK WITHIN THE RUNWAY SAFETY AREA OR RUNWAY OBSTACLE FREE AREA WILL REQUIRE A RUNWAY CLOSURE. WORK SHALL BE EXPEDITED IN THESE AREAS AND AT THE END OF EACH WORKING PERIOD THESE AREAS SHALL BE SMOOTHLY GRADED TO ALLOW THE RUNWAY TO BE REOPENED PER FAA REQUIREMENTS. AT LEAST ONE OF THE RUNWAYS SHALL REMAIN IN OPERATION AT ALL TIMES. IF NECESSARY, STEEL PLATES SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR TO COVER ANY OPEN TRENCHES OR EXCAVATION WITHIN THE RSA AT NO ADDITIONAL COST TO THE CONTRACT. NO MATERIAL SHALL BE STOCKPILED WITHIN THE RSA. IF DURING RUNWAY CLOSURE AN EMERGENCY IS DECLARED, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE RUNWAY OF ALL VEHICLES, MEN, EQUIPMENT AND BARRICADES

TAXIWAYS:

34. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER FIVE (5) WORKING DAYS IN ADVANCE FOR WORK WITHIN THE TAXIWAY OBJECT FREE AREA. ANY WORK WITHIN THE TAXIWAY OBJECT FREE AREA WILL REQUIRE A TAXIWAY CLOSURE. WORK WITHIN THE TAXIWAY OBJECT FREE AREA SHALL BE EXPEDITED AND AT THE END OF EACH WORKING PERIOD THESE AREAS SHALL BE SMOOTHLY GRADED TO ALLOW THE TAXIWAY TO BE REOPENED PER FAA REQUIREMENTS. IF NECESSARY, STEEL PLATES SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR TO COVER ANY OPEN TRENCHES OR EXCAVATION WITHIN THE TOFA AT NO ADDITIONAL COST TO THE CONTRACT. NO MATERIAL OR EQUIPMENT SHALL BE STOCKPILED OR STORED WITHIN THE TOFA. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE EQUIPMENT TO ALLOW AIRCRAFT TO PASS, THEY SHALL DO SO AT NO EXTRA COST TO THE PROJECT.

# ALLOWABLE CONSTRUCTION HOURS

THE ALLOWABLE CONSTRUCTION HOURS FOR THE VILLAGE OF WHEELING AND THE CITY OF PROSPECT HEIGHTS ARE FROM 7 AM TO 6 PM, MONDAY THROUGH SATURDAY, THE AIRPORT WILL SEEK A WAIVER WITH THE VILLAGE AND CITY TO ALLOW CONSTRUCTION OUTSIDE OF THOSE HOURS FOR THE PHASES SHOWN TO BE COMPLETED AND OVER WEEKENDS ONLY. AT ALL OTHER TIMES, IT IS EXPECTED THE CONTRACTOR WILL ADHERE TO THE VILLAGE AND CITY NOISE ORDINANCE AND ALLOWABLE CONSTRUCTION HOUR POLICIES. SHOULD THE CONTRACTOR REQUIRE ADDITIONAL WORKING HOURS, HE SHALL REQUEST, THROUGH THE RESIDENT ENGINEER, THAT THE VILLAGE AND CITY BE CONTACTED TO REQUEST ADDITIONAL WAIVER OF THE NOISE ORDINANCE POLICY. ANY FINES LEVIED BY THE VILLAGE OR CITY TO THE AIRPORT FOR VIOLATIONS OF THE NOISE ORDINANCE AND ALLOWABLE CONSTRUCTION HOURS SHALL BE PAID BY THE CONTRACTOR

CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS, WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS (SEE SPECIAL PROVISIONS SECTION 30-05). THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS SUBCONTRACTORS. IT IS ANTICIPATED THE FOLLOWING PROJECTS MAY BE UNDER CONSTRUCTION CONCURBENTLY WITH THIS PROJECT. NO ADDITIONA COMPENSATION SHALL BE CONSIDERED FOR ANY EFFORTS TO COORDINATE AND ACCESS THE TAXIWAY SITE DUE TO ADJACENT BUILDING CONSTRUCTION

HAWTHORNE HANGAR AND APRON DEVELOPMENT IN EAST QUADRAN

AIRFIELD PAVEMENT REPAIRS

AIRFIELD PAVEMENT REMARKING

## GROUND CONTROL FREQUENCY: 121.7 MHz AIR CONTROL FREQUENCY: 119.9 MHz

MAXIMUM ANTICIPATED HEIGHT OF CONSTRUCTION EQUIPMENT: DUMP TRUCK IN DUMP POSITION - 2

IN THE EVENT THE CONTRACTOR PROPOSES TO UTILIZE CONSTRUCTION EQUIPMENT THAT IS TALLER THAN WHAT IS LISTED, THE CONTRACTOR WILL BE RESPONSIBLE TO SUBMIT EAA FORM 7460 FOR AIRSPACE APPROVAL. THE RESIDENT ENGINEER WILL PROVIDE BASE AIRPORT INFORMATION FOR THE CONTRACTOR'S USF

	TABLE 1 - CRITICAL POINTS						
WORK AREA	POINT	APPROXIMATE ELEVATION OF GROUND (1929 DATUM)	ANTICIPATED EQUIPMENT AND HEIGHT	APPROXIMATE ELEVATION OF EQUIPMENT (1929 DATUM)	LATITUDE (NAD 83)	LONGITUDE (NAD 83)	
1A	C1	646	SEMI/DUMP TRUCK - 25'	671	42°06'51.34"	87°54'15.50"	
1A	C2	645	SEMI/DUMP TRUCK - 25'	670	42°06'50.28"	87°54'14.95"	
1A	C3	642	SEMI/DUMP TRUCK - 25'	667	42°06'45.78"	87°53'57.26"	
1A	C4	644	SEMI/DUMP TRUCK - 25'	669	42°06'44.33"	87°53'57.76"	
1A	C5	642	SEMI/DUMP TRUCK - 25'	667	42°06'36.97"	87°53'52.49"	
1B	C6	644	SEMI/DUMP TRUCK - 25'	669	42°06'49.61"	87°54'11.13"	
1B	C7	644	SEMI/DUMP TRUCK - 25'	669	42°06'46.74"	87°54'11.76"	
1C	C8	643	SEMI/DUMP TRUCK - 25'	668	42°06'45.61"	87°54'02.06"	
2	C9	645	SEMI/DUMP TRUCK - 25'	670	42°06'48.36"	87°54'06.91"	
1C	C10	646	SEMI/DUMP TRUCK - 25'	671	42°06'43.42"	87°54'07.88"	
STAGING	S1	643	PICK UP TRUCK - 10'	653	42°06'57.48"	87°54'22.22"	
STAGING	S2	644	PICK UP TRUCK - 10'	654	42°06'56.92"	87°54'20.77"	
STAGING	S3	646	PICK UP TRUCK - 10'	656	42°06'54.59"	89°54'22.19"	
STAGING	S4	641	PICK UP TRUCK - 10'	651	42°06'36.17"	87°53'47.11"	
STAGING	S5	640	PICK UP TRUCK - 10'	650	42°06'37.54"	87°53'46.14"	
STAGING	S6	643	PICK UP TRUCK - 10'	653	42°06'36.37"	87°53'43.18"	

EXISTING CRITICAL AIRCRAFT AND REQUIRED SAFETY AREAS						
RUNWAY	16/34	12/30	6/24			
APPROACH CATEGORY	D	В	В			
DESIGN GROUP	ш	Ш	I			
DESIGN AIRCRAFT	GULFSTREAM 550	KING AIR B200	CESSNA 421			
APPROACH SPEED	141 KNOTS	103 KNOTS	96 KNOTS			
WINGSPAN	94 FEET	55 FEET	42 FEET			
TAIL HEIGHT	25.8 FEET	15.0 FEET	11.6 FEET			
STRENGTH (MGTW)	90,500 LBS.	12,500 LBS.	7,450 LBS.			
LENGTH	97 FEET	44 FEET	37 FEET			
RUNWAY SAFETY AREA WIDTH (RSA)	500 (250' FROM Ç)	150 (75' FROM ငူ)	120 (60' FROM ငူ)			
(1)(3) RWY OBJECT FREE AREA WIDTH (ROFA)	800	500	400			
TAXIWAY SAFETY AREA WIDTH (TSA)	118	79	49			
(1)(3) TXY OBJECT FREE AREA WIDTH (TOFA)	186 (93' FROM ငူ)	131(65.5' FROM ငု)	89 (44.5' FRM Cֲ)			

- 12/30 WHICH SHALL BE CLOSED DURING THE CONSTRUCTION PHASE DURATION
- 2. RUNWAY 12/30 END COORDINATES ARE NOT CHANGING IN THIS PROJECT
- AT THE END OF THE WORK DAY NO CONSTRUCTION EQUIPMENT SHALL BE PARKED/STORED WITHIN THE OBJECT FREE AREA(S) OF OPEN OR CLOSED RUNWAYS AND/OR TAXIWAYS. PARKED/STORED EQUIPMENT HEIGHT SHALL NOT PENETRATE PART 77 SURFACE(S).

# ELECTRICAL NOTES - ALL PHASES

- ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER AIRPORT FLECTRICAL CABLES SHALL REMAIN IN SERVICE UNTIL REPLACED AS ACCEPTABLE TO THE RESIDENT ENGINEER. ALL TEMPORARY CABLING AND SPLICING NECESSARY TO KEEP THE CIRCUITS IN OPERATION SHALL BE CONSIDERED INCIDENTAL TO CONTRACT
- WHEN FAA CABLES ARE REQUIRED TO BE LOCATED, A 10 2. WORKING DAY ADVANCED NOTICE SHALL BE GIVEN TO THE FAA BEFORE ANY SUCH MARKINGS ARE REQUIRED. ONCE FAA MARKS THE CARLES THE CONTRACTOR WILL BE REQUIRED. TO SURVEY THE FAA UTILITIES SO THEY CAN BE REPLACED DURING CONSTRUCTION WITHOUT REMARKING BY THE FAA. THIS SHALL BE INCIDENTAL AND AT THE CONTRACTOR'S EXPENSE. THE FAA PERSONNEL ARE ONLY AVAILABLE FROM 9 AM TO 3 PM, MONDAY THROUGH FRIDAY WITH ADVANCED
- SPECIAL ATTENTION IS NECESSARY WHEN WORKING NEAR FAA POWER AND CONTROL CABLES. ANY FAA UTILITY THAT IS DAMAGED OR CUT DURING CONSTRUCTION SHALL BI REPAIRED IMMEDIATELY. FAA REQUIRES THAT ANY DAMAGED CABLE BE REPLACED IN ITS ENTIRETY, FROM POWER/CONTROL SOURCE TO THE EQUIPMENT/SERVICE. SPLICES OF ANY KIND WILL NOT BE PERMITTED. EXPOSURES OF ANY FAA CABLES MUST BE DONE BY HAND DIGGING OR HYDRO-EXCAVATION. NO ADDITIONAL COMPENSATION WILL BE MADE FOR LOCATING. REPLACEMENT OR REPAIR OF FAA FACILITIES OR CABLES BUT, SHALL BE INCIDENTAL AND AT THE CONTRACTOR'S EXPENSE

TOFA, ROFA, RSA, CRITICAL AREAS, PART 77 AND DEPARTURE/APPROACH SURFACES ARE SHOWN FOR RUNWAY

NO CONSTRUCTION WITHIN THESE LIMITS WILL BE ALLOWED WITHOUT THE RUNWAY AND/OR TAXIWAY CLOSED.

IL. CONTR IL. LETTIN IL. PROJEC S.B.G. PRO	IL. CONTRACT: PA061         IL. LETTING ITEM: 10A         IL. PROJECT: PWK-4552         S.B.G. PROJECT: 3-17-SBGP-133/139/TBD         REVISIONS         NUMBER       BY         DATE         0       1         0       1					
CHICAGO EXECUTIVE AIRPORT WHEELING/PROSPECT HEIGHTS, ILLINOIS			GENERAL NOTES AND DETAILS - SHEET 1			
CRAMFORD, MURPHY & TILLY, INC.	CONSULTING ENGINEERS License No. 184-000613		CHICAGO EXECUTIVE CHICAGO AIRPORT			
DESIGN BY: DRAWN BY: CHECKED E	IY:		DKP JRO DKP			
APPROVED	BY:	06 /01	KWS			
JOB No:		16290	-04-00			
	FI	NAL				

# PHASING NOTES (ALL PHASES)

- 1 THE INTENT OF THE PHASING PLANS IS TO MINIMIZE THE IMPACT OF CONSTRUCTION ON THE OPERATION OF THE AIRPORT. THE APPROVED BY THE RESIDENT ENGINEER AND AIRPORT EXECUTIVE DIRECTOR.
- 2. PRIOR TO REOPENING A CLOSED RUNWAY, THE ENTIRE (RSA) RUNWAY SAFETY AREA (250 FEET FROM CENTERLINE AND INCLUDING BEYOND THE END OF THE RUNWAY WITHIN AIRPORT PROPERTY) AND (TOFA) TAXIWAY OBJECT FREE AREA MUST MEET FAA CRITERIA. FAA CRITERIA REQUIRES THAT THERE BE NO OPEN EXCAVATIONS OR TRENCHES IN THE SAFETY AREA(S), THE MAXIMUM PAVEMENT DROP OFF BE3 INCHES, AND ALL GRADES IN ANY DIRECTION BE LESS THAN 5 PERCENT. STEEL PLATES, TEMPORARY WEDGING OF BASE COURSE AND BITUMINOUS CONCRETE MAY BE REQUIRED TO MEET CRITERIA. ALL NECESSARY TEMPORARY MEASURES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- THE CONTRACTOR SHALL SUBMIT A CONSTRUCTION SCHEDULE. STRICT ADHERENCE TO THE APPROVED SCHEDULE WILL BE ENFORCED TO AVOID CONFLICTS WITH OTHER CONSTRUCTION ACTIVITIES ON THE AIRPORT AND THE ADVERSE EFFECTS THEY COULD HAVE ON AIRPORT OPERATIONS.
- THE CONTRACTOR SHALL COORDINATE CLOSELY WITH THE AIRPORT STAFF TO SCHEDULE THE RUNWAY/TAXIWAY CLOSURES ITEMS SUCH AS THE EXTENDED WEATHER FORECAST, MATERIAL AVAILABILITY, EQUIPMENT DEPENDABILITY AND MANPOWER AVAILABILITY SHALL BE DISCUSSED PRIOR TO SCHEDULING THIS CRITICAL CLOSURE. THE AIRPORT EXECUTIVE DIRECTOR AND THE CONTRACTOR SHALL MUTUALLY AGREE ON THE EXACT DATES AND TIMES OF THE CLOSURE(S)
- 6. CONTRACTOR MUST MAINTAIN ACCESS TO ALL ACTIVE AND OPEN AREAS AT ALL TIMES. CONTRACTOR SHALL RELOCATE CONTRACTOR ADDITIONAL COST TO CONTRACT TO ALLOW AIRCRAFT TO PASS. CONTRACTOR SHALL COORDINATE CONSTRUCTION OPERATIONS AT ALL ACTIVE AND OPEN AREAS TO PROVIDE MINIMAL DISRUPTIONS TO AIRCRAFT MOVEMENT IN THAT AREA
- 7. FAA AND AIRPORT ACCESS ROAD(S) SHALL NOT BE USED AS A HAUL ROAD BY THE CONTRACTOR WITHOUT PRIOR APPROVAL
- 8. TO THE EXTENT POSSIBLE THE CONTRACTOR SHALL HAVE ALL EMPLOYEE PARKING OUTSIDE OF AIRPORT FENCE OR AS INDICATED AT THE LOCATION SHOWN
- 9. THE AIRPORT RESERVES THE RIGHT TO MODIFY THE SEQUENCE OF CONSTRUCTION INCLUDING BUT NOT LIMITED TO PHASING, WORK AREAS, BARRICADE PLACEMENT, ACCESS AND HAUL ROUTES, AND CONTRACTOR MOVEMENTS AT ANY TIME DURING THE PROJECT WITH FAA. IDA AND ATCT APPROVAL

# GENERAL NOTES - RUNWAY 16/34

- 1. PRIOR TO REOPENING A CLOSED BUNWAY, THE ENTIRE BUNWAY SAFETY AREA MUST MEET FAA CRITERIA, FAA CRITERIA REQUIRE THAT THERE BE NO OPEN EXCAVATIONS OR TRENCHES, THE MAXIMUM PAVEMENT DROPOFF BE 3 INCHES, AND ALL GRADES IN ANY DIRECTION BE LESS THAN 3 PERCENT. TEMPORARY WEDGING OF BASE COURSE AND BITUMINOUS CONCRETE WILL BE REQUIRED TO MEET CRITERIA
- 2. BECAUSE OF THE CRITICAL LIMITATIONS WHICH THE CLOSURE OF RUNWAY 16/34 PLACES ON THE USERS OF THE AIRPORT, LOUIDATED DAMAGES IN THE AMOUNT OF \$2500 WILL BE DEDUCTED FROM THE MONES OWED THE CONTRACTOR FOR EACH HALF HOUR OVER 6:00 AM UNTIL SPECIFIED WORK IS COMPLETED AND THE MONIES OWED THE CONTRACTOR FOR EACH DAMAGES MAY BE ASSESSED STARTING AT 6:01 AM ON ANY DAY THE RUNWAY IS NOT REOPENED.

# GROOVING NOTE

1. IT SHALL BE UNDERSTOOD THAT AFTER PAVING IS COMPLETE, BITUMINOUS PAVEMENT GROOVING WILL BE THE CONTROLLING ITEM, WHICH REQUIRES A CURE TIME OF 28 DAYS, WHILE CALENDAR DAYS WILL BE RECORDED, THESE DAYS WILL BE CONSIDERED UNWORKABLE. BASED ON SUGGESTED SEQUENCE AND SCHEDULE IT IS ESTIMATED THAT 21 DAYS WILL NOT BE CHARGED AGAINST CONTRACT TIME.

# AIRPORT EVENT SUMMARY

ANTICIPATED TO BE ON JUNE 29, 2019

ANTICIPATED FROM JULY 19 TO JULY 29

NO WORK SHALL BE ALLOWED

RUNWAY 16/34 SHALL BE OPEN

\* EEA FLY-IN CONVENTION

# **AIRFIELD LIGHTS AND SIGNS NOTES**

- \* ANNUAL 5K / 1 MILE WALK EVENT/FIREWORKS CONTRACTOR SHALL COVER ALL AIRFIELD SIGNS AND TAXIWAY LIGHTS ON CLOSED TAXIWAYS UNTIL THE TAXIWAY IS RE-OPENED FOR AIRCRAFT USE RUNWAYS 16/34, 12/30 AND 6/24 SHALL BE OPEN THE METHOD AND MATERIALS USED TO COVER THE SIGNS AND LIGHTS SHALL MEET THE ENGINEER'S AND AIRPORT'S APPROVAL, COST INCIDENTAL TO THE CONTRACT. REMOVING LAMPS FROM ENERGIZED FIXTURES AS A MEANS TO REMOVE THE LIGHTS OR FIXTURES FROM SERVICE SHALL NOT BE ACCEPTABLE
  - 2. CONTRACTOR SHALL TURN OFF RUNWAY EDGE LIGHTING REGULATOR AND LOCK-OUT/TAG-OUT CIRCUIT BREAKER AND CUT OUT INSIDE THE FLECTRICAL VAULT. DURING ALL RUNWAY CLOSURES, CONTRACTOR SHALL COORDINATE ACCESS TO THE VAULT WITH THE AIRPORT MANAGER/RESIDENT ENGINEER PRIOR TO RE-OPENING THE RUNWAY. THE CONTRACTOR SHALL COORDINATE WITH AIRPORT MANAGER/RESIDENT ENGINEER TO RE-ENERGIZE THE RUNWAY CIRCUIT.







OFF PAVEMENT TEMPORARY CLOSED RUNWAY MARKER DETAIL NO SCALE



CONSTRUCTION EQUIPMENT AND TRUCK SIGNAL FLAG NOT TO SCALE

# CLOSED RUNWAY MARKER NOTES

- DURING VARIOUS PHASES OF WORK, IT WILL BE NECESSARY TO CLOSE RUNWAYS TO AIR TRAFFIC ON A TEMPORARY BASIS AS COORDINATED WITH THE AIRPORT AND TOWER PERSONNEL.
- FOR RUNWAY CLOSURES INVOLVING A SINGLE RUNWAY, IT IS ANTICIPATED THAT THE AIRPORT SHALL MOBILIZE THE AIRPORT OWNED LIGHTED "X"S ON EACH END OF THE CLOSED RUNWAY. THE CONTRACTOR SHALL BE REQUIRED TO MAINTAIN THE LIGHTED "X"S DURING EACH CLOSURE PERIOD. CONTRACTOR SUPPLIED MAINTENANCE SHALL INCLUDE, BUT NOT BE LIMITED TO, FUELING, REPLACING LAMPS, CHECKING AND SUPPLYING OIL, ETC. IF ANY DAMAGE IS INCURRED TO THE AIRPORT LIGHTED "X"S DURING CONSTRUCTION BY THE CONTRACTOR, THE CONTRACTOR SHALL REPLACE THE LIGHTED "X" IN KIND AT NO COST TO THE CONTRACT OR AIRPORT
- FOR RUNWAY CLOSURES INVOLVING MORE THAN ONE RUNWAY, OR IF THE AIRPORT OWNED LIGHTED "X"S ARE NOT AVAILABLE, THE CONTRACTOR SHALL MARK THE RUNWAYS TO BE CLOSED BY PLACING YELLOW CROSSES AT THE LOCATION AND DIMENSIONS DETAILED ON THE SEQUENCE OF CONSTRUCTION AND PER AC 150/5370-2 (LATEST EDITION). THE CROSSES ARE SHOWN ON THE SERVECTIVE RUNWAYS ACCORDING TO THE VARIOUS PHASES OF WORK AS DELINEATED IN THE SUGGESTED SEQUENCE OF CONSTRUCTION.
- 4. TEMPORARY CLOSED RUNWAY MARKERS SHALL BE YELLOW.
- 5. TEMPORARY MARKERS SHALL BE MATERIAL APPROVED BY THE ENGINEER

 $\square$ 

- CONTRACTOR SHALL MAINTAIN AND RELOCATE MARKERS AS SHOWN ON THE PLANS OR AS NEEDED TO FACILITATE CONSTRUCTION
- MARKERS ON PAVEMENT SHALL BE PLACED OVER EXISTING RUNWAY NUMERALS AS SHOWN
- COST OF FURNISHING, INSTALLING, MAINTAINING AND REMOVING MARKERS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT

PLAN VIEW

150' -



⊕

# AIRSIDE LOW PROFILE LIGHTED BARRICADE

NOT TO SCALE

# BARRICADE NOTES

- FLASHER OR STEADY BURN LIGHTS SHALL BE BATTERY OPERATED, LENS SHALL BE RED AND BE ABLE TO BOTATE
- 2. FACING OF BARRICADE SHALL BE COVERED WITH REFLECTIVE TAPE OR PAINT.
- BARRICADES TO BE PLACED WITH A MAXIMUM OF 4' SPACING END TO END UP TO THE EDGE OF PAVEMENT ALONG OPERATIONAL PAVEMENT ADJACENT TO CONSTRUCTION AS DIRECTED BY THE RESIDENT ENGINEER ALTERNATE ELASHER OR STEADY BURN LENSES SO THAT EVERY OTHER LENS IS BOTATED 90°
- FLASHER OR STEADY BURN LIGHTS SHALL BE SECURED TO 4. THE BARRICADES, AS APPROVED BY THE RESIDENT FNGINFFR
- BARRICADES SHALL BE OF LOW MASS, EASILY 5. COLLAPSIBLE UPON CONTACT WITH AN AIRCRAFT OR ANY OF IT COMPONENTS, AND WEIGHTED TO AVOID BEING BLOWN OVER
- BARRICADES SHALL BE OF A COMMERCIAL DESIGN AND 6 SHALL MEET CURRENT FAA REQUIREMENTS.
- PLACE ALL BARRICADES OUTSIDE RUNWAY SAFETY AREAS AND OUTSIDE TAXIWAY OBJECT FREE AREAS.
- ALL COST ASSOCIATED WITH THE LOW PROFILE 8. BARRICADES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.











# STORM WATER POLLUTION PREVENTION PLAN

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME.

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEFRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING, WHICH WILL BE AT THE SUBSECTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SELDING, WHICH WILL BE AT THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

# SITE DESCRIPTION:

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

THIS PROJECT CONSISTS OF REHABILITATION OF AN EXISTING BITUMINOUS PAVEMENT AT THE CHICAGO EXECUTIVE AIRPORT. THE PROJECT INCLUDES TURF SHOULDER ADJUSTMENT, VARIOUS PAVEMENT ITEMS, ELECTRICAL WORK, PAVEMENT MARKING AND OTHER MISCELLANEOUS CONSTRUCTION WORK.

DESCRIPTION OF CONSTRUCTION ACTIVITY:

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS GRUBBING, EXCAVATION AND GRADING

PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEAN-UP OF TEMPORARY EROSION CONTROL

REMOVAL, ADJUSTMENTS AND INSTALLATION OF ELECTRICAL AND MISCELLANEOUS ITEMS.

VARIABLE DEPTH BITUMINOUS PAVEMENT MILLING AND PAVING.

TURF SHOULDER ADJUSTMENT, SEEDING AND MULCHING.

BITUMINOUS PAVEMENT GROOVING.

INSTALLATION OF NEW PAVEMENT MARKING.

REMOVAL AND DISPOSAL OF TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES.

### AREA OF CONSTRUCTION SITE

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 25 ACRES OF WHICH 2 ACRES WILL BE DISTURBED BY GRADING AND OTHER ACTIVITIES.

# OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS;

- 1. INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS.
- 2. PROJECT PLAN DOCUMENTS, SPECIFICATION AND SPECIAL PROVISIONS, AND PLAN DRAWINGS INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

### DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE:

THE CONSTRUCTION SITE DRAINS INTO THE DES PLAINES RIVER THROUGH A STORM SEWER SYSTEM

# EROSION AND SEDIMENT CONTROL:

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION:

THE DRAWINGS SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE: TEMPORARY SEEDING, PERMANENT SEEDING, MULCHING, SOD, PROTECTION OF TREES, PRESERVATION OF NATURAL VEGETATION, ADDALL BE INTIATED AS SOON AS PRACTICABLE IN PORTION OF THEES, PRESERVATION OF NATURAL VEGETATION, AND ALL OTHER APPROPRIATE MEASURES AS DIRECTED BY THE ENGINEER, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.

AREAS OF EXISTING VEGETATION (WOOD AND GRASSLANDS) OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE IDENTIFIED BY THE ENGINEER FOR PRESERVING AND SHALL BE PROTECTED FROM CONSTRUCTION ACTIVITIES.

DEAD, DISEASED, OR UNSUITABLE VEGETATION WITHIN THE SITE SHALL BE REMOVED AS DIRECTED BY THE ENGINEER

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NEDES PERMIT NUMBER ILETO ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES.

WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION

EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED. AT THE CONTRACTOR'S EXPENSE, IF THEY ARE TO REMAIN UNUSED FOR MORE THAN SEVEN (7) DAYS.

THE DOWN STREAM SIDE OF ALL STOCKPILES SHALL BE ENCOMPASSED WITH EROSION CONTROL BARRIER.

AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:

A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS

CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS WITHIN THE STAGING AREA. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTANT IN ACCORDANCE WITH EPA WATER OUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPARED OR REMOVED FROM THE SITE.

THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT PERIODICALLY DURING CONSTRUCTION ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2" OR GREATER OR EQUIVALENT SNOWFALL AND DURING WINTER SHUTDOWN PERIOD. THE PROJECT SHALL ADDITIONALLY BE INSPECTED BY THE RESIDENT ENGINEER ON A BI-WEEKLY BASIS TO DETERMINE THAT THE EROSION AND SEDIMENT CONTROL EFFORTS ARE IN PLACE AND EFFECTIVE AND IF OTHER EROSION CONTROL WORK IS NECESSARY.

SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCIDENTAL TO THE CONTRACT.

THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCIDENTAL TO THE CONTRACT.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING SOIL CONTAMINATION FROM BUILDING MATERIALS, FERTILIZERS, CHEMICALS, PAVEMENT MARKING, WASTE PILES, FUEL CONTAINMENT, AND ANY OTHER POTENTIAL HAZARDOUS MATERIALS THAT MAY EXIST ONSITE.

NO DEDICATED CONCRETE OR ASPHALT BATCH PLANTS SHALL BE LOCATED ON THIS SITE.

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED.

COST OF MAINTAINING THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE INCIDENTAL TO THE CONTRACT.

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RE-SEEDED AND/OR SODDED

MAINTENANCE AFTER CONSTRUCTION:

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE OF TEMPORARY AND PERMANENT EROSION CONTROL SYSTEMS UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR.

### DOCUMENTATION:

PRIOR TO BEGINNING WORK. THE CONTRACTOR SHALL COMPLETE AND SUBMIT A "NOTICE OF INTENT (NOI)" PROPERLY SIGNED TO THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY

PRIOR TO BEGINNING WORK. THE CONTRACTOR SHALL POST A SIGN OR OTHER NOTICE NEAR THE MAIN ENTRANCE OF THE CONSTRUCTION SITE. IF THIS IS NOT POSSIBLE, THEN IT MAY BE PERMITTED TO POST THIS NOTICE IN A LOCAL PUBLIC BUILDING. THE SIGN OR NOTICE MUST CONTAIN THE FOLLOWING:

A COPY OF THE COMPLETED NOTICE OF INTENT (NOI) AS SUBMITTED TO THE IEPA 2. THE LOCATION OF THE SWPPP AND NAME AND 24/7 TELEPHONE NUMBER OF THE CONTACT PERSON.

THROUGHOUT CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN AND UPDATE AN "AS-BUILT" SET OF STORM WATER POLLUTION PREVENTION PLANS IN THE PROJECT FILES. THE SWPPP SHALL BE UPDATED WITHIN 7-DAYS OF ANY MODIFICATIONS TO THE PLANS. THE SWPPP AND ALL REVISIONS SHALL BE RETAINED FOR THREE YEARS AFTER FINAL STABILIZATION OF THE SITE, WHICH SHALL BE DEFINED AS VEGETATION COVER OF AT LEAST 70% OF HISTORIC CONDITIONS

A STORM WATER POLLUTION PREVENTION PLAN EROSION CONTROL INSPECTION REPORT (FORM BC 2259) SHALL BE BE COMPLETED WITH INSPECTION FREQUENCIES AS OUTLINED HEREIN. SWPPP REPORTS SHALL BE RETAINED FOR THREE YEARS AFTER THE DATE OF FINAL STABILIZATION AS DEFINED HEREIN.

ANY VIOLATION OF THE PROVISIONS OF THE PLAN IS IDENTIFIED DURING THE CONDUCT OF THE CONSTRUCTION COVERED IN THIS PLAN, THE ENGINEER AND/OR CONTRACTOR SHALL COMPLETE AND FILE AN "INCIDENT OF NONCOMPLIANCE (ION)" REPORT FOR THE IDENTIFIED VIOLATION. THE FORMS SHALL BE AS PROVIDED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY, AND SHALL INCLUDE SPECIFIC INFORMATION ON THE INCIDENT THAT CAUSED NONCOMPLIANCE, ACTIONS THAT WERE TAKEN TO CORRECT THE NONCOMPLIANCE AND TO PREVENT ITS' REOCCURRENCE, AND A STATEMENT DETAILING ANY ENVIRONMENTAL IMPACT WHICH MAY HAVE RESULTED FROM THE NONCOMPLIANCE. ALL REPORTS OF NONCOMPLIANCE SHALL BE SIGNED BY A RESPONSIBLE AUTHORITY IN ACCORDANCE WITH PART VI. G. OF THE GENERAL PERMIT.

AFTER PROJECT FINAL ACCEPTANCE. THE CONTRACTOR SHALL COMPLETE AND SUBMIT A "NOTICE OF TERMINATION (NOT)" FORM PROPERLY SIGNED TO THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY. FORMS FOR THE IEPA SHALL BE MAILED TO THE FOLLOWING ADDRESS'

> NPDES PERMIT # DATE ISSUED DATE EXPIRED

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL, MAIL CODE #15 ATTN: PERMIT SECTION 1021 NORTH GRAND AVENUE EAST P.O. BOX 19276 SPRINGFIELD, ILLINOIS 62794-9276

<u>GENEF</u>	RAL NOTES FOR SOIL EROSION AND SED	MENT CONTROL:		IL. CONTRA	CT: PA061	
1.	<ol> <li>ALL TREE PROTECTION, SEDIMENT CONTROL MEASURES, AND PERMANENT AND TEMPORARY STORM WATER PRACTICES SHALL BE IN PLACE PRIOR TO STARTING CONSTRUCTION.</li> </ol>				ITEM: 104 PWK-455	A 2
2.	NO WORK SHALL BE PERFORMED IN ISOLATED FROM CONCENTRATED FLOWS FOR ISOLATION WILL NOT BE ACCEPTABL	FLOWING WATER. WORK IN AND NEAR OR STREAM FLOWS AT ALL TIMES. THE E.	FLOWING WATER SHALL BE USE OF EARTHEN MATERIAL	S.B.G. PROJE	CT:3-17-SBG	GP-133/139/TBD
3.	CONSTRUCTION MATERIALS AND/OR OTH THE PATH OF STREAM FLOW.	ER STOCKPILES SHALL NOT BE LOCATED	ON STREAM BANKS NOR IN			
4.	TEMPORARY EROSION CONTROL DEVIC DIRECTED BY THE ENGINEER.	S SHALL BE CONSTRUCTED AS SHOW	IN ON THE PLANS OR AS			
5.	PERMANENT SEEDING SHALL BE USE CONTRACTOR PROLONG GRADING OR SH AT ONE TIME.	D WHENEVER POSSIBLE. UNDER NO APING SO THAT THE ENTIRE PROJECT CA	CIRCUMSTANCES SHALL THE IN BE PERMANENTLY SEEDED		BY	DATE
6.	THE CONTRACTOR SHALL INSPECT A NECESSARY. ADJACENT STREETS SHALL	DJACENT STREETS DAILY AND CLEAN BE KEPT FREE OF SOIL AND DEBRIS.	ADJACENT STREETS WHEN			
7.	SHOULD IT BE NECESSARY TO REMOVE CONTRACTOR SHALL FIRST OBTAIN PERI THE SAME DAY. THE COST OF REMOVIN THE CONTRACT.	ANY EROSION CONTROL DEVICES FOR C IISSION AND SHALL REPLACE AND/OR RE G AND REPLACING THE DEVICE SHALL BE	ONSTRUCTION REASONS, THE PAIR THE REMOVED DEVICES CONSIDERED INCIDENTAL TO	0	1	2
8.	ALL OTHER SOIL EROSION AND SEDIMI RESIDENT ENGINEER, COOK COUNTY, CH IEPA SHALL BE IMPLEMENTED IMMEDIATE	NT CONTROL DEVICES AND MEASURES I ICAGO EXECUTIVE AIRPORT, IDOT DIVISION LY UPON NOTIFICATION OF THE CONTRAC	DEEMED NECESSARY BY THE I OF AERONAUTICS, AND THE TOR.	THIS BAR AT FULL	IS EQUAL SCALE (3-	TO 2" 4X22).
9.	THE CONTRACTOR SHALL PROVIDE LO ENGINEER, PRIOR TO ANY CONCRETE P OF WATER. LOCATIONS SHALL BE A ADDITIONALLY THE CONTRACTOR SHALL FINISHING TOOLS. ALL WASTE WATER APPROVED CONCRETE WASHOUT FACILIT	CATIONS FOR CONCRETE TRUCK WASHO DURS. THESE LOCATIONS SHALL NOT BE PROVED BY THE ENGINEER PRIOR T PROVIDE ADEQUATE FACILITIES TO WASH AND EXCESS CONCRETE MATERIALS SH	UT, AS APPROVED BY THE NEAR ANY STREAM OR BODY O ANY CONCRETE POURS. OUT PAVING EQUIPMENT AND IALL BE CONTAINED BY AN			Z
10.	THE CONTRACTOR SHALL COORDINATE MEASURES ARE CONSISTENT BETWEEN A	CONSTRUCTION ACTIVITIES TO ENSUR LL PROJECT PHASES AND ALL SUB-CONT	E THAT EROSION CONTROL RACTORS.	g		L L
11.	THE CONTRACTOR SHALL TAKE ALL P SEDIMENT, CONSTRUCTION EQUIPMENT, DEBRIS OR ANY CONSTRUCTION MATERIA	RECAUTIONS TO PROTECT WETLANDS TO OR BY HIS PERSONNEL. THE CONTRA L IS NOT DISPOSED OF IN THE WETLAND	REMAIN FROM DAMAGE BY CTOR SHALL ASSURE THAT S.	ICHII		NO -
12.	WATER PUMPED OR OTHERWISE DISCHA FILTERED BY AN APPROVED MEANS.	RGED FROM THE SITE DURING CONSTRUC	TION DEWATERING SHALL BE	A L NO   A L I 1		
13.	SEDIMENT COLLECTED DURING CONSTR SHALL BE DISPOSED OF ON A REGUL SYSTEMS WHEN THE HEIGHT OF THE S RECOMMENDED BY THE MANUFACTURER,	UCTION BY THE VARIOUS TEMPORARY AR BASIS. SEDIMENT SHALL BE REMOVE DIMENT EXCEEDS ONE-HALF OF THE HE WHICHEVER IS LESS.	EROSION CONTROL SYSTEMS D FROM EROSION CONTROL IGHT OF THE DEVICE OR AS	AIRPOR HTS, IL RUNW,		REVE
14.	ALL EROSION CONTROL MEASURES THROUGHOUT THE PERIOD OF LAND DIS MEASURES ARE OPERATIONAL.	SHALL BE KEPT OPERATIONAL AND TURBANCE UNTIL PERMANENT SOIL EROS	MAINTAINED CONTINUOUSLY ION AND SEDIMENT CONTROL			N PF
15. THE CONDITION OF THE CONSTRUCTION SITE FOR WINTER SHUTDOWN SHALL BE ADDRESSED EARLY IN THE FALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILIZED WITH TEMPORARY AND/OR PERMANENT VEGETATIVE COVER. ALL OPEN AREAS THAT ARE TO REMAIN IDLE THROUGHOUT THE WINTER SHALL RECEIVE TEMPORARY EROSION CONTROL MEASURES INCLUDING TEMPORARY SEEDING, MULCHING AND/OR EROSION CONTROL BLANKET PRIOR TO THE END OF THE FALL GROWING SEASON. THE AREAS TO BE WORKED BEYOND THE END OF THE GROWING SEASON MUST INCORPORATE SOIL STABILIZATION MEASURES THAT DO NOT RELY ON VEGETATIVE COVER SUCH AS EROSION CONTROL BLANKET AND HEAVY MULCHING.			E ADDRESSED EARLY IN THE MAY BE STABILIZED WITH HAT ARE TO REMAIN IDLE URES INCLUDING TEMPORARY ND OF THE FALL GROWING ON MUST INCORPORATE SOIL EROSION CONTROL BLANKET	cago execu G/Prospect Runway 12/3		OLLUTIO
16.	PERMANENT STABILIZATION SHALL BE CO	MPLETED WITHIN 7 DAYS FOR AREAS WH	ERE WORK IS COMPLETED.	풋그뜨		ዲ ሪ ሪ
CONTR THIS O DESCR PROTE	RACTOR CERTIFICATION STATEMENT CERTIFICATION STATEMENT IS A PART OF RIBED BELOW IN ACCORDANCE WITH NPD CITION AGENCY.	THE STORM WATER POLLUTION PREVENTIN S PERMIT NO. ILR10 ISSUED BY THE ILL	ON PLAN FOR THE PROJECT INOIS ENVIRONMENTAL	ABILITA;		ATEF 40TE
PROJE	CT INFORMATION:			1		≧∠
ROUTE	CHICAGO EXECUTIVE AIRPORT	MARKED:	AND RUNWAY LIGHTING			22
SECTIO	DN: <u>13</u>	PROJECT NUMBER: PWK-4552	30 (TPD (DA061)			<u></u>
COUN	TY: <u>COOK</u>	CONTRACT NUMBER: 3-17-386P-13371	39/180 (PA061)			S
I CER POLLU DISCH CERTIF	TIFY UNDER PENALTY OF LAW THAT I UN ITION DISCHARGE ELIMINATION SYSTEM (N ARGES ASSOCIATED WITH INDUSTRIAL ACT FICATION.	DERSTAND THE TERMS AND CONDITIONS ( PDES) PERMIT (ILR10) THAT AUTHORIZES VITY FROM THE CONSTRUCTION SITE IDEN	DF THE GENERAL NATIONAL THE STORM WATER ITIFIED AS PART OF THIS			
SIGNA	TURE:	DATE:		, IN .		VE
PRINT	ED NAME:	TITLE:		Pyright	2	CUTION
NAME	OF FIRM:			© co ERS	1900	IRPI
STREE	T ADDRESS:			RPH	4	0
CITY, PHONE	STATE, ZIP: E NUMBER:				Ω.	æ
THE II CONTR REQUI	NFORMATION WITHIN THIS BOX SHALL BE RACT TO OBTAIN THE REQUIRED NPDES I REMENT.	COMPLETED BY THE CONTRACTOR AFTER ERMIT FROM IEPA. COMPLETION OF THIS	THE AWARD OF THE IS A CONTRACT		License	SHIG
	RECORD OF	SITE DISTURBANCE AND STABILIZATION				
MAJOF	GRADING ACTIVITIES:			DESIGN BY:		DKP
MAJOF	GRADING ACTIVITIES:	BEGINNING DATE:		DRAWN BY:		JRO
SITE S	STABILIZATION:	BEGINNING DATE:		CHECKED BY:		DKP
				APPROVED BY	:	KWS
SHE S	OCATION:	COMPLETION DATE:		JOB No:	16200	04-00
CONST	IRUCTION CEASED: EXPLANATION:	BEGINNING DATE: COMPLETION DATE:		000 NO.		, ,,-,,
THE II ACCOP NOTED	NFORMATION WITHIN THIS BOX SHALL BE RDANCE WITH THE NPDES GENERAL PERI DIRECTLY ON THE SWPPP SITE MAP.	COMPLETED BY THE CONTRACTOR AS CO IT FOR STORMWATER DISCHARGES. THIS	INSTRUCTION PROGRESSES IN INFORMATION MAY ALSO BE	SHEET 11	OF 3	7 SHEETS

GENERAL NOTES FOR SOIL EROSION AND SE	DIMENT CONTROL:	IL. CONTRAC	T: PA061
I. ALL IREE PROTECTION, SEDIMENT C PRACTICES SHALL BE IN PLACE PRIOF	IL. LETTING	PWK-4552	
<ol> <li>NO WORK SHALL BE PERFORMED I ISOLATED FROM CONCENTRATED FLOW FOR ISOLATION WILL NOT BE ACCEPTA</li> </ol>	N FLOWING WATER. WORK IN AND NEAR FLOWING WATER SHALL BE S OR STREAM FLOWS AT ALL TIMES. THE USE OF EARTHEN MATERIAL IBLE.	S.B.G. PROJEC	T:3-17-SBGP-133/139/TBD
<ol> <li>CONSTRUCTION MATERIALS AND/OR O THE PATH OF STREAM FLOW.</li> </ol>	THER STOCKPILES SHALL NOT BE LOCATED ON STREAM BANKS NOR IN		
<ol> <li>TEMPORARY EROSION CONTROL DEV DIRECTED BY THE ENGINEER.</li> </ol>	ICES SHALL BE CONSTRUCTED AS SHOWN ON THE PLANS OR AS		
<ol> <li>PERMANENT SEEDING SHALL BE U CONTRACTOR PROLONG GRADING OR AT ONE TIME.</li> </ol>	SED WHENEVER POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDED	RE NUMBER	VISIONS BY DATE
<ol> <li>THE CONTRACTOR SHALL INSPECT NECESSARY. ADJACENT STREETS SHAL</li> </ol>	ADJACENT STREETS DAILY AND CLEAN ADJACENT STREETS WHEN L BE KEPT FREE OF SOIL AND DEBRIS.		
<ol> <li>SHOULD IT BE NECESSARY TO REMO CONTRACTOR SHALL FIRST OBTAIN PE THE SAME DAY. THE COST OF REMOV THE CONTRACT.</li> </ol>	/E ANY EROSION CONTROL DEVICES FOR CONSTRUCTION REASONS, THE RMISSION AND SHALL REPLACE AND/OR REPAIR THE REMOVED DEVICES ING AND REPLACING THE DEVICE SHALL BE CONSIDERED INCIDENTAL TO	0	1 2
<ol> <li>ALL OTHER SOIL EROSION AND SED RESIDENT ENGINEER, COOK COUNTY, IEPA SHALL BE IMPLEMENTED IMMEDIA</li> </ol>	MENT CONTROL DEVICES AND MEASURES DEEMED NECESSARY BY THE CHICAGO EXECUTIVE AIRPORT, IDOT DIVISION OF AERONAUTICS, AND THE TELY UPON NOTIFICATION OF THE CONTRACTOR.	THIS BAR AT FULL	IS EQUAL TO 2" SCALE (34X22).
<ol> <li>THE CONTRACTOR SHALL PROVIDE ENGINEER, PRIOR TO ANY CONCRETE OF WATER. LOCATIONS SHALL BE ADDITIONALLY THE CONTRACTOR SHAL FINISHING TOOLS. ALL WASTE WATEI APPROVED CONCRETE WASHOUT FACIL</li> </ol>	OCATIONS FOR CONCRETE TRUCK WASHOUT, AS APPROVED BY THE POURS. THESE LOCATIONS SHALL NOT BE NEAR ANY STREAM OR BODY APPROVED BY THE ENGINEER PRIOR TO ANY CONCRETE POURS. L PROVIDE ADEQUATE FACILITIES TO WASH OUT PAVING EQUIPMENT AND R AND EXCESS CONCRETE MATERIALS SHALL BE CONTAINED BY AN ITY.		N
10. THE CONTRACTOR SHALL COORDINA MEASURES ARE CONSISTENT BETWEEN	TE CONSTRUCTION ACTIVITIES TO ENSURE THAT EROSION CONTROL ALL PROJECT PHASES AND ALL SUB-CONTRACTORS.	g	
11. THE CONTRACTOR SHALL TAKE ALL SEDIMENT, CONSTRUCTION EQUIPMEN DEBRIS OR ANY CONSTRUCTION MATEI	PRECAUTIONS TO PROTECT WETLANDS TO REMAIN FROM DAMAGE BY T, OR BY HIS PERSONNEL. THE CONTRACTOR SHALL ASSURE THAT RIAL IS NOT DISPOSED OF IN THE WETLANDS.	NGHT	NO
12. WATER PUMPED OR OTHERWISE DISCI FILTERED BY AN APPROVED MEANS.	HARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE		
13. SEDIMENT COLLECTED DURING CONS SHALL BE DISPOSED OF ON A REG SYSTEMS WHEN THE HEIGHT OF THE RECOMMENDED BY THE MANUFACTURE	TRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS ULAR BASIS. SEDIMENT SHALL BE REMOVED FROM EROSION CONTROL SEDIMENT EXCEEDS ONE-HALF OF THE HEIGHT OF THE DEVICE OR AS R, WHICHEVER IS LESS.	AIRPOR AIRPOR ALTS, IL	REVE - SHE
<ol> <li>ALL EROSION CONTROL MEASURES THROUGHOUT THE PERIOD OF LAND MEASURES ARE OPERATIONAL.</li> </ol>		N PF	
15. THE CONDITION OF THE CONSTRUCTIN FALL GROWING SEASON SO THAT TEMPORARY AND/OR PERMANENT V. THROUGHOUT THE WINTER SHALL REU SEEDING, MULCHING AND/OR EROSI SEASON. THE AREAS TO BE WORKED STABILIZATION MEASURES THAT DO N AND HEAVY MULCHING.	CAGO EXECU G/PROSPEC1		
16. PERMANENT STABILIZATION SHALL BE	COMPLETED WITHIN 7 DAYS FOR AREAS WHERE WORK IS COMPLETED.		S A
CONTRACTOR CERTIFICATION STATEMENT THIS CERTIFICATION STATEMENT IS A PART O DESCRIBED BELOW IN ACCORDANCE WITH NE PROTECTION ACENCY	OF THE STORM WATER POLLUTION PREVENTION PLAN FOR THE PROJECT DES PERMIT NO. ILR10 ISSUED BY THE ILLINOIS ENVIRONMENTAL	WHEE VILLE	
PROJECT INFORMATION:		計	≥ z
ROUTE: CHICAGO EXECUTIVE AIRPORT	MARKED:		N N
SECTION: 13	PROJECT NUMBER: PWK-4552		0
COUNTY: COOK	CONTRACT NUMBER: 3-17-SBGF-133/139/1BD (PA061)		S.
I CERTIFY UNDER PENALTY OF LAW THAT I POLLUTION DISCHARGE ELIMINATION SYSTEM DISCHARGES ASSOCIATED WITH INDUSTRIAL A CERTIFICATION.	UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL (NPDES) PERMIT (ILR10) THAT AUTHORIZES THE STORM WATER CTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS		
SIGNATURE:	DATE:	t cmr.	IVE
PRINTED NAME:	TITLE:	opyright TILL	CUT
NAME OF FIRM:	_	LER &	EXE
STREET ADDRESS:	—		
CITY, STATE, ZIP: PHONE NUMBER:	_		
THE INFORMATION WITHIN THIS BOX SHALL I CONTRACT TO OBTAIN THE REQUIRED NPDES REQUIREMENT.	SE COMPLETED BY THE CONTRACTOR AFTER THE AWARD OF THE PERMIT FROM IEPA. COMPLETION OF THIS IS A CONTRACT		
RECORD OF	SITE DISTURBANCE AND STABILIZATION		
MAJOR GRADING ACTIVITIES: LOCATION:	BEGINNING DATE:	DESIGN BY:	DKP
MAJOR GRADING ACTIVITIES: LOCATION:	BEGINNING DATE:	DRAWN BY:	JRO
SITE STABILIZATION:	BEGINNING DATE:	CHECKED BY:	DKP
SITE STABILIZATION:	BEGINNING DATE:	DATE:	06/08/2018
LOCATION:	COMPLETION DATE: BEGINNING DATE:	JOB No:	16290-04-00
			FINAL
ACCORDANCE WITH THE NPDES GENERAL PE NOTED DIRECTLY ON THE SWPPP SITE MAP.	DE COMPLETED BT THE CONTRACTOR AS CONSTRUCTION PROGRESSES IN RMIT FOR STORMWATER DISCHARGES. THIS INFORMATION MAY ALSO BE	SHEET 11	OF 37 SHEETS

<u>GENEF</u>	RAL NOTES FOR SOIL EROSION AND SED	MENT CONTROL:		IL. CONTRA	CT: PA061	
1.	<ol> <li>ALL TREE PROTECTION, SEDIMENT CONTROL MEASURES, AND PERMANENT AND TEMPORARY STORM WATER PRACTICES SHALL BE IN PLACE PRIOR TO STARTING CONSTRUCTION.</li> </ol>				ITEM: 104 PWK-455	A 2
2.	NO WORK SHALL BE PERFORMED IN ISOLATED FROM CONCENTRATED FLOWS FOR ISOLATION WILL NOT BE ACCEPTABL	FLOWING WATER. WORK IN AND NEAR OR STREAM FLOWS AT ALL TIMES. THE E.	FLOWING WATER SHALL BE USE OF EARTHEN MATERIAL	S.B.G. PROJE	CT:3-17-SBG	GP-133/139/TBD
3.	CONSTRUCTION MATERIALS AND/OR OTH THE PATH OF STREAM FLOW.	ER STOCKPILES SHALL NOT BE LOCATED	ON STREAM BANKS NOR IN			
4.	TEMPORARY EROSION CONTROL DEVIC DIRECTED BY THE ENGINEER.	S SHALL BE CONSTRUCTED AS SHOW	IN ON THE PLANS OR AS			
5.	PERMANENT SEEDING SHALL BE USE CONTRACTOR PROLONG GRADING OR SH AT ONE TIME.	D WHENEVER POSSIBLE. UNDER NO APING SO THAT THE ENTIRE PROJECT CA	CIRCUMSTANCES SHALL THE IN BE PERMANENTLY SEEDED		BY	DATE
6.	THE CONTRACTOR SHALL INSPECT A NECESSARY. ADJACENT STREETS SHALL	DJACENT STREETS DAILY AND CLEAN BE KEPT FREE OF SOIL AND DEBRIS.	ADJACENT STREETS WHEN			
7.	SHOULD IT BE NECESSARY TO REMOVE CONTRACTOR SHALL FIRST OBTAIN PERI THE SAME DAY. THE COST OF REMOVIN THE CONTRACT.	ANY EROSION CONTROL DEVICES FOR C IISSION AND SHALL REPLACE AND/OR RE G AND REPLACING THE DEVICE SHALL BE	ONSTRUCTION REASONS, THE PAIR THE REMOVED DEVICES CONSIDERED INCIDENTAL TO	0	1	2
8.	ALL OTHER SOIL EROSION AND SEDIMI RESIDENT ENGINEER, COOK COUNTY, CH IEPA SHALL BE IMPLEMENTED IMMEDIATE	NT CONTROL DEVICES AND MEASURES I ICAGO EXECUTIVE AIRPORT, IDOT DIVISION LY UPON NOTIFICATION OF THE CONTRAC	DEEMED NECESSARY BY THE I OF AERONAUTICS, AND THE TOR.	THIS BAR AT FULL	IS EQUAL SCALE (3-	TO 2" 4X22).
9.	THE CONTRACTOR SHALL PROVIDE LO ENGINEER, PRIOR TO ANY CONCRETE P OF WATER. LOCATIONS SHALL BE A ADDITIONALLY THE CONTRACTOR SHALL FINISHING TOOLS. ALL WASTE WATER APPROVED CONCRETE WASHOUT FACILIT	CATIONS FOR CONCRETE TRUCK WASHO DURS. THESE LOCATIONS SHALL NOT BE PROVED BY THE ENGINEER PRIOR T PROVIDE ADEQUATE FACILITIES TO WASH AND EXCESS CONCRETE MATERIALS SH	UT, AS APPROVED BY THE NEAR ANY STREAM OR BODY O ANY CONCRETE POURS. OUT PAVING EQUIPMENT AND IALL BE CONTAINED BY AN			Z
10.	THE CONTRACTOR SHALL COORDINATE MEASURES ARE CONSISTENT BETWEEN A	CONSTRUCTION ACTIVITIES TO ENSUR LL PROJECT PHASES AND ALL SUB-CONT	E THAT EROSION CONTROL RACTORS.	g		L L
11.	THE CONTRACTOR SHALL TAKE ALL P SEDIMENT, CONSTRUCTION EQUIPMENT, DEBRIS OR ANY CONSTRUCTION MATERIA	RECAUTIONS TO PROTECT WETLANDS TO OR BY HIS PERSONNEL. THE CONTRA L IS NOT DISPOSED OF IN THE WETLAND	REMAIN FROM DAMAGE BY CTOR SHALL ASSURE THAT S.	ICHII		NO -
12.	WATER PUMPED OR OTHERWISE DISCHA FILTERED BY AN APPROVED MEANS.	RGED FROM THE SITE DURING CONSTRUC	TION DEWATERING SHALL BE	A L NO   A L I 1		
13.	SEDIMENT COLLECTED DURING CONSTR SHALL BE DISPOSED OF ON A REGUL SYSTEMS WHEN THE HEIGHT OF THE S RECOMMENDED BY THE MANUFACTURER,	UCTION BY THE VARIOUS TEMPORARY AR BASIS. SEDIMENT SHALL BE REMOVE DIMENT EXCEEDS ONE-HALF OF THE HE WHICHEVER IS LESS.	EROSION CONTROL SYSTEMS D FROM EROSION CONTROL IGHT OF THE DEVICE OR AS	AIRPOR HTS, IL RUNW,		REVE
14.	ALL EROSION CONTROL MEASURES THROUGHOUT THE PERIOD OF LAND DIS MEASURES ARE OPERATIONAL.	SHALL BE KEPT OPERATIONAL AND TURBANCE UNTIL PERMANENT SOIL EROS	MAINTAINED CONTINUOUSLY ION AND SEDIMENT CONTROL			N PF
15. THE CONDITION OF THE CONSTRUCTION SITE FOR WINTER SHUTDOWN SHALL BE ADDRESSED EARLY IN THE FALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILIZED WITH TEMPORARY AND/OR PERMANENT VEGETATIVE COVER. ALL OPEN AREAS THAT ARE TO REMAIN IDLE THROUGHOUT THE WINTER SHALL RECEIVE TEMPORARY EROSION CONTROL MEASURES INCLUDING TEMPORARY SEEDING, MULCHING AND/OR EROSION CONTROL BLANKET PRIOR TO THE END OF THE FALL GROWING SEASON. THE AREAS TO BE WORKED BEYOND THE END OF THE GROWING SEASON MUST INCORPORATE SOIL STABILIZATION MEASURES THAT DO NOT RELY ON VEGETATIVE COVER SUCH AS EROSION CONTROL BLANKET AND HEAVY MULCHING.			E ADDRESSED EARLY IN THE MAY BE STABILIZED WITH HAT ARE TO REMAIN IDLE URES INCLUDING TEMPORARY ND OF THE FALL GROWING ON MUST INCORPORATE SOIL EROSION CONTROL BLANKET	cago execu G/Prospect Runway 12/3		OLLUTIO
16.	PERMANENT STABILIZATION SHALL BE CO	MPLETED WITHIN 7 DAYS FOR AREAS WH	ERE WORK IS COMPLETED.	풋그뜨		ዲ ሪ ሪ
CONTR THIS O DESCR PROTE	RACTOR CERTIFICATION STATEMENT CERTIFICATION STATEMENT IS A PART OF RIBED BELOW IN ACCORDANCE WITH NPD CITION AGENCY.	THE STORM WATER POLLUTION PREVENTIN S PERMIT NO. ILR10 ISSUED BY THE ILL	ON PLAN FOR THE PROJECT INOIS ENVIRONMENTAL	ABILITA;		ATEF 40TE
PROJE	CT INFORMATION:			1		≧∠
ROUTE	CHICAGO EXECUTIVE AIRPORT	MARKED:	AND RUNWAY LIGHTING			22
SECTIO	DN: <u>13</u>	PROJECT NUMBER: PWK-4552	30 / TPD (PAO61)			<u></u>
COUN	TY: <u>COOK</u>	CONTRACT NUMBER: 3-17-386P-13371	39/180 (PA061)			S
I CER POLLU DISCH CERTIF	TIFY UNDER PENALTY OF LAW THAT I UN ITION DISCHARGE ELIMINATION SYSTEM (N ARGES ASSOCIATED WITH INDUSTRIAL ACT FICATION.	DERSTAND THE TERMS AND CONDITIONS ( PDES) PERMIT (ILR10) THAT AUTHORIZES VITY FROM THE CONSTRUCTION SITE IDEN	DF THE GENERAL NATIONAL THE STORM WATER MIFIED AS PART OF THIS			
SIGNA	TURE:	DATE:		, IN .		VE
PRINT	ED NAME:	TITLE:		Pyright	2	CUTION
NAME	OF FIRM:			© co ERS	1900	IRPI
STREE	T ADDRESS:			RPH	4	0
CITY, PHONE	STATE, ZIP: E NUMBER:				Ω.	æ
THE II CONTR REQUI	NFORMATION WITHIN THIS BOX SHALL BE RACT TO OBTAIN THE REQUIRED NPDES I REMENT.	COMPLETED BY THE CONTRACTOR AFTER ERMIT FROM IEPA. COMPLETION OF THIS	THE AWARD OF THE IS A CONTRACT	CONSULT CONSULT	License	SHIG
	RECORD OF	SITE DISTURBANCE AND STABILIZATION				
MAJOF	GRADING ACTIVITIES:			DESIGN BY:		DKP
MAJOF	GRADING ACTIVITIES:	BEGINNING DATE:		DRAWN BY:		JRO
SITE S	STABILIZATION:	BEGINNING DATE:		CHECKED BY:		DKP
				APPROVED BY	:	KWS
SHE S	OCATION:	COMPLETION DATE:		JOB No:	16200	04-00
CONST	IRUCTION CEASED: EXPLANATION:	BEGINNING DATE: COMPLETION DATE:		000 NO.		, ,,-,,
THE II ACCOP NOTED	NFORMATION WITHIN THIS BOX SHALL BE RDANCE WITH THE NPDES GENERAL PERI DIRECTLY ON THE SWPPP SITE MAP.	COMPLETED BY THE CONTRACTOR AS CO IT FOR STORMWATER DISCHARGES. THIS	INSTRUCTION PROGRESSES IN INFORMATION MAY ALSO BE	SHEET 11	OF 3	7 SHEETS

GENERAL NOTES FOR SOIL EROSION AND SE	DIMENT CONTROL:	IL. CONTRA	CT: PA061
I. ALL IREE PROTECTION, SEDIMENT C PRACTICES SHALL BE IN PLACE PRIOF	IL. LETTING	PWK-4552	
<ol> <li>NO WORK SHALL BE PERFORMED II ISOLATED FROM CONCENTRATED FLOW FOR ISOLATION WILL NOT BE ACCEPTA</li> </ol>	N FLOWING WATER. WORK IN AND NEAR FLOWING WATER SHALL BE S OR STREAM FLOWS AT ALL TIMES. THE USE OF EARTHEN MATERIAL IBLE.	S.B.G. PROJE	CT:3-17-SBGP-133/139/TBD
<ol> <li>CONSTRUCTION MATERIALS AND/OR O THE PATH OF STREAM FLOW.</li> </ol>	THER STOCKPILES SHALL NOT BE LOCATED ON STREAM BANKS NOR IN		
<ol> <li>TEMPORARY EROSION CONTROL DEV DIRECTED BY THE ENGINEER.</li> </ol>	ICES SHALL BE CONSTRUCTED AS SHOWN ON THE PLANS OR AS		
5. PERMANENT SEEDING SHALL BE U: CONTRACTOR PROLONG GRADING OR AT ONE TIME.	SED WHENEVER POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDED	NUMBER	BY DATE
<ol> <li>THE CONTRACTOR SHALL INSPECT NECESSARY. ADJACENT STREETS SHALL</li> </ol>	ADJACENT STREETS DAILY AND CLEAN ADJACENT STREETS WHEN L BE KEPT FREE OF SOIL AND DEBRIS.		
<ol> <li>SHOULD IT BE NECESSARY TO REMOVING CONTRACTOR SHALL FIRST OBTAIN PE THE SAME DAY. THE COST OF REMOVITHE CONTRACT.</li> </ol>	VE ANY EROSION CONTROL DEVICES FOR CONSTRUCTION REASONS, THE RMISSION AND SHALL REPLACE AND/OR REPAIR THE REMOVED DEVICES ING AND REPLACING THE DEVICE SHALL BE CONSIDERED INCIDENTAL TO	0	1 2
<ol> <li>ALL OTHER SOIL EROSION AND SEDI RESIDENT ENGINEER, COOK COUNTY, IEPA SHALL BE IMPLEMENTED IMMEDIA</li> </ol>	MENT CONTROL DEVICES AND MEASURES DEEMED NECESSARY BY THE CHICAGO EXECUTIVE AIRPORT, IDOT DIVISION OF AERONAUTICS, AND THE TELY UPON NOTIFICATION OF THE CONTRACTOR.	THIS BAR AT FULL	IS EQUAL TO 2" SCALE (34X22).
<ol> <li>THE CONTRACTOR SHALL PROVIDE I ENGINEER, PRIOR TO ANY CONCRETE OF WATER. LOCATIONS SHALL BE ADDITIONALLY THE CONTRACTOR SHAL FINISHING TOOLS. ALL WASTE WATEI APPROVED CONCRETE WASHOUT FACIL</li> </ol>	OCATIONS FOR CONCRETE TRUCK WASHOUT, AS APPROVED BY THE POURS. THESE LOCATIONS SHALL NOT BE NEAR ANY STREAM OR BODY APPROVED BY THE ENGINEER PRIOR TO ANY CONCRETE POURS. L PROVIDE ADEOUATE FACILITIES TO WASH OUT PAVING EQUIPMENT AND R AND EXCESS CONCRETE MATERIALS SHALL BE CONTAINED BY AN ITY.		A
10. THE CONTRACTOR SHALL COORDINA MEASURES ARE CONSISTENT BETWEEN	TE CONSTRUCTION ACTIVITIES TO ENSURE THAT EROSION CONTROL ALL PROJECT PHASES AND ALL SUB-CONTRACTORS.	<u>g</u>	PL 1
11. THE CONTRACTOR SHALL TAKE ALL SEDIMENT, CONSTRUCTION EQUIPMEN DEBRIS OR ANY CONSTRUCTION MATER	PRECAUTIONS TO PROTECT WETLANDS TO REMAIN FROM DAMAGE BY T, OR BY HIS PERSONNEL. THE CONTRACTOR SHALL ASSURE THAT RIAL IS NOT DISPOSED OF IN THE WETLANDS.	NS I	N L
12. WATER PUMPED OR OTHERWISE DISCH FILTERED BY AN APPROVED MEANS.	HARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE		
13. SEDIMENT COLLECTED DURING CONS SHALL BE DISPOSED OF ON A REG SYSTEMS WHEN THE HEIGHT OF THE RECOMMENDED BY THE MANUFACTURE	TRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS ULAR BASIS. SEDIMENT SHALL BE REMOVED FROM EROSION CONTROL SEDIMENT EXCEEDS ONE-HALF OF THE HEIGHT OF THE DEVICE OR AS R, WHICHEVER IS LESS.	AIRPOR HTS, IL	REVE
<ol> <li>ALL EROSION CONTROL MEASURES THROUGHOUT THE PERIOD OF LAND I MEASURES ARE OPERATIONAL.</li> </ol>		N PF	
15. THE CONDITION OF THE CONSTRUCTION FALL GROWING SEASON SO THAT TEMPORARY AND/OR PERMANENT V THROUGHOUT THE WINTER SHALL REC SEEDING, MULCHING AND/OR EROSIN SEASON. THE AREAS TO BE WORKED STABILIZATION MEASURES THAT DO N AND HEAVY MULCHING.	CAGO EXECU G/PROSPEC1 BUNWAY 12/3		
16. PERMANENT STABILIZATION SHALL BE	COMPLETED WITHIN 7 DAYS FOR AREAS WHERE WORK IS COMPLETED.		A A
CONTRACTOR CERTIFICATION STATEMENT		<u></u> ]  ॅॅॅॅॅॅॅ	μË
THIS CERTIFICATION STATEMENT IS A PART O DESCRIBED BELOW IN ACCORDANCE WITH NF PROTECTION AGENCY.	OF THE STORM WATER POLLUTION PREVENTION PLAN FOR THE PROJECT DES PERMIT NO. ILR'10 ISSUED BY THE ILLINOIS ENVIRONMENTAL		
PROJECT INFORMATION:			N N
ROUTE: CHICAGO EXECUTIVE AIRPORT	MARKED: KEHABILITATE RUNWAY 12/30 AND RUNWAY LIGHTING		RI
SECTION: <u>13</u> COUNTY: <u>COOK</u>	CONTRACT_NUMBER: <u>3-17-SBGP-133/139/TBD</u> (PA061)		1 0 1 0
I CERTIFY UNDER PENALTY OF LAW THAT I I POLLUTION DISCHARGE ELIMINATION SYSTEM DISCHARGES ASSOCIATED WITH INDUSTRIAL A CERTIFICATION.	JNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL (NPDES) PERMIT (ILR10) THAT AUTHORIZES THE STORM WATER CTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS	<u></u>	0
SIGNATURE:	DATE:	CMT. IN	NE .
PRINTED NAME:		yright TILL Y	UTI BRT
NAME OF FIRM:	_	© cor ERS	SOG1:
STREET ADDRESS:	—	RPH.	
CITY, STATE, ZIP: PHONE NUMBER:	_		- 18 18
THE INFORMATION WITHIN THIS BOX SHALL F CONTRACT TO OBTAIN THE REQUIRED NPDES REQUIREMENT.	SE COMPLETED BY THE CONTRACTOR AFTER THE AWARD OF THE PERMIT FROM IEPA. COMPLETION OF THIS IS A CONTRACT		Clicense r
RECORD OF	SITE DISTURBANCE AND STABILIZATION		
MAJOR GRADING ACTIVITIES: LOCATION:	BEGINNING DATE:	DESIGN BY:	DKP
MAJOR GRADING ACTIVITIES: LOCATION:	BEGINNING DATE:	DRAWN BY:	JRO
SITE STABILIZATION:	BEGINNING DATE:	CHECKED BY	DKP
SITE STABILIZATION:	BEGINNING DATE:	DATE:	. NW3 06/08/2018
LOCATION: CONSTRUCTION CEASED:	COMPLETION DATE:	JOB No:	16290-04-00
			FINAL
ACCORDANCE WITH THE NPDES GENERAL PE NOTED DIRECTLY ON THE SWPPP SITE MAP.	RMIT FOR STORMWATER DISCHARGES. THIS INFORMATION MAY ALSO BE	SHEET 11	OF 37 SHEETS

Ś



620B(W).tif ewL0G0\_CE N

> Ϋ́ UPDATE

20 ໝົ







- E EXISTING UNDERDRAIN
- F EXISTING GROUNDLINE



# TURF SHOULDER DETAIL

NOT TO SCALE

NOTES:

- TOPSOIL REQUIRED FOR FILL SHALL BE INCLUDED IN THE COSTS FOR SHOULDER ADJUSTMENT (AR152480)
- LIMITS OF TURF SHOULDER SHALL BE ADJUSTED IN THE FIELD AS REQUIRED.



TAXIWAY TYPICAL SECTION B-B NOT TO SCALE

CEA Alignments.dwg

- (A) NEW VARIABLE DEPTH BITUMINOUS SURFACE MILLING NEW 2\* BITUMINOUS SURFACE COURSE (401) NEW BITUMINOUS SURFACE COURSE LEVELING (AS REQUIRED)(401) NEW BITUMINOUS TACK COAT (603)
- B EXISTING BITUMINOUS PAVEMENT (DEPTH VARIES)
- C EXISTING 7" CRUSHED AGGREGATE BASE COURSE
- D EXISTING 12" POROUS GRANULAR EMBANKMENT
- G SHOULDER ADJUSTMENT, TOPSOILING, SEEDING AND HEAVY DUTY MULCHING

IL. CONTRACT: PA061 IL. LETTING ITEM:10A IL. PROJECT: PWK-4552 S.B.G. PROJECT:3-17-SBGP-133/139/TBD					
	REVIS		DATE		
NUMBER	B	T	DATE		
0		1	2		
THIS B, AT FUI	AR IS LL SCA	EQUAL ALE (34	TO 2" 4X22).		
CHICAGO EXECUTIVE AIRPORT WHEELING/PROSPECT HEIGHTS, ILLINOIS	HEHABILITATE HUNWAY 12/30 AND HUNWAY LIGHTING		TYPICAL SECTIONS		
CCAPACITY CONT. INC. CCAPACITY, INC.	CONSULTING ENGINEERS License No. 184-000613		<b>CHICEGO</b> AIRPORT		
DESIGN BY:			KWS		
DRAWN BY:			JRO		
CHECKED B	IY:		DKP		
APPROVED	BY:		DKP		
DATE:		06/08	8/2018		
JOB No:		16290	-04-00		
FINAL					















DATE:



# NOTES

- THE CONTRACTOR SHALL VISIT THE PROJECT SITE AND ACQUAINT HIMSELF WITH THE REQUIRED WORK. CONTRACTOR SHALL BE FAMILIAR TO THE SITE AND REQUIRED WORK PRIOR TO BID. SITE VISITS SHALL BE COORDINATED WITH THE AIRPORT EXECUTIVE DIRECTOR.
- PRIOR TO ORDERING NEW MATERIAL, CONTRACTOR SHALL FIELD MEASURE FOR JOINTING MATERIAL SIZES AND AMOUNT. MEASUREMENTS SHALL ALSO DETERMINE BACKER ROD SIZE AND QUANTITIES. ALSO PER NEW JOINTS DETAILS, DEPTH OF NEW JOINT SEALANT SHALL BE AS RECOMMENDED BY MANUFACTURER. NO EXTRA COMPENSATION WILL BE MADE FOR EXCESS MATERIALS NOT USED.
- FOR VARYING JOINT WIDTHS AND DEPTHS, THERE SHALL BE NO ADDITIONAL COST FOR DEEPER SAWCUTS, LARGER BACKER RODS AND SEALANT MATERIAL USED.
- 4. CONTRACTOR SHALL CONSTRUCT A 1/4" CHAMFER ON ALL CONCRETE JOINTS PER THE DETAIL ON THIS SHEET AT NO ADDITIONAL COST. CHAMFERS ARE NOT NEEDED WHERE CHAMFER IS NOT CONSTRUCTIBLE AT SMALLER SPALLING AREAS.



022701		
EXISTING JOINT WIDTH	SUGGESTED BACKER ROD DIAMETER (SEE NOTE A)	SUGGESTED JOINT TOTAL DEPTH
1/2"	5/8"	1"-5/8"
5/8"	3/4"	1"-7/8"
3/4"	7/8"	2"-1/8"
7/8"	1"	2"-1/4"
1"	1"-1/4"	2"-7/8"
1"-1/8"	1"-1/2"	3"-3/8"
1"-1/4"	1"-1/2"	3"-1/2"

NOTE A: IF LARGER SIZE IS USED, CONTRACTOR SHALL INCREASE SAW DEPTH (JOINT TOTAL DEPTH) AS REQUIRED AT NO ADDITIONAL COST TO THE CONTRACT.





# CLEAN AND SEAL LONGITUDINAL / TRANSVERSE JOINTS





# CLEAN AND SEAL ISOLATION JOINT

NOTE: PAID FOR AS CLEAN AND SEAL EXPANSION JOINT



₽ġ 12-30 gnments bas. /.dwg

CEA



CHAMFER JOINT DETAIL NOT TO SCALE

1/4" MIN.

3/8" MAX

(SEE JOINT NOTE 4)

	DETAIL	1 AND 2
	HOT/COLD POUR	SILICONE
W=WIDTH OF SEALANT RESERVOIR (IN.)	1/2	3/8
D=DEPTH OF SEALANT RESERVOIR (IN.)	1/2	1/4
B=BACKER ROD DIAMETER (IN.)	N/A	N/A
S=SECOND SAWCUT DEPTH (IN.) MINIMUM	3/4	1/2

NOTE: JOINT SEALING SHALL BE PER SECTION 605 OF SPECIAL PROVISIONS.



DETAIL 1

DETAIL 2

SHALL BE SAWED AND SEALED (PROJECT LIMITS), PAID FOR AS

AND SEAL JOINTS.

IL. CONTRACT: PA061 IL. LETTING ITEM: 10A IL. PROJECT: PWK-4552 S.B.G. PROJECT: 3-17-SBGP-133/139/TBD REVISIONS					
NUMBER	В	Y	DATE		
0	1		2		
THIS B AT FUI	AR IS LL SCA	EQUAL LE (34	TO 2" +X22).		
CHICAGO EXECUTIVE AIRPORT WHEELING/PROSPECT HEIGHTS, ILLINOIS	HEHABILITATE HUNWAT 12/30 AND HUNWAT LIGHTING		PAVEMENT JOINT SEALING DETAILS		
CLANT CONTINUES TILLY, INC.	CUNSULTING ENGINEERS License No. 184-000613		CHICAGO EXECUTIVE AIRPORT		
DESIGN BY:			KWS		
DRAWN BY:	IY:		JRO DKP		
APPROVED	BY:				
DATE:		06/08	3/2018		
JOB No:		16290	-04-00		
	FI		e=		



Щ. UPDATE

2018

NUMBER       BY       DATE         Image: Comparison of the state of the	IL. CONTRACT: PA061 IL. LETTING ITEM: 10A IL. PROJECT: PWK-4552 S.B.G. PROJECT: 3-17-SBGP-133/139/TBD						
<ul> <li> <ul></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul></li></ul>	NUMBER	В	Y	DATE			
Image: Construction of the second							
CHECKED BY: KWS DIRICAL OR SUBJECT HEIGHLY, INC. MISCELLANEOUS DETAILS,							
0       1       2         THIS BAR IS EQUAL TO 2"         THIS BAR IS EQUAL TO 2"         AT FULL SCALE (34X22).         ITHIS BAR IS EQUAL TO 2"         THIS BAR IS EQUAL TO 2"         THIS BAR IS EQUAL TO 2"         Units EDITIONE         UNITS EDITIONE      <							
THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22)."	0	1		2			
WISCELLANEOUS DETAILS  WISCELANEOUS  WISCELANEOUS DETAILS  WISCELANEOUS  WISCELANEOUS  WISCELANEOUS DETAILS  WISCELANEOUS  WIS	THIS B. AT FU	AR IS LL SCA	EQUA	L TO 2" 34X22).			
DESIGN BY:       KWS         DRAWN BY:       JR0         DRAWN BY:       JR4         DRAWN BY:       DKP         DRAWN BY:       DKP         APPROVED BY:       DKP         DKP       DKP         APPROVED BY:       DKP         DKP       DKP	CHICAGO EXECUTIVE AIRPORT WHEELING/PROSPECT HEIGHTS, ILLINOIS	HEHABILITATE RUNWAY 12/30 AND RUNWAY LIGHTING		MISCELLANEOUS DETAILS			
DESIGN BY:         KWS           DRAWN BY:         JRO           CHECKED BY:         DKP           APPROVED BY:         DKP           DATE:         06/08/2018           JOB No:         16290-04-00	CRAWFORD, MURPHY & TILLY, INC.	CONSULING ENGINEERS License No. 184-000613		CHICAGO EXECUTIVE AIRPORT			
DRAWN BY:         JRO           CHECKED BY:         DKP           APPROVED BY:         DKP           DATE:         06/08/2018           JOB No:         16290-04-00	DESIGN BY:			KWS			
CHECKED BY:         DKP           APPROVED BY:         DKP           DATE:         06/08/2018           JOB No:         16290-04-00	DRAWN BY: JRO						
DATE: 06/08/2018 JOB No: 16290-04-00	CHECKED BY: DKP						
JOB No: 16290-04-00	APPROVED BY:         DKP           DATE:         06/08/2018						
FINAL	JOB No: 16290-04-00						
	FINAL						







EEGEND BAD 58 BAD 58 NEW ELEVATION EXISTING ELEVATION EXISTING ELEVATION	IL. CONTRACT: IL. LETTING ITE IL. PROJECT: PW S.B.G. PROJECT: NUMBER E D D THIS BAR IS AT FULL SC	PA061 EM: 10A /K-4552 I-17-SBGP-133/139/TBD SIONS BY DATE DATE L 2 EQUAL TO 2" ALE (34X22).
	CHICAGO EXECUTIVE AIRPORT WHEELING/PROSPECT HEIGHTS, ILLINOIS REHABILITATE RUNWAY 12/30 AND RUNWAY LIGHTING	INTERSECTION GRADING PLAN TAXIWAYS D, Y AND Z
	E Copyright der. Inc. CRAMFORD, MURPHY & TILLY, INC. CONSULTING ENCINEERS License No. 184-000613	CHICEGO EXECUTIVE AIRPORT
	DRAWN BY:	JRO
	APPROVED BY:	DKP
	DATE:	06/08/2018
	JOB No:	16290-04-00
	FI FI	NAL
TAXIWAY D, Y AND Z	SHEET 25 C	F 37 SHEFTS
	SHEEL 25 C	T J/ SHEEIS

				I	BITUMINO	US PAVEMI	ENT MILLI	NG (AR4016	550) - MILL	ING DEPTH	IS				
	37.5' LEF	T OF CENT	TERLINE	18.75' LE	FT OF CEN	FERLINE	C	ENTERLIN	E	18.75' RIG	HT OF CEN	NTERLINE	37.5' RIG	HT OF CEN	TERLINE
STATION	PROP	EXST	MILL	PROP	EXST	MILL	PROP	EXST	MILL	PROP	EXST	MILL	PROP	EXST	MILL
	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH
375+59.66	NA	NA	NA	NA	NA	NA	639.37	639.37	0.17	639.64	639.64	0.17	639.52	639.52	0.17
376+00.00	NA	NA	NA	639.55	639.31	-0.08	639.83	639.76	0.10	639.63	639.71	0.25	639.42	639.42	0.17
376+50.00	NA	NA	NA	639.76	639.66	0.07	640.04	639.96	0.09	639.78	639.71	0.10	639.51	639.51	0.17
377+00.00	639.63	639.50	0.03	639.90	639.87	0.13	640.18	640.11	0.10	639.89	639.82	0.10	639.59	639.59	0.17
377+50.00	639.77	639.67	0.07	640.05	639.98	0.10	640.33	640.25	0.09	639.98	639.97	0.16	639.63	639.63	0.17
378+00.00	639.82	639.80	0.15	640.19	640.12	0.10	640.47	640.40	0.10	640.19	640.15	0.12	639.91	639.65	-0.10
378+50.00	640.06	639.87	-0.02	640.33	640.28	0.11	640.62	640.55	0.10	640.33	640.33	0.16	640.05	639.98	0.10
379+00.00	640.20	639.99	-0.04	640.48	640.42	0.11	640.76	640.70	0.11	640.48	640.43	0.12	640.19	640.14	0.12
379+50.00	640.35	640.12	-0.07	640.62	640.35	-0.11	640.90	640.83	0.09	640.62	640.56	0.11	640.33	640.31	0.14
380+00.00	640.48	640.27	-0.05	640.75	640.67	0.09	641.03	640.98	0.11	640.75	640.68	0.10	640.47	640.44	0.14
380+50.00	640.59	640.40	-0.02	640.86	640.79	0.10	641.14	641.07	0.10	640.86	640.81	0.11	640.58	640.54	0.13
381+00.00	640.67	640.44	-0.06	640.95	640.89	0.11	641.23	641.17	0.10	640.95	640.89	0.11	640.66	640.62	0.13
381+50.00	640.73	640.62	0.06	641.01	640.95	0.11	641.29	641.20	0.08	641.01	640.94	0.09	640.72	640.65	0.09
382+00.00	640.77	640.57	-0.03	641.05	640.98	0.10	641.33	641.24	0.08	641.05	640.99	0.11	640.76	640.71	0.11
382 + 50.00	640.79	640.57	-0.05	641.06	640.98	0.08	641.34	641.26	0.09	641.06	640.99	0.10	640.77	640.70	0.10
383+00.00	640.78	640.68	0.06	641.05	640.97	0.09	641.33	641.25	0.08	641.05	640.99	0.10	640.76	640.71	0.12
383 + 50.00	640.74	640.54	-0.04	641.02	640.95	0.10	641.30	641.21	0.08	641.02	640.95	0.10	640.73	640.69	0.13
384+00.00	640.69	640.50	-0.02	640.96	640.88	0.09	641.24	641.17	0.10	640.96	640.90	0.11	640.67	640.62	0.11
384+50.00	640.61	640.38	-0.06	640.88	640.79	0.07	641.17	641.08	0.08	640.88	640.81	0.10	640.59	640.53	0.11
385+00.00	640.52	640.48	0.13	640.79	640.69	0.06	641.07	641.01	0.10	640.79	640.72	0.09	640.50	640.40	0.07
385+50.00	640.43	640.25	-0.02	640.70	640.60	0.07	640.98	640.89	0.07	640.73	640.66	0.10	640.48	640.41	0.10
386+00.00	640.34	640.21	0.04	640.61	640.51	0.06	640.89	640.81	0.08	640.68	640.62	0.11	640.46	640.48	0.19
386+50.00	640.24	640.08	0.00	640.52	640.39	0.03	640.80	640.70	0.07	640.55	640.49	0.10	640.30	640.26	0.12
387+00.00	640.15	640.02	0.04	640.43	640.32	0.06	640.71	640.61	0.06	640.43	640.36	0.09	640.14	640.04	0.07
387+50.00	640.06	639.90	0.01	640.34	640.19	0.02	640.62	640.51	0.06	640.34	640.23	0.06	640.05	639.90	0.02
388+00.00	639.97	639.86	0.06	640.25	640.12	0.04	640.53	640.42	0.06	640.25	640.11	0.03	639.95	639.81	0.03
388+50.00	639.88	639.77	0.06	640.16	640.02	0.03	640.44	640.34	0.07	640.16	640.00	0.01	639.86	639.74	0.05
389+00.00	639.79	639.56	-0.07	640.07	639.97	0.07	640.35	640.26	0.08	640.07	639.97	0.07	639.77	639.62	0.01
389+50.00	639.70	639.54	0.00	639.97	639.86	0.06	640.26	640.17	0.08	639.97	639.87	0.06	639.68	639.61	0.10
390+00.00	639.62	639.55	0.10	639.90	639.80	0.07	640.18	640.08	0.07	639.90	639.80	0.07	639.60	639.56	0.13
390+50.00	639.56	639.41	0.01	639.84	639.75	0.07	640.12	640.04	0.09	639.84	639.75	0.08	639.55	639.51	0.12
391+00.00	639.53	639.36	0.00	639.81	639.72	0.08	640.09	640.02	0.10	639.81	639.76	0.11	639.51	639.48	0.14
391+50.00	639.52	639.31	-0.04	639.79	639.70	0.07	640.07	640.00	0.10	639.79	639.70	0.08	639.51	639.46	0.12
392+00.00	639.53	639.39	0.03	639.80	639.72	0.09	640.08	640.03	0.12	639.80	639.72	0.09	639.51	639.51	0.16
392+50.00	639.56	639.40	0.00	639.84	639.76	0.08	640.12	640.07	0.11	639.84	639.75	0.08	639.55	639.51	0.13
393+00.00	639.61	639.53	0.09	639.90	639.83	0.10	640.18	640.14	0.13	639.90	639.82	0.09	639.61	639.59	0.14
393+50.00	639.70	639.58	0.04	639.98	639.92	0.10	640.26	640.23	0.14	639.98	639.92	0.10	639.68	639.66	0.14
394+00.00	639.80	639.80	0.16	640.08	640.03	0.11	640.36	640.32	0.13	640.08	640.03	0.12	639.79	639.77	0.15
394+50.00	639.93	639.83	0.06	640.20	640.16	0.13	640.48	640.50	0.18	640.20	640.17	0.14	639.91	639.92	0.18
395+00.00	640.07	640.04	0.14	640.35	640.38	0.20	640.63	640.66	0.20	640.35	640.38	0.20	640.06	640.10	0.21
395+50.00	640.31	640.19	0.05	640.52	640.56	0.21	640.80	640.84	0.21	640.52	640.54	0.19	640.22	640.28	0.23
396+00.00	640.43	640.38	0.12	640.70	640.73	0.20	640.98	641.04	0.22	640.70	640.73	0.19	640.41	640.38	0.14
396+50.00	640.60	640.57	0.14	640.88	640.99	0.28	641.16	641.26	0.27	640.97	641.01	0.21	640.77	640.79	0.19
396+60.80	640.64	640.64	0.17	640.91	640.94	0.19	641.20	641.20	0.17	641.01	641.05	0.21	640.82	640.82	0.17

	BITUMINOUS PAVEMENT MILLING (AR401650) - MILLING DEPTHS														
	37.5' LEF	T OF CENI	FERLINE	18.75' LE	FT OF CEN	TERLINE	CENTERLINE			18.75' RIGHT OF CENTERLINE			37.5' RIGHT OF CENTERLINE		
STATION	PROP	EXST	MILL	PROP	EXST	MILL	PROP	EXST	MILL	PROP	EXST	MILL	PROP	EXST	MILL
	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH
408+22.86	643.27	643.27	0.17	643.60	643.60	0.17	643.83	643.83	0.17	643.61	643.61	0.17	643.29	643.29	0.16
408+50.00	643.26	643.26	0.17	643.55	643.61	0.22	643.83	643.86	0.20	643.55	643.60	0.22	643.27	643.12	0.02
409+00.00	643.25	643.25	0.17	643.53	643.49	0.13	643.81	643.78	0.14	643.53	643.49	0.12	643.25	643.17	0.08
409+50.00	643.23	643.24	0.18	643.52	643.46	0.10	643.80	643.74	0.10	643.52	643.46	0.10	643.24	643.20	0.13
410 + 00.00	643.12	643.12	0.17	643.46	643.46	0.17	643.79	643.72	0.09	643.51	643.46	0.11	643.22	643.21	0.15
410 + 50.00	643.21	643.22	0.17	643.50	643.44	0.10	643.78	643.68	0.07	643.52	643.41	0.05	643.26	643.26	0.17
411 + 00.00	643.20	643.10	0.06	643.48	643.44	0.12	643.77	643.67	0.07	643.46	643.42	0.12	643.15	643.15	0.17
411 + 50.00	643.19	643.11	0.09	643.47	643.39	0.09	643.75	643.66	0.07	643.46	643.40	0.11	643.15	643.15	0.17
412 + 00.00	643.17	643.11	0.11	643.46	643.36	0.07	643.74	643.66	0.08	643.46	643.38	0.09	643.17	643.17	0.17
412 + 50.00	643.17	643.13	0.12	643.45	643.37	0.08	643.73	643.64	0.07	643.44	643.37	0.10	643.14	643.14	0.17
413 + 00.00	643.18	643.08	0.07	643.46	643.36	0.06	643.74	643.65	0.07	643.46	643.37	0.07	643.23	643.12	0.06
413+50.00	643.21	643.16	0.12	643.49	643.39	0.06	643.77	643.67	0.07	643.49	643.40	0.08	643.26	643.13	0.03
414 + 00.00	643.26	643.17	0.08	643.54	643.44	0.07	643.82	643.73	0.08	643.54	643.44	0.07	643.26	643.15	0.06
414+50.00	643.34	643.24	0.07	643.62	643.53	0.08	643.90	643.82	0.09	643.62	643.53	0.07	643.34	643.27	0.10
415+00.00	643.43	643.33	0.07	643.72	643.62	0.07	644.00	643.89	0.06	643.72	643.60	0.05	643.43	643.32	0.06
415+50.00	643.55	643.47	0.08	643.83	643.73	0.07	644.11	644.03	0.08	643.83	643.74	0.07	643.55	643.52	0.13
416+00.00	643.69	643.61	0.08	643.97	643.88	0.08	644.25	644.16	0.08	643.97	643.87	0.07	643.69	643.56	0.04
416+50.00	643.85	643.79	0.11	644.13	644.06	0.09	644.41	644.31	0.07	644.13	643.98	0.01	643.85	643.65	-0.04
417+00.00	644.03	644.01	0.14	644.31	644.22	0.07	644.59	644.52	0.09	644.31	644.17	0.02	644.03	643.89	0.03
417 + 50.00	644.21	644.22	0.17	644.49	644.43	0.10	644.78	644.67	0.06	644.49	644.39	0.06	644.21	644.14	0.09
418 + 00.00	644.39	644.19	-0.04	644.68	644.56	0.05	644.96	644.88	0.09	644.68	644.56	0.05	644.40	644.27	0.04
418 + 50.00	644.57	644.44	0.03	644.86	644.77	0.08	645.14	645.05	0.07	644.86	644.76	0.07	644.58	644.45	0.04
419+00.00	644.70	644.65	0.11	644.99	644.96	0.14	645.27	645.23	0.12	644.99	644.95	0.13	644.71	644.64	0.09
419+50.00	644.81	644.82	0.17	645.10	645.10	0.16	645.38	645.46	0.25	645.10	645.09	0.16	644.82	644.85	0.19
420+00.00	644.90	644.94	0.20	645.19	645.23	0.20	645.47	645.30	0.00	645.19	645.18	0.16	644.90	644.89	0.16
420+50.00	644.98	644.82	0.01	645.26	645.11	0.02	645.54	645.25	-0.12	645.26	645.08	-0.01	644.97	644.77	-0.04
420+74.38	645.02	644.62	-0.23	645.30	645.01	-0.12	645.58	645.25	-0.16	645.30	645.03	-0.10	645.02	644.63	-0.22

# NOTES

- 1. MILL DEPTH IS SHOWN IN FEET.
- 2. THE BITUMINOUS PAVEMENT MILLING DEPTHS ARE PROVIDED TO ACHIEVE THE 2" BITUMINOUS OVERLAY DEPTH.
- NEGATIVE BITUMINOUS MILLING DEPTHS REFLECT A REQUIRED BITUMINOUS LEVELING TO ACHIEVE THE 2" BITUMINOUS OVERLAY. NO BITUMINOUS MILLING IS REQUIRED IN THESE LOCATIONS.
- BITUMINOUS LEVELING SHALL BE PLACED AT THE NEGATIVE MILL DEPTH LOCATIONS AS SPECIFIED IN THE TABLE TO ACHIEVE THE APPROPRIATE DEPTH PRIOR TO THE 2" BITUMINOUS OVERLAY. BITUMINOUS LEVELING SHALL BE PAID FOR UNDER AR401610 - BITUMINOUS SURFACE COURSE.
- 5. NO ADDITIONAL PAYMENT FOR MILLING DEPTHS GREATER THAN SPECIFIED IN THE PLANS WILL BE MADE
- 6. N/A ELEVATIONS ARE LOCATIONS OUTSIDE THE RUNWAY PAVEMENT.

IL. CONTRACT: PA061 IL. LETTING ITEM: 10A IL. PROJECT: PWK-4552 S.B.G. PROJECT: 3-17-SBGP-133/139/TBD					
NUMBER	В	Y	DATE		
0 This B. At Fu	AR IS LL SCA	EQUAL	2 TO 2" 4X22).		
CHICAGO EXECUTIVE AIRPORT WHEELING/PROSPECT HEIGHTS, ILLINOIS	HEHABILITATE HUNWAY 12/30 AND HUNWAY LIGHTING		BITUMINOUS MILLING DEPTH TABLE RUNWAY 12/30		
CRAWFORD, MURPHY & TILLY, INC.	CONSUL ING ENGINERS License No. 184-000613		CHICAGO EXECUTIVE AIRPORT		
DESIGN BY:			KWS		
DRAWN BY:	BY:		JRO DKP		
APPROVED	BY:		DKP		
DATE:		06/0	8/2018		
JOB No:		16290	0-04-00		
CULLY	FI				



























DULE	
SIGN LOCATION	COMMENTS
۸. 795+56.25, 50'LT. Ç ТАХІЖАҮ К	REMOVE EXISTING SIGN AND BASE NEW SIGN AND BASE
. 398+48.9, 61.1'LT. Ç RUNWAY 12/30	REMOVE EXISTING SIGN AND BASE NEW SIGN AND BASE
А. 802+01.00, 50'LT. Ç ТАХІЖАҮ К	REMOVE EXISTING SIGN AND BASE NEW SIGN AND BASE
A. 397+77, 63.7'RT. Ç RUNWAY 12/30	REPLACE SIGN PANELS
. 204+52.6, 53.0'RT. မူ RUNWAY 6/24	REMOVE EXISTING SIGN AND BASE NEW SIGN AND BASE
A. 199+40, 55.0' LT. C. TAYIMAY E	NEW SIGN AND BASE
Α. 10+59.+, 10.5' ΙΤ Ͼ ΤΑΧΙΨΑΥ Υ	REPLACE SIGN PANELS
Α. 12+20.8, 37.4'LT. Ç TAXIWAY Y	REPLACE SIGN PANELS
Ά. 1+98.5, 63.5' LT. Ç TAXIWAY E1	NEW SIGN AND BASE

IL. CONTRACT: PA061 IL. LETTING ITEM: 10A IL. PROJECT: PWK-4552 S.B.G. PROJECT: 3-17-SBGP-133/139/TBD						
	REVIS	SIONS				
NUMBER	В	Y	DAIE			
0	,		2			
THIS B. AT FU	AR IS LL SCA	EQUAL ALE (34	TO 2" 4X22).			
CHICAGO EXECUTIVE AIRPORT WHEELING/PROSPECT HEIGHTS, ILLINOIS	REHABILITATE RUNWAY 12/30 AND RUNWAY LIGHTING		ELECTRICAL DETAILS - SHEET 3			
CRAWFORD, MURPHY & TILLY, INC.	CONSUL IING ENGINERS License No. 184-000613		CHICE EXECUTIVE AIRPORT			
DESIGN BY:			ARM			
DRAWN BY:			JRO			
CHECKED E	BY:		DKP			
APPROVED	BI:	06/0	UKP 8/2018			
DATE: 06/08/2018 JOB No: 16290-04-00						
JUE NO: 16290-04-00						
FINAL						

# PROPOSED VAULT NOMENCLATURE

(1) EXISTING 30KW (5-STEP) REGULATOR FOR RUNWAY 16/34.

- (2) EXISTING 20KW (5-STEP) REGULATOR FOR RUNWAY 6/24.
- (3) EXISTING 10KW (3-STEP) REGULATOR FOR RUNWAY 12/30 TO BE REMOVED.
- (4) EXISTING 10KW (3-STEP) REGULATOR FOR TAXIWAY G,D AND 34 HOLD APRON.
- 5 EXISTING 10KW (3-STEP) REGULATOR FOR RUNWAY 16/34 RDR.
- (6) EXITSTING 15KW (3-STEP) REGULATOR FOR RUNWAY 16/34 RGL.
- (7) EXISTING 30 KW (5-STEP) REGULATOR (SPARE).
- (8) EXISTING 10 KW (3-STEP) REGULATOR FOR A, B, D, E, F, Y, L AND A.
- (9) EXISTING 30KW (5-STEP) SPARE.
- (1) EXISTING 20KW (3-STEP) REGULATOR FOR RUNWAY 16 APPROACH.
- (1) EXISTING 30 KW (5-STEP) REGULATOR FOR LIMA.
- (12) EXISTING 30KW (3-STEP) REGULATOR FOR TAXIWAY K.
- (13) EXISTING 10KW (3-STEP) REGULATOR FOR TAXIWAY C.
- (14) FUTURE AIRFIELD LIGHTING REGULATOR.
- 15 EXISTING MAIN UTILITY SERVICE CIRCUIT BREAKER DISCONNECT. 800A, 480V, 3-POLE.
- (16) EXISTING AUTOMATIC TRANSFER SWITCH. 800A, 480V, 3-POLE.
- (1) EXISTING HIGH VOLTAGE POWER DISTRIBUTION PANEL. 480V, 3-PHASE WITH 800AMP MAIN CIRCUIT BREAKER.
- (18) EXISTING 150KVA, 480V-280Y/120V, 30, 4-WIRE TRANSFORMER.
- (1) EXISTING LOW VOLTAGE LIGHTING PANEL. 208Y/120V, 3-PHASE WITH 400AMP MAIN CIRCUIT BREAKER.
- (20) EXISTING PLC CONTROL CABINET.
- (21) EXISTING 800AMP CT CABINET.
- (22) EXISTING 12"x12"x12' LONG LOW VOLTAGE WIREWAY.
- (23) EXISTING 12"X12"x12' LONG HIGH VOLTAGE WIREWAY.
- (24) EXISTING 12"x12"x9' LONG HIGH VOLTAGE WIREWAY.
- (25) EXISTING 12"x12"x9' LONG LOW VOLTAGE WIREWAY.
- (26) EXISTING 30KW (3-STEP) REGULATOR FOR HFC APRON.

(27) NEW 10KW (3-STEP) REGULATOR FOR RUNWAY 12/30.

28 INSTALL NEW 2-1/C #8 5KV, L-824 CABLES IN EXISTING CONDUIT FROM NEW 30KW SPARE REGULATOR TO HIGH VOLTAGE WIREWAY. INSTALL L-823 CONNECTORS.

# NOTES:

- 1. ALL PROPOSED WORK OR ITEMS BEING MODIFIED ARE SHOWN IN BOLD. ALL OTHER ITEMS SHOWN ARE FOR INFORMATIONAL PURPOSES ONLY.
- 2. CONTRACTOR SHALL REMOVE EXISTING 10KW REGULATOR (RUNWAY 12/30 APPROACH) AND DISPOSE OF IT OFF OF AIRPORT PROPERTY.
- 3. CONTRACTOR SHALL FURNISH AND INSTALL NEW 10KW (3-STEP) REGULATOR FOR RUNWAY 12/30 EDGE LIGHTING CIRCUIT.
- 4. CONNECT EXISTING POWER AND CONTROLS FOR RUNWAY 12/30 REGULATOR ..









