

F.A.I. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	COOK	312	7
STA. TO STA.		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	
60A62		• (1919.15, 2021 922 PT1 & PT2) R-1	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE																		
				URBAN ROADWAY	RETAINING WALL		BRIDGE		SIGNING	SAFETY	LIGHTING	SURVEILLANCE	CDD LIGHTING									
					016-W923	016-W931	STR NO 016-0142	STR NO 016-1148						Y002-1C	SFTY-3N	Y030-1E	Y032-1F	Y030-1E				
20101000	TEMPORARY FENCE	FOOT	847	847																		
20200100	EARTH EXCAVATION	CU YD	38,181	38,181																		
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	103	103																		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,426	2,426																		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	184			73	111															
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,500	1,500																		
20800150	TRENCH BACKFILL	CU YD	3,102.0	3,102.0																		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	42,709	42,709																		
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4,178	4,178																		
* 21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	8,759	8,759																		
* 21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	8,759	8,759																		
* 25000210	SEEDING, CLASS 2A	ACRE	2.08	2.08																		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	240	240																		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	236	236																		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	234	234																		
NP 25000750	MOWING	ACRE	2.89	2.89																		
* 25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	0.14	0.14																		
* 25001820	SEEDING, CLASS 5 (MODIFIED)	ACRE	0.35	0.35																		
* 25002014	SEEDING, CLASS 4A (MODIFIED)	ACRE	0.35	0.35																		
* 25100630	EROSION CONTROL BLANKET	SQ YD	12,937	12,937																		
* 25200200	SUPPLEMENTAL WATERING	UNIT	310.8	310.8																		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	7,626	7,626																		
28000300	TEMPORARY DITCH CHECKS	EACH	1	1																		
28000510	INLET FILTERS	EACH	169	169																		
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	CU YD	4,983	4,983																		
31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	37,727	37,727																		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17.5	17.5																		
40600300	AGGREGATE (PRIME COAT)	TON	85.6	85.6																		
42001300	PROTECTIVE COAT	SQ YD	47,426	47,426																		
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SQ YD	29,253	29,253																		

* DENOTES SPECIALTY ITEMS

NP = NON-PARTICIPATING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
 63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)
SUMMARY OF QUANTITIES
 SCALE: NONE
 DATE: June 9, 2006
 DRAWN BY: NJH
 CHECKED BY: RMG



SOQ-1

6/16/2006 9:58:39 AM