F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	312	13
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

60A62 * (1919.15, 2021-922 PT1 & PT2) R-1

SUMMARY OF QUANTITIES

				90% FEDERAL / 10% STATE									
				URBAN ROADWAY	RETAINING WALL		BRIDGE		SIGNING	SAFETY	LIGHTING	SURVEILLANCE	CDOT LIGHTING
					016-W923	016-W931	STR NO 016-0142	STR NO 016-1148					
CODE NO.	ITEM	UNIT	QUANTITY	J000	Y007	Y007	SFTY-2A	SFTY-2A	Y002-1C	SFTY-3N	Y030-1E	Y032-1F	Y030-1E
* Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4							4			
* Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1							1			
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	1,017	1,017									
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1									
⊙ Z0076600	TRAINEES	HOUR	1000	1000									
* X0325499	AERIAL CABLE, 2 1/C NO. 4	FOOT	150										150
* X0325491	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., SCH. 80 PVC	FOOT	653										653
* X0325492	CONVENTIONAL STREET LIGHTING UNIT WALL MOUNTED, INSTALL ONLY	EACH	8										8
* X0325494	GALVANIZED STEEL CONDUIT IN TRENCH, 2" DIA., SCH. 40	FOOT	25										25
* 80700110	GROUND ROD, 3/4" DIA. X 10 FT.	EACH	8										8
* X0325500	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, TYPE J	EACH	2									2	
* TWY02040	MAINTAIN EXISTING LIGHTING SYSTEM	L SUM	1										1
* X0945500	PAINT EXISTING POLE COMPLETE	EACH	8										8
* X0325495	REMOVE EXISTING STREET LIGHTING UNIT AND SALVAGE	EACH	9										9
* X0324901	REMOVE EXISTING STREET LIGHTING FOUNDATION	EACH	9										9
* X0325496	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SAND	FOOT	25										25
* X0325493	CABLE IN CONDUIT, TRIPLEX, 2-1/C NO. 6 AND 1-1/C NO. 8 GND.	FOOT	840										840
X0325501	FABRIC REINFORCED ELASTOMERIC MAT	SQ FT	63			63							
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	15					15					
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	993				458	535					
X0325498	DUCTILE IRON PIPE	FOOT	143	143									
X0325502	MEDIAN BARRIER GATE SYSTEM	EACH	1	1									
X0325503	REMOVAL OF EXISTING TEMPORARY SOIL RETENTION SYSTEM	FOOT	926	926									

⊙ Y080

* DENOTES SPECIALTY ITEMS

CTE | AECOM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH
DATE: June 9, 2006 CHECKED BY: RMG

SQQ-7

6/6/2006 9:38:43 AM