

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94		COOK	247	9
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
60A63 • (19)9.15, 2021-922 PT1 & PT2) R-2				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE																
				URBAN		URBAN ROADWAY	RETAINING WALL	BRIDGE		SIGNING	LIGHTING	SURVEILLANCE	SAFETY	CDOT LIGHTING						
				J000	Y007	69TH STREET SOUTHWEST	STR NO 016-0142	STR NO 016-1148	Y002-1C	Y030-1E	Y032-1F	SFTY-3N	Y030-1E							
60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	250	250																
60618324	CONCRETE MEDIAN SURFACE, 6 INCH (SPECIAL)	SO FT	4,437	4,437																
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	125.0	125.0																
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1																
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	1	1																
63200310	GUARDRAIL REMOVAL	FOOT	841	841																
63700805	CONCRETE BARRIER TRANSITION	FOOT	573	573																
64200105	SHOULDER RUMBLE STRIP	FOOT	34,880	34,880																
67100100	MOBILIZATION	L SUM	1	1																
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1																
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6,510	6,510																
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SO FT	311	311																
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	31,964	31,964																
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	4,139	4,139																
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	8,477	8,477																
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	613	613																
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	18,675	18,675																
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	6,510	6,510																
* 72000100	SIGN PANEL-TYPE 1	SO FT	64						64											
* 72000200	SIGN PANEL-TYPE 2	SO FT	88						88											
* 72000300	SIGN PANEL - TYPE 3	SO FT	955.5						955.5											
* 72400200	REMOVE SIGN PANEL ASSEMBLY-TYPE B	EACH	4						4											
* 72400330	REMOVE SIGN PANEL-TYPE 3	SO FT	251						251											
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	65.8						65.8											
* 73000100	WOOD SIGN SUPPORT	FOOT	94						94											
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	7						7											
* 73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	157						157											
* 73302150	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (24" X 5'-6")	FOOT	28						28											
* 73305000	OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	123						123											
* 73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	53.3						53.3											

* DENOTES SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. 90/94 (DAN RYAN EXPRESSWAY) 63RD STREET TO GARFIELD BLVD (SB LOCAL LANES)
NAME	DATE	
		SUMMARY OF QUANTITIES
		SCALE: NONE
		DATE: June 9, 2006
		DRAWN BY: NJH
		CHECKED BY: RMC

CTE | AECOM

S00-3

6/9/2006 9:39:55 AM