CONTRACT 60B67

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1238	125_SB_1-1-1	LAKE	13	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN / 100% STATE / SFTY-2A
44001000	BITUMINOUS CONCRETE SURFACE REMOVAL	SQ YD	45	45
50102400	CONCRETE REMOVAL	CU YD	25.4	25.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	25.4	25.4
50300300	PROTECTIVE COAT	SQ YD	142	142
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1670	1670
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2280	2280
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	145	145
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	737	737
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	360	360
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	300	300
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	400	400
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	36	36
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	4
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	1695	1695
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	22	22
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
XX005369	TRAFFIC CONTROL & PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1
△ Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2
△ Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE

△ SFTY-3N
* SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 6/2/2006

6/2/2006
C:\Bsr\Bsr1s3\s13920\Roadway\s13920ROSUM.dgn