

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94		COOK	565	8
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
62301		• (2021-922 PT2 ETC 2324.6-1P) R-10		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE															
				URBAN ROADWAY	RETAINING WALL		MWRD BOX CULVERT	SIGNING	SAFETY	LIGHTING	SURVEILLANCE								
					016-W977	43rd-31st						Y000	Y007	Y007	Y002-1C	SFTY-3N	Y030-1E	Y032-1F	
40600300	AGGREGATE (PRIME COAT)	TON	87.8	87.8															
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SQ YD	6,214	6,214															
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	430					430											
42001300	PROTECTIVE COAT	SQ YD	137,134	137,134															
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SQ YD	83,582	83,582															
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	2,371	2,371															
44000009	BITUMINOUS SURFACE REMOVAL 3"	SQ YD	267	267															
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1,664	1,626				38											
44000100	PAVEMENT REMOVAL	SQ YD	114,998	114,998															
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	36,897	36,897															
44000700	APPROACH SLAB REMOVAL	SQ YD	164					164											
44001980	CONCRETE BARRIER REMOVAL	FOOT	419	419															
44003100	MEDIAN REMOVAL	SQ FT	10,297	10,297															
44004250	PAVED SHOULDER REMOVAL	SQ YD	5,297	5,297															
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SQ YD	616	616															
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1													
50102400	CONCRETE REMOVAL	CU YD	18			18													
50200100	STRUCTURE EXCAVATION	CU YD	631			195	170	16				250							
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	269.4	269.4															
50300225	CONCRETE STRUCTURES	CU YD	413	30	180	143						60							
50300255	CONCRETE SUPERSTRUCTURE	CU YD	258		72	86	97					3							
50300260	BRIDGE DECK GROOVING	SQ YD	153				153												
50300300	PROTECTIVE COAT	SQ YD	1,608		592	479	263					274							
50300510	RUSTICATION FINISH	SQ FT	8,182		4,222	3,503						457							
50500505	STUD SHEAR CONNECTORS	EACH	1,692		992	700													
50700209	UNTREATED TIMBER LAGGING	SQ FT	6,541		3,724	2,817													
50700211	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	874			874													
50700215	FURNISHING SOLDIER PILES (W SECTION)	FOOT	3465		2,150	1315													
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	99,480	5,000	39,920	32,030	17,690					4,840							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	8,495	8,495															
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	427	427															

• DENOTES SPECIALTY ITEMS



REVISIONS		NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
GARFIELD BLVD TO 31ST STREET (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE  
DATE: June 9, 2006

DRAWN BY: PHP  
CHECKED BY: RMG

Rev. S00-2

5/8/2006 4:08:31 PM p:\p40468\civ\105-contrs 16 & 19\summary 18/00022a.rtf