

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE																
				URBAN ROADWAY	RETAINING WALL		MWRD BOX CULVERT	SIGNING	SAFETY	LIGHTING	SURVEILLANCE									
					016-W977	43rd-31st						Y000	Y007	Y007	Y002-1C	SFTY-3N	Y030-1E	Y032-1F		
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	14,846	14,846																
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	3,714	3,714																
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SO FT	9,373	8,173	1,200															
X0324112	BARRIER BASE	FOOT	17,958	17,958																
X0324433	LIGHT TOWER SERVICE PAD, 6"	SO FT	816									816								
X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	22,352		12,973	9,379														
X0324469	CONDUIT ENCASED, REINFORCED CONCRETE, 2-4" DIA., CNC	FOOT	100																	100
X0324470	CONDUIT ENCASED, REINFORCED CONCRETE, 3-4" DIA., CNC	FOOT	480																	480
X0324471	CONDUIT ENCASED, REINFORCED CONCRETE, 4-4" DIA., CNC	FOOT	36																	36
X0324472	CONDUIT ENCASED, REINFORCED CONCRETE, 5-4" DIA., CNC	FOOT	116																	116
X0324640	FLUTED KNEE WALL	FOOT	218			218														
X0324646	CONDUIT ENCASED, REINFORCED CONCRETE, 6-4" DIA., CNC	FOOT	270																	270
X0324697	SOIL STABILIZERS	POUND	1,669,253	1,669,253																
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	1,331	1,331																
X0324793	LIGHT TOWER SERVICE PAD, SPECIAL	SO FT	1,496									1,496								
X0325080	VIDEO TAPING OF MWRD CULVERT	FOOT	245					245												
X0325081	CONCRETE SLAB HYDRO-DEMOLITION	SO YD	165					165												
X0919000	TEMPORARY PAVEMENT REMOVAL	SO YD	11,728	11,728																
X2020300	EXCAVATE AND PLACE EXISTING GRANULAR MATERIAL	CU YD	27,469	27,469																
X2500322	SEEDING, CLASS 5A (MODIFIED)	ACRE	2.84	2.84																
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	392	392																
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	262	262																
X4210400	LUG SYSTEM REMOVAL	EACH	4	4																
X4834090	PORTLAND CEMENT CONCRETE SHOULDERS 14"	SO YD	24,114	24,114																
X6061003	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.48 (MODIFIED)	FOOT	4,450	4,450																
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	9,236	9,236																
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SO FT	4,168	4,168																
X6370910	CONCRETE BARRIER, SINGLE FACE, 32" HEIGHT	FOOT	3,801	3,801																
X6370930	CONCRETE BARRIER, DOUBLE FACE, 32" HEIGHT	FOOT	12,386	12,386																
X6370935	CONCRETE BARRIER, SINGLE FACE, 32" (MODIFIED)	FOOT	523	523																

• DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
 GARFIELD BLVD TO 31ST STREET (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: PHP  
 DATE: June 9, 2006 CHECKED BY: RWG



Rev. S00-7

4/18/2006 4:08:35 PM