

SUMMARY OF QUANTITIES

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	588	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
62303		• (2021-922 PT2 ETC 2324.6-1P) R-11		

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	90% FEDERAL / 10% STATE										
				ROADWAY IDOT J000	ROADWAY CDOT J000	RETAINING WALLS 69TH SW Y007 39TH-47TH Y007		MWRD CULVERT X02B-2A	SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	764	764										
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	774	774										
20101000	TEMPORARY FENCE	FOOT	35	35										
20200100	EARTH EXCAVATION	CU YD	110,547	110,547										
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	2439	2439										
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10,252	10,252										
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	75				14	56				5		
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,500	1,500										
20800150	TRENCH BACKFILL	CU YD	3234	3234										
20900110	POROUS GRANULAR BACKFILL	CU YD	844	844										
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	119,406	119,406										
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	29,672	29,672										
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	34,170	34,170										
21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	34,170	34,170										
25000210	SEEDING, CLASS 2A	ACRE	10.0	10.0										
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,187	1,187										
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,185	1,185										
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,185	1,185										
NP 25000750	MOWING	ACRE	13.8	13.8										
25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	3.2	3.2										
25100630	EROSION CONTROL BLANKET	SQ YD	63,842	63,842										
25200200	SUPPLEMENTAL WATERING	UNIT	1,534	1,534										
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	30,484	30,484										
28000510	INLET FILTERS	EACH	408	408										
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	80,641	80,641										
31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	39,765	39,765										
31200100	STABILIZED SUB-BASE 4"	SQ YD	8,390	8,390										
35300410	PORTLAND CEMENT CONCRETE BASE COURSE 9 1/2"	SQ YD	4,265	4,265										
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	211	211										

NP = NON-PARTICIPATING
* - SPECIALTY ITEM

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbanoa.com



REVISIONS	NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
GARFIELD BLVD TO 31ST STREET (SB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: 1"=N.T.S.
DATE: 06/09/06
DRAWN BY: RGR
CHECKED BY: DDM

Rev.

S00-01

M:\660\660\94\90\94\SHEETS\S660_19CS0001.dwg 15:43:35 PM 6/9/2006