

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	588	31
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
62303 • (2021-922 PT2 ETC 2324.6-1P) R-11				

LANDSCAPING SCHEDULE

STATION	TO	STATION	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	SUPPLEMENTAL WATERING	TOPSOIL FURNISH AND PLACE, 4"	TOPSOIL FURNISH AND PLACE, 12"	COMPOST FURNISH AND PLACE, 6"	SEEDING CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	SEEDING, CLASS 4 (MODIFIED)	EROSION CONTROL BLANKET	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	VINE-PARTHENOCISSUS TRICUSPIDATA (BOSTON IVY), 1-GALLON POT	SEEDING, CLASS 5A (MODIFIED)	WEED CONTROL
STATION	TO	STATION	UNIT	UNIT	UNIT	SQ YD	SQ YD	SQ YD	ACRE	POUND	POUND	POUND	ACRE	SQ YD	EACH	EACH	ACRE	POUND
3475+50.00	TO	3482+00.00	0	0	0	0	3	3	0.00	1	1	1	0.00	3	5	0	0.00	1.00
3482+00.00	TO	3506+00.00	0	0	60	942	1,561	1,561	0.52	47	47	47	0.00	2,503	40	16	0.00	1.00
3506+00.00	TO	3529+00.00	0	0	179	3,477	3,992	3,992	0.98	135	133	133	0.48	7,469	285	68	0.48	10.00
3529+00.00	TO	3553+00.00	216	506	258	6,040	4,698	4,698	1.72	200	200	200	0.5	10,738	0	210	0.50	2.90
3553+00.00	TO	3577+00.00	385	252	389	7,803	8,393	8,393	1.82	302	302	302	1.5	16,196	43	17	1.54	0.80
3577+00.00	TO	3601+00.00	163	16	312	6,371	6,590	6,590	2.01	241	241	241	0.7	12,961	0	0	0.67	0.00
3601+00.00	TO	3625+00.00	0	0	243	3,551	6,579	6,579	2.10	189	189	189	0.0	10,130	370	260	0.00	8.80
3625+00.00	TO	3638+05.00	0	0	92	1,488	2,354	2,354	0.80	72	72	72	0.0	3,842	0	320	0.00	4.50
TOTALS			764	774	1,534	29,672	34,170	34,170	9.95	1,187	1,185	1,185	3.19	63,842	743	891	3.19	29.00

EROSION CONTROL SCHEDULE

STATION	TO	STATION	SEDIMENT CONTROL, SILT FENCE	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	INLET FILTERS	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	TEMPORARY EROSION CONTROL SEEDING	MOWING
STATION	TO	STATION	FOOT	FOOT	EACH	EACH	POUND	ACRE
3475+50.00	TO	3482+00.00	0	0	12	24	0	0.00
3482+00.00	TO	3506+00.00	1,290	323	44	88	1,612	0.52
3506+00.00	TO	3529+00.00	1,794	449	46	92	4,650	1.87
3529+00.00	TO	3553+00.00	2,257	564	66	132	7,286	2.3
3553+00.00	TO	3577+00.00	2,625	656	62	124	10,513	3.4
3577+00.00	TO	3601+00.00	2,444	611	55	110	3,159	2.6
3601+00.00	TO	3625+00.00	2,394	599	65	130	2,319	2.2
3625+00.00	TO	3638+05.00	871	218	32	64	944	0.9
TOTALS			13,675	3,419	382	764	30,484	13.76

SCH-02

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



REVISIONS	
NAME	DATE
REVISED SHEET	6/23/06

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
GARFIELD BLVD TO 31ST STREET (SB LOCAL LANES)

ROADWAY SCHEDULES

SCALE: NTS
DATE: 06/09/06
DRAWN BY: RA
CHECKED BY: RS

12/26/05 PM 6/21/2006