

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	2003-02961	COOK	344	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

62581

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN 100% STATE		SIGNING Y002-1C	SAFETY SFTY-3N
			TOTAL QUANTITIES	ROADWAY J000-2A		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,098	1,098		
X0320622	FIELD MEASUREMENTS	L. SUM	1		1	
X0321472	REMOVE TEMPORARY CONCRETE BARRIER	FOOT	720	720		
X0321781	MECHANICAL SPLICE	EACH	876		876	
X0321866	REMOVE, STORE AND RE-ERECT SIGN PANEL	SQ FT	885		885	
X0322215	CLEANING BRIDGE SCUPPERS AND DOWNSPOUTS	EACH	269		269	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	3297		3297	
X0323574	MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE	CAL MO	9		9	
X0323557	BRIDGE JOINT SYSTEM (EXPANSION), 1"	FOOT	325		325	
X0323558	BRIDGE JOINT SYSTEM (EXPANSION), 1-5/8"	FOOT	1137		1137	
X0323559	BRIDGE JOINT SYSTEM (FIXED),	FOOT	395		395	
X0324112	BARRIER BASE	FOOT	362	362		
X0324292	MAINTENANCE OF EXISTING TRAFFIC SURVEILLANCE	CAL MO	9		9	
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	621	621		
X4834090	PORTLAND CEMENT CONCRETE SHOULDERS 14"	SQ YD	875	875		
X6370930	CONCRETE BARRIER DOUBLE FACE, 32" HEIGHT	FOOT	362	362		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1		
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	240	240		
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	84	84		
X7040600	FURNISH TEMPORARY CONCRETE BARRIER	FOOT	360	360		
<del>XX001854</del>	<del>STABILIZED SUB BASE, 6"</del>	<del>SQ YD</del>	<del>875</del>	<del>875</del>		
XX005128	STRIP SEAL EXPANSION JOINT ASSEMBLY	FOOT	3558		3558	
Z0002600	BAR SPLICERS	EACH	1,330		1,330	
<b>XZ193500</b>	BRIDGE DECK MICROSILICA CONCRETE OVERLAY, 2 1/4"	SQ YD	102,774		102,774	
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION, 1/2"	SQ YD	102,774		102,774	
X0321743	SILICONE JOINT SEALER 1"	FOOT	10,486		10,486	
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	16	16		
X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	10	10		

S00-03

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbainc.com



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
SB DAN RYAN ELEVATED BRIDGE  
REPAIR FROM 15TH TO 28TH STREETS  
SUMMARY OF QUANTITIES

SCALE: = NTS  
DATE: 4/14/2006

DRAWN BY: RA  
CHECKED BY: RS

Rev.

10/30/06 10:39:31 AM