

F.A.E. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2003-0671	VARIOUS	27	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
CONTRACT NO. 62635				

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE SFTY- 2A																	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	COOK COUNTY				LAKE CO.													
				LOC. 1 016-0874	LOC. 2 016-0307	LOC. 3 016-0928	LOC. 4 049-0013														
20300100	CHANNEL EXCAVATION	CU YD	14		14																
28100107	STONE RIPRAP, CLASS A4	SQ YD	2600	360	865	1015	360														
28200200	FILTER FABRIC	SQ YD	4100	1860	865	1015	360														
28400100	GABIONS	CU YD	100	100																	
28401000	SLOPE MATTRESS 12"	SQ YD	1430	1430																	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	1	1	1	1														
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25														
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.25	0.25	0.25	0.25														
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5			0.5														
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1																
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1			1															
X0301852	DEWATERING STRUCTURE NO. 1	EACH	1	1																	
X0301853	DEWATERING STRUCTURE NO. 2	EACH	1		1																
X0301854	DEWATERING STRUCTURE NO. 3	EACH	1			1															
X0301855	DEWATERING STRUCTURE NO. 4	EACH	1				1														
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	205.6	51.4	51.4	51.4	51.4														

5/12/2006 10:48:00 AM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**

PLOT DATE: 5/12/2006