

62923

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	801.FED. 201.STATE					
				1000					
20800150	TRENCH BACKFILL	CU YD	75	75					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1603	1603					
21400100	GRADING AND SHAPING DITCHES	FOOT	2606	2606					
25000210	SEEDING, CLASS 2A	ACRE	2.2	2.2					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	38	38					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	38	38					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	38	38					
25100630	EROSION CONTROL BLANKET	SQ YD	441	441					
28100105	STONE RIPRAP, CLASS A3	SQ YD	17	17					
28100107	STONE RIPRAP, CLASS A4	SQ YD	34	34					
28200200	FILTER FABRIC	SQ YD	51	51					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19	19					
40600300	AGGREGATE (PRIME COAT)	TON	96	96					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	14	14					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	197	197					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	3248	3248					
44000004	BITUMINOUS SURFACE REMOVAL 1"	SQ YD	3200	3200					
44000124	BITUMINOUS REMOVAL OVER PATCHES, 6"	SQ YD	9670	9670					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	395	395					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	313	313					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	2616	2616					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1276	1276					
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	900	900					
50105220	PIPE CULVERT REMOVAL	FOOT	93	93					
54201279	PIPE CULVERTS, TYPE 2 RCCP 24"	FOOT	45	45					
54209892	PIPE CULVERTS, TYPE 2, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 27"	FOOT	234	234					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	5	5					
54214722	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 27"	EACH	10	10					
54215424	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24"	EACH	2	2					

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	801.FED. 201.STATE					
				1000					
54215430	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30"	EACH	1	1					
54244805	INLET BOX, STANDARD 542501	EACH	3	3					
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	90	90					
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100					
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	1158	1158					
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	140	140					
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1185	1185					
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	555	555					
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	12	12					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3					
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1275	1275					
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2191	2191					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	59753	59753					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	981	981					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	80	80					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	50	50					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	59753	59753					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES