

COMPANY NAME: #COMPANY NAME#  
 PROJECT CONTACT: #PROJECT CONTACT#  
 CLIENT: #CLIENT#  
 #DATES# #TIME#

PROF. FILE SURVEYED \_\_\_\_\_ BY \_\_\_\_\_ DATE \_\_\_\_\_  
 NOTE BOOK GRADES CHECKED \_\_\_\_\_  
 (E.M. NOTED) ADJUSTMENTS CHNG \_\_\_\_\_  
 NO. \_\_\_\_\_

PLAN SURVEYED \_\_\_\_\_ BY \_\_\_\_\_ DATE \_\_\_\_\_  
 NOTE BOOK ALIGNMENT CHECKED \_\_\_\_\_  
 (E.M. NOTED) ADJUSTMENTS CHNG \_\_\_\_\_  
 NO. \_\_\_\_\_

80% F&P  
 20% STATE

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	1000-2A	SFTY-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	288	288	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	559	559	
20200100	EARTH EXCAVATION	CU YD	79371	79371	
20700110	POROUS GRANULAR EMBANKMENT	TON	1015	1015	
20800150	TRENCH BACKFILL	CU YD	883	883	
21301062	EXPLORATION TRENCH 82" DEPTH	FOOT	49500	49500	
25000100	SEEDING, CLASS 1	ACRE	7.2	7.2	
25000200	SEEDING, CLASS 2	ACRE	33.4	33.4	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3008	3008	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3006	3006	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3006	3006	
25100115	MULCH, METHOD 2	ACRE	40.6	40.6	
25100630	EROSION CONTROL BLANKET	SQ YD	2348	2348	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20300	20300	
28000300	TEMPORARY DITCH CHECKS	EACH	286	286	
28000400	PERIMETER EROSION BARRIER	FOOT	4800	4800	
28000500	INLET AND PIPE PROTECTION	EACH	100	100	
28100607	STONE DUMPED RIPRAP, CLASS A4	TON	1101	1101	
28200200	FILTER FABRIC	SQ YD	1209	1209	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	12462	12462	
31102100	SUB-BASE GRANULAR MATERIAL, TYPE C 4"	SQ YD	28404	28380	24
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	2515	2515	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1989	1989	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	10275	10269	6
40600300	AGGREGATE (PRIME COAT)	TON	188.4	188.2	0.2
40600865	CONSTRUCTING TEST STRIP	EACH	2	2	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	728	728	
40600990	TEMPORARY RAMP	SQ YD	114	114	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	254	254	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6"	SQ YD	154	154	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	82959	82883	76
44000100	PAVEMENT REMOVAL	SQ YD	3902	3902	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1636	1636	
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	2245	2245	
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	12612	12568	14
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	979	979	
44201768	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	386	386	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1195	1195	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	11771	11759	12
48202410	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2"	SQ YD	22730	22709	21
50106200	REMOVE EXISTING CULVERTS	EACH	64	64	
50800105	REINFORCEMENT BARS	POUND	5310	5310	
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2	2	
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	2	2	
54001004	BOX CULVERT END SECTION, CULVERT NO. 4	EACH	2	2	
54001005	BOX CULVERT END SECTION, CULVERT NO. 5	EACH	2	2	
54001006	BOX CULVERT END SECTION, CULVERT NO. 6	EACH	2	2	
54003000	CONCRETE BOX CULVERTS	CU YD	24	24	
54010503	PRECAST CONCRETE BOX CULVERT 6' X 3'	FOOT	84.0	84.0	
54010904	PRECAST CONCRETE BOX CULVERT 9' X 4'	FOOT	102.0	102.0	
54011004	PRECAST CONCRETE BOX CULVERT 10' X 4'	FOOT	54.0	54.0	
542A0223	PIPE CULVERTS, CLASS A, TYPE 1, 18"	FOOT	440	440	
542D0223	PIPE CULVERTS, CLASS D, TYPE 1, 18"	FOOT	1986	1986	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1, 24"	FOOT	195	195	
542D0235	PIPE CULVERTS, CLASS D, TYPE 1, 30"	FOOT	60	60	
542D5473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	170	170	
542D5465	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	52	52	
54207573	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND - SIZE 18"	FOOT	326	326	
54207581	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND - SIZE 36"	FOOT	219	219	
54213463	END SECTIONS 18"	EACH	76	76	
54213459	END SECTIONS 24"	EACH	6	6	
54213465	END SECTIONS 30"	EACH	2	2	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5	5	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	12	12	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
54214293	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	8	8	
54214305	END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	2	2	

\* SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.S. 1517 (U.S. ROUTE 150)  
 SUMMARY OF QUANTITIES  
 (SHEET 1 OF 2)

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1517 (2)RS-3	(3)RS-4	MCLEAN	223	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			