

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1517	(2)RS-3 (3)RS-4	MCLEAN	223	32
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

66383

LOCATION	LETTERS AND SYMBOLS (SQ FT)	THERMOPLASTIC PAVEMENT MARKING								LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING				SHORT-TERM PAVEMENT MARKING LINE - 4" YELLOW CENTERLINE (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL*** (SQ FT)	RAISED REFLECTIVE PAVEMENT MARKERS (EACH)		
		LINE - 4"		EDGE LINE		LINE - 6"	LINE - 8"	LINE - 24"	LINE - 4"		LINE - 6"	LINE - 8"							
		CENTERLINE	SOLID	SOLID	SOLID	CENTERLINE	LANE LINE	STOP BAR	CENTERLINE		SOLID	SOLID	SOLID	CENTERLINE				LANE LINE	
	SOLID YELLOW LEFT (FOOT)	SOLID YELLOW RIGHT (FOOT)	SOLID WHITE LEFT (FOOT)	SOLID WHITE RIGHT (FOOT)	SKIP-DASH YELLOW (FOOT)	WHITE (FOOT)	WHITE (FOOT)	SKIP-DASH YELLOW (FOOT)	SOLID YELLOW LEFT (FOOT)	SOLID YELLOW RIGHT (FOOT)	SOLID WHITE LEFT (FOOT)	SOLID WHITE RIGHT (FOOT)	SKIP-DASH YELLOW (FOOT)	LANE WHITE (FOOT)					
U.S. ROUTE 150																			
408+02.77 TO 420+23		1082	1082												122	762	14		
420+23 TO 426+04		453						120							58	231	6		
426+04 TO 436+07								250							100	159	13		
436+07 TO 443+46			620	436	270			160		620	436	270			74	547	8		
443+46 TO 446+63				316	319			80			316	319			32	263	4		
446+63 TO 454+02		739		739	741			190		739	739	741			74	859	9		
454+02 TO 496+79				4282	4276			1070			4282	4276			428	3528	53		
496+79 TO 507+35			1056	1058	1055			260		1056	1058	1055			106	1221	14		
507+35 TO 517+91		918		1059	858			240		918	1059	858			106	1100	12		
517+91 TO 565+43				4748	4758			1180			4748	4758			475	3914	59		
565+43 TO 571+76			633	633	633			160		633	633	633			63	734	8		
571+76 TO 575+99				423	423			110			423	423			42	351	5		
575+99 TO 583+91		792		792	792			200		792	792	792			79	918	10		
583+91 TO 597+11				1124	1320			300			1124	1320			132	1008	15		
597+11 TO 607+67			1056	1056	1056			260			1056	1056			106	1221	13		
607+67 TO 610+31				264	264			70			264	264			27	220	3		
610+31 TO 615+59		528		528	528			130		528	528	528			53	611	7		
615+59 TO 682+12				6468	6285			1590		528	6468	6285			665	5264	83		
682+12 TO 689+51			739	738	741			180		739	738	741			74	854	9		
689+51 TO 692+15				264	264			70			264	264			26	220	3		
692+15 TO 700+07		792		792	792			200		792	792	792			79	918	10		
700+07 TO 713+27			1320	1324	1318			330			1324	1318			132	1529	17		
713+27 TO 723+83		1056		1059	1055			260		1056	1059	1055			106	1221	13		
723+83 TO 729+11				528	528			130			528	528			53	435	6		
729+11 TO 738+61			950	948	952			240			948	952			95	1101	12		
738+61 TO 744+95		634	634	628	640					634	634	628	640		63	866	8		
744+95 TO 749+17		422		422	422			110		422	422	422			42	491	5		
749+17 TO 754+51.18				535	535			130			535	535			54	440	7		
SUBTOTAL		7416	8090	31164	30825			8020		7416	8090	31164	30825		3466	30986	426		
SEMINARY STREET																			
1100+00.00 TO 1101+31.14								25											
C.H. 36 NORTH																			
1203+00.00 TO 1210+00.00		589	589	711	712					589	589	711	712		70	965	8		
T.R. 2075																			
1300+20.00 TO 1306+43.18								11											
C.H. 36 SOUTH																			
1500+00.00 TO 1502+56.21	17.6	229	229	248	335			86	32	17.6	229	229	248	335	86	26	356	3	
T.R. 2200																			
1601+00.00 TO 1602+98.36								38											
T.R. 2325																			
1700+00.00 TO 1702+50.00								35											
T.R. 2375																			
1800+50.00 TO 1802+39.72								26											
T.R. 2400																			
1900+00.00 TO 1901+50.00								27											
T.R. 2450																			
2400+50.00 TO 2402+32.08								29											
ENTRANCE																			
441+87 RT	17.6	72	72					70	30	17.6	72	72				123			
SUBTOTAL	35.2	890	890	959	1047			156	281	35.2	890	890	959	1047	86	96	1444	11	
TOTAL - PER APPLICATION*	35.2			81281				8020	156	281	35.2			81281	8020	86	3562	32430	437
GRAND TOTAL**	35.2			81281				8020	156	281	35.2			243843	24060	258	10686	32430	437

\* TOTAL REPRESENTS THE QUANTITIES REQUIRED FOR ONE APPLICATION OF A GIVEN PAVEMENT MARKING.  
 \*\* GRAND TOTAL INCLUDES QUANTITIES FOR 3 APPLICATIONS OF SHORT-TERM AND TEMPORARY PAVEMENT MARKING.  
 \*\*\* WORK ZONE PAVEMENT MARKING REMOVAL ASSUMES THE ONLY REMOVAL REQUIRED WILL BE FROM ONE APPLICATION OF SHORT-TERM AND ONE APPLICATION OF TEMPORARY FOLLOWING PLACEMENT OF THE SURFACE COURSE.

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.S. 1517 (U.S. ROUTE 150)  
 PAVEMENT MARKING SCHEDULE

SCALE: VERT. DATE  
 HORIZ. DATE  
 DRAWN BY  
 CHECKED BY

PLAN SURVEYED ALIGNED CHECKED BY: DATE: 1517 (2)RS-3 (3)RS-4 MCLEAN 223 32  
 NOTE BOOK NO. 66383  
 PROFILE SURVEYED GRADES CHECKED BY: DATE: 1517 (2)RS-3 (3)RS-4 MCLEAN 223 32  
 NOTE BOOK NO. 66383  
 COMPANY NAME: #COMPANY NAME#  
 PROJECT CONTACT: #PROJECT CONTACT#  
 CLIENT: #CLIENT#  
 DATE: #DATE#  
 FILE#