

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	IN & TS	KENDALL	174	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE TYPE:			
				STP FUNDS		HES FUNDS	
				LIGHTING Y030-1E ^{100%} CTTY	ROADWAY I000 ^{80% FED. 20% ST.}	SIGNALS Y031-1F ^{90% FED. 10% ST.}	ROADWAY I000-1A ^{90% FED. 10% ST.}
66700095	PERMANENT SURVEY MARKERS	EACH	14		14		
67000400	ENGINEER'S FIELD OFFICE TYPE A	CAL MO	15		7		8
67100100	MOBILIZATION	L SUM	1		1		
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1		1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1		1		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1		1		
70103815	TRAFFIC CONTROL AND SURVEILLANCE	CAL DA	40		40		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3942		1971		1971
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	281		140.5		140.5
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	39829		19914.5		19914.5
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1841		920.5		920.5
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1691		845.5		845.5
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	178		89		89
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1313		657		656
78300105	PAVEMENT MARKING REMOVAL	FOOT	685		342		343
* 72000100	SIGN PANEL - TYPE 1	SQ FT	200		67		133
* 72000200	SIGN PANEL - TYPE 2	SQ FT	77		51		26
* 73000100	WOOD SIGN SUPPORT	FOOT	620				620
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	281				281
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34829				34829
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1841				1841
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1691				1691
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	178				178
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	324		162		162
78200300	PRISMATIC CURB REFLECTOR	EACH	9		5		4
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	132		66		66
• 80500200	SERVICE INSTALLATION, TYPE B	EACH	1			1	
• 80803530	TRAFFIC SIGNAL WOOD POLE, 25 FT., CLASS 4	EACH	1			1	
• 81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	424			424	
• 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1841			1841	
• 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	123			123	
• 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	70			70	
• 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	125			125	
• 81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	218			218	
• 81400400	CONCRETE HANDHOLE	EACH	13			13	
• 81400600	CONCRETE DOUBLE HANDHOLE	EACH	1			1	

*SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____ DATE _____

DRAWN BY _____ CHECKED BY _____

4/27/2006 c:\puro\pccr\1992004\schmdu\res.dgn