

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(27-38)I-1 & (27-1)I-2	FORD	14	4
ILLINOIS				

SUMMARY OF QUANTITIES

CONSTRUCTION CODE: **J000**

RURAL
100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SECTION (27-38)I-1	SECTION (27-1)I-2
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4		4
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.25	0.75
70101605	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	1		1
70103815	TRAFFIC CONTROL AND SURVEILLANCE	CALDAY	40	10	30
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1775		1775
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1170		1170
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	2390		2390
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	990		990
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	40	5	35
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1537		1537
X0301766	DRILL AND GROUT #6 TIE BARS	EACH	235		235
X0301894	REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE UNDERDRAINS	EACH	1		1
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAINS REMOVAL	EACH	1		1
X3120700	STABILIZED SUB-BASE 4", SUPERPAVE	SQ YD	912		912
Z0001058	AGGREGATE SUBGRADE 18"	SQ YD	1432		1432
● Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	EACH	1		1
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	819		819

● SFTY 3N

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAI 57
SEC: (27-38)I-1 & (27-1)I-2
FORD COUNTY

Date: April 5, 2006
File Name: ar/projects/emo107/c0303/040506.dgn