

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(7R-1,10)I	KANKAKEE	11	6
STA. 248+00		TO STA. 259+00		
ILLINOIS				
*FAP 332 & FAS 310 (IL 1 & IL 17)				

PAVEMENT PATCHING SCHEDULE

LOCATION STATION	LEFT LANE						RIGHT LANE						NOTES
	PAVEMENT PATCHING 11"			DOWEL BARS	SAW CUTS	PAVE'T FABRIC	PAVEMENT PATCHING 11"			DOWEL BARS	SAW CUTS	PAVE'T FABRIC	
	TYPE II	TYPE III	TYPE IV	EACH	FOOT	SQ YD	TYPE II	TYPE III	TYPE IV	EACH	FOOT	SQ YD	
	SQ YD	SQ YD	SQ YD				SQ YD	SQ YD	SQ YD				
STA. 248+00													BEGIN PROJECT
STA. 248+28	13			34	69								
STA. 248+50							13			34	69		
STA. 248+71	13			35	70								
STA. 248+92	13			35	70		13			35	70		
STA. 249+55							13			36	71		
STA. 249+60			34	36	90	34							
STA. 249+82							13			36	72		
STA. 250+03	14			37	74								
STA. 250+19							14			37	73		
STA. 250+87	14			38	75		14			38	75		
STA. 251+45							14			39	76		
STA. 251+51	15			39	77								
STA. 251+93	15			40	78		15			40	77		
STA. 252+40	15			41	79		15			41	79		
STA. 252+72	15			41	79								
STA. 252+77								19		53	97	19	
STA. 252+93	15			40	79								
STA. 253+35	15			40	79								
STA. 253+52	15			40	79								CENTERLINE IL 1 (NORTH) & IL 17 (SOUTH)
STA. 254+46								18		49	92	18	
STA. 254+78	15			40	78		15			40	78		
STA. 254+94							15			40	78		
STA. 254+99	15			40	78								
STA. 255+31	15			40	78								
STA. 255+84	15			40	78		15			40	78		
STA. 255+99							15			40	78		
STA. 256+10													
STA. 256+36	15			40	78		15			40	78		
STA. 256+73		20		40	82	20		20		40	82	20	
STA. 257+16	15			40	78		15			40	78		
STA. 257+37	15			40	78		15			40	78		
STA. 257+74								24		40	86	24	
STA. 257+79	15			40	78								
STA. 258+16	15			40	78								
STA. 258+42	15			40	78		15			40	78		
STA. 258+69	15			40	78		15			40	78		
STA. 259+00													END PROJECT
TOTALS	337	20	34	976	1938	53	259	81		878	1721	81	

Date: 4/21/2006
c:\projects\cm311\cm311\details.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE

FAP 332 & FAS 310
SECTION (7R-1,10)I
KANKAKEE COUNTY