

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-4B)-4	LASALLE	18	3
FED. ROAD DIST. NO.		ILLINOIS	NON-FED. AID PROJECT	

SUMMARY OF QUANTITY

CONSTRUCTION CODE: SFTY-2A

CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
50102500	CONCRETE REMOVAL (SPECIAL)	CU YD	60
50300255	CONCRETE SUPERSTRUCTURE	CU YD	60
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	17280
67000400	ENGINEER'S FIELD OFFICE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	3
70101605	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	3
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4340
70400100	TEMPORARY CONCRETE BARRIER	FOOT	18370
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	18370
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LIINE 4"	FOOT	14242
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LIINE 6"	FOOT	1780
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	13151
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4340
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	180
78003135	<i>PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, LINE 6", SPECIAL</i>	FOOT	1,780
▲ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	3
▲ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	3
Z0047300	PROTECTIVE SHIELD	SQ YD	1200
X0325518	ULTRA-THIN BONDED WEARING COURSE	SQ YD	28900

▲SFTY 3N *SPECIALTY ITEM

DATE: 06/21/2005
C:\PROJECTS\0258\PLAN\ARE LINDO\66678\DETAILS.DGN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 I-39 OVER THE ILLINOIS RIVER
 F.A.I. ROUTE 39
 SECTION: (50-4B)-4
 LASALLE COUNTY
 S.N. 050-0191