

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	48B	VERMILION	27	11

CONTRACT NO. 70462

TEMPORARY DITCH CHECKS

CHANNEL LOCATION	EACH
12+50	1
14+00	1
15+50	1
17+00	1
TOTAL	4

INLET & PIPE PROTECTION

ILL 1 LOCATION	OFFSET	EACH
824+77	34.0' RT	1

REMOVAL OF EXISTING STRUCTURE

ILL 1 LOCATION	EACH
824+77	1

NAME PLATES

ILL 1 LOCATION	EACH
824+77	1

BOX CULVERT END SECTION

ILL 1 LOCATION	OFFSET	EACH
824+77	34.0' RT	1
824+77	32.0' LT	1
TOTAL		2

POROUS GRANULAR BACKFILL

ILL 1	STATION TO STATION	VOLUME (CU. YD.)
	824+61 824+66	53.88
	824+66 824+70	64.92
	824+84 824+88	64.92
	824+88 824+93	53.88
	TOTAL	237.6
	USE	238

PRECAST CONCRETE BOX CULVERT 12' X 4' (M273)

ILL 1 LOCATION	ILL 1 LOCATION	SIZE (FOOT)	LENGTH (FOOT)
824+77 32.0' LT	824+77 34.0' RT	12' X 4'	66.0

CHANNEL EXCAVATION

CHANNEL	STATION TO STATION	VOLUME (CU. YD.)
	10+50 16+50	571

EXPLORATION TRENCH 52" DEPTH

ILL 1	STATION TO STATION	OFFSET	LENGTH (FEET)
	824+52 825+02	34.0' RT	50.0
	824+52 825+02	32.0' LT	50.0
	TOTAL		100.0

COMBINATION CURB AND GUTTER REMOVAL

ILL 1	STATION TO STATION	OFFSET	LENGTH (FEET)
	824+60 824+94	21' RT	34.0
	824+60 824+94	21' LT	34.0
	TOTAL		68.0

SIDEWALK REMOVAL

ILL 1	STATION TO STATION	OFFSET	AREA (SQ. FT.)
	824+60 824+94	27' LT	170

REVISED 7/13/06