

SCHEDULE OF QUANTITIES

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|----------------|---------|-----------|-----------------|--------------|
| 332 | 48B | VERMILION | 27 | 11 |

CONTRACT NO. 70462

TEMPORARY DITCH CHECKS

| CHANNEL LOCATION | EACH |
|---------------------|------|
| 12+50 | 1 |
| 14+00 | 1 |
| 15+50 | 1 |
| 17+00 | 1 |
| TOTAL | 4 |

INLET & PIPE PROTECTION

| ILL 1 LOCATION | OFFSET | EACH |
|-------------------|----------|------|
| 824+77 | 34.0' RT | 1 |

REMOVAL OF EXISTING STRUCTURE

| ILL 1 LOCATION | EACH |
|-------------------|------|
| 824+77 | 1 |

NAME PLATES

| ILL 1 LOCATION | EACH |
|-------------------|------|
| 824+77 | 1 |

BOX CULVERT END SECTION

| ILL 1 LOCATION | OFFSET | EACH |
|-------------------|----------|------|
| 824+77 | 34.0' RT | 1 |
| 824+77 | 32.0' LT | 1 |
| TOTAL | | 2 |

POROUS GRANULAR BACKFILL

| ILL 1 | STATION TO | STATION | VOLUME (CU. YD.) |
|-------|------------|---------|---------------------|
| | 824+61 | 824+66 | 53.88 |
| | 824+66 | 824+70 | 64.92 |
| | 824+84 | 824+88 | 64.92 |
| | 824+88 | 824+93 | 53.88 |
| | TOTAL | | 237.6 |
| | USE | | 238 |

PRECAST CONCRETE BOX CULVERT 12' X 4' (M273)

| ILL 1 LOCATION | ILL 1 LOCATION | SIZE (FOOT) | LENGTH (FOOT) |
|-------------------|-------------------|----------------|------------------|
| 824+77 32.0' LT | 824+77 34.0' RT | 12' X 4' | 66.0 |

CHANNEL EXCAVATION

| CHANNEL | STATION TO | STATION | VOLUME (CU. YD.) |
|---------|------------|---------|---------------------|
| | 10+50 | 16+50 | 1219 |

EXPLORATION TRENCH 52" DEPTH

| ILL 1 | STATION TO | STATION | OFFSET | LENGTH (FEET) |
|-------|------------|---------|----------|------------------|
| | 824+52 | 825+02 | 34.0' RT | 50.0 |
| | 824+52 | 825+02 | 32.0' LT | 50.0 |
| | TOTAL | | | 100.0 |

COMBINATION CURB AND GUTTER REMOVAL

| ILL 1 | STATION TO | STATION | OFFSET | LENGTH (FEET) |
|-------|------------|---------|--------|------------------|
| | 824+60 | 824+94 | 21' RT | 34.0 |
| | 824+60 | 824+94 | 21' LT | 34.0 |
| | TOTAL | | | 68.0 |

SIDEWALK REMOVAL

| ILL 1 | STATION TO | STATION | OFFSET | AREA (SQ. FT.) |
|-------|------------|---------|--------|-------------------|
| | 824+60 | 824+94 | 27' LT | 170 |