

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	34RS-2	MADISON	39	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT _____		

RESURFACING SCHEDULE

LOCATION			BITUMINOUS SURFACE REMOVAL 1.5"	BITUMINOUS SURFACE REMOVAL 3"	BIT. MAT'L PRIME COAT	AGGREGATE PRIME COAT	BITUMINOUS SHOULDER 1.5"	SURFACE COURSE 1.5"	STRIP REFLECTIVE CRACK CONTROL TREATMENT
STA TO STA			(SQ YD)	(SQ YD)	(TON)	(TON)	(TON)	(TON)	(FT)
IL 157									
982+30.00	TO	984+20.00	906.67		0.24	1.14	12.32	63.84	
984+20.00	TO	995+60.00	5328.89		1.43	6.84	64.59	383.04	1140.00
995+60.00	TO	997+88.50	863.22		0.27	1.29		72.51	228.50
997+88.50	TO	999+36.00	524.44		0.16	0.79		44.05	
999+36.00	TO	1000+84.00	587.89		0.18	0.88		49.38	148.00
1000+84.00	TO	1002+77.00	825.61		0.26	1.24		69.35	193.00
1002+77.00	TO	1004+28.00	599.81		0.19	0.90		50.38	151.00
1004+28.00	TO	1025+44.00	7758.67		2.43	11.64		651.73	
1028+62.00	TO	1028+74.37	54.98		0.02	0.08		4.62	
77+27.61	TO	98+86.00	8596.84	996.00	3.00	14.39		805.80	
TOTAL =			26048	996	8.2	40	77	2195	1861

* BITUMINOUS SURFACE REMOVAL 3" SHALL BE FROM STA. 88+22.00 TO 90+88.00 IN THE SOUTHBOUND LANE AND FROM 88+88.00 TO STA. 90+88.00 IN THE NORTHBOUND AND TURN LANE.

SIDEROAD RESURFACING SCHEDULE

LOCATION	BITUMINOUS SURFACE REMOVAL 1.5"	BIT. MAT'L PRIME COAT	AGGREGATE PRIME COAT	INCIDENTAL BITUMINOUS SURFACING
	(SQ YD)	(TON)	(TON)	(TON)
4th Street	245.44	0.08	0.37	20.62
3rd Street	173.33	0.05	0.26	14.56
2nd Avenue	164.67	0.05	0.25	13.83
1st Avenue	117.44	0.04	0.18	9.86
Mckinley	97.89	0.03	0.15	8.22
Franklin (East Side)	76.89	0.02	0.12	6.46
Hale Street(West Side)	109.78	0.03	0.16	9.22
Hale Street(East Side)	102.00	0.03	0.15	8.57
Holy Oak	96.33	0.03	0.14	8.09
Nelson	114.67	0.04	0.17	9.63
Jefferson (East Side)	88.67	0.03	0.13	7.45
Jefferson (West Side)	88.78	0.03	0.13	7.46
Park (East)	112.78	0.04	0.17	9.47
Longfellow	100.44	0.03	0.15	8.44
Schwarz (East)	203.00	0.06	0.30	17.05
Schwarz (West)	362.77	0.11	0.54	30.47
TOTAL =	2255	0.7	4	189

PAVEMENT MARKING SCHEDULE

LOCATION			THERMOPLASTIC PAVEMENT MARKING										RAISED REFLECTIVE PAVEMENT MARKERS			RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
			4"					6"	12"	12"	24"	LETTERS & SYMBOLS	ONE WAY CRYSTAL	ONE WAY AMBER	TWO WAY AMBER	
			SOLID YELLOW LANE LINE	SOLID WHITE LANE LINE	SOLID WHITE EDGE LINE	4" SOLID YELLOW SKIP-DASHED	SOLID DOUBLE YELLOW LINE	SOLID WHITE CROSS WALK	SOLID YELLOW DIAGONAL	STOP BARS	CROSS WALK	TURN ARROW				
STATION	TO	STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH		EACH	EACH
982+30	TO	983+50	240		240	60						31.2			6	6
983+50	TO	989+00	408	150	854	100	540			48		93.6	6		18	24
989+00	TO	995+00	1200		1004	300						93.6			30	30
995+00	TO	999+50	900		840	240						93.6			22	22
999+50	TO	1005+50	375	190	958	80	850	342	30	48	246	93.6	7	6	18	31
1005+50	TO	1011+50	1200		1138	300	1200	77			48	93.6			32	32
1011+50	TO	1017+50	1200		1138	300		75			48	93.6			30	30
1017+50	TO	1023+00	1100		1008	280		120			96	93.6			26	26
1023+00	TO	1028+50	488		348	120					48	31.2			14	14
1028+50	TO	81+00	768		770	200						62.4			18	18
81+00	TO	86+50	1100		887	280		169				108			28	28
86+50	TO	92+50	454	150	1040	80	540	190		48	259	124.8	6		20	26
92+50	TO	97+50	732	67	894	200		176			120	93.6	2		20	22
97+50	TO	98+86		8	272							15.6	1		4	5
SUB-TOTALS			10165	565	11391	2540	1930	1149	30	144	865	1122	22	6	286	314
TOTALS					26591			1149	174		865	1122		314		314

*STATION EQUATION: 1028+74.37 = 77+27.61

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

FAP ROUTE 600
SECTION 34RS-2
MADISON COUNTY

PLAN SURVEYED BY DATE
PLOTTED BY DATE
CHECKED BY DATE
NO. OF SHEETS FILED
CADD FILE NAME

5/15/2006
5/15/2006
5/15/2006
5/15/2006
5/15/2006