

SUMMARY OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1780	24-BR-2	CLINTON	63	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES			80% FED 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		X080-2A	SFTY-3N
X0325294	PREFORMED JOINT STRIP SEAL	FOOT	378	378	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2	
40600300	AGGREGATE (PRIME COAT)	TON	1	1	
40600990	TEMPORARY RAMP	SQ YD	53	53	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	480	480	
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	693	693	
44004250	PAVED SHOULDER REMOVAL	SQ YD	48	48	
50101600	REMOVAL OF EXISTING SUPERSTRUCTURES	L SUM	1	1	
50102400	CONCRETE REMOVAL	CU YD	9.3	9.3	
50300150	NEOPRENE EXPANSION JOINT 2"	FOOT	33	33	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	230.3	230.3	
50300300	PROTECTIVE COAT	SQ YD	577	577	
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	22028	22028	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1650	1650	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	25590	25590	
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	159	159	
51401600	TEMPORARY BRIDGE RAIL	FOOT	844	844	
51500100	NAME PLATES	EACH	1	1	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	2833	2833	
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	6343	6343	
58700200	BRIDGE SEAT SEALER	SQ FT	1299	1299	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100110	TRAFFIC BARRIER TERMINAL, TYPE 11	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	146	146	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	26	26	
67100100	MOBILIZATION	L SUM	1	1	
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	

SUMMARY OF QUANTITIES			80% FED 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		X080-2A	SFTY-3N
70106600	TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED CONTROLLER)	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	128	128	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3101	3101	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1162.5	1162.5	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1076	1076	
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	1000	1000	
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	162.5	162.5	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3101	3101	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	11	11	
* 78100300	REPLACEMENT REFLECTOR	EACH	4	4	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4	
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	22	22	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	22	22	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1034	1034	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	9	9	
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	1110	1110	
X0321468	PLUG EXISTING DECK DRAINS	EACH	40	40	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	356	356	
X0325356	PREFORMED JOINT STRIP SEAL, 1"	FOOT	346.5	346.5	
X3560130	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH	SQ YD	127	127	
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	385	385	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	4	4	
X7200200	WIDE LOAD SIGNING	L SUM	1	1	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	310	310	
Z0002600	BAR SPLICERS	EACH	88	88	
Z0015595	DECK DRAIN EXTENSIONS	EACH	26	26	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	70	70	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0053750	RETROFIT CONCRETE PARAPET	FOOT	450	450	

PLOT DATE = 5/16/2006
 PLOT SCALE = 1/4" = 10'-0"
 PLOT SCALE = 1/8" = 20'-0"
 REFERENCE = #REF#

*SPECIALTY ITEMS

REV.