STATE OF ILLINOIS


DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

PROPOSED HIGHWAY PLANS


FAS ROUTE 1780 (OLD US 50) SECTION 24-BR-2 PROJECT BHS-1780 (120 SUPERSTRUCTURE REPLACEMENT **CLINTON COUNTY**

C-98-040-06



3 SPAN STEEL AND 12 SPAN PPC DECK BEAM COMBINATION REMOVE & REPLACE PPC DECK BEAMS IN KIND AND OVERLAY ENTIRE STRUCTURE OVER SHOAL CREEK REGIN STA 100 + 75 END STA 111+00 SN 014-0062






24-BR-2


CONTRACT NO. 76899 COUNTY TOTAL SHEET NO.

CLINTON 63



PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

MICROFILMED REEL NUMBER AWARDED RESIDENT ENGINEER AS BUILT CHANGES WERE MADE ON THE FOLLOWING SHEETS



FOR INDEX OF SHEETS, SEE SHEET NO. 2

ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123

DESIGN DESIGNATION

ADT = 5400 (2003)

38.60972 89.49508 LONG

GROSS LENGTH 0.16 MI NET LENGTH 0.16 MI

CONTRACT NO. 76899

CLINTON COUNTY

346-3179 (618)

(618) 346 - 3209

ARTHUR MUEHLFELD PATTI LEBEAU ENGINEER:

CONTACT: SQUAD

PROJECT

SECTION 24-BR-2

FAS ROUTE 1780

 			CON	1117	<i>,</i> ,	140.	1003
 F.A.S. RTE.	SECTIO	N	COUN	TY	SH	TAL EETS	SHEET NO.
1780	24-ER-	2	CLINT	ON		63	2
STA.		TO	STA.				
FED. ROAD	DIST. NO.	ILLINOIS	FED.	AID	PRO	DJECT	

INDEX OF SHEETS

- **COVER SHEET**
- INDEX OF SHEETS, HIGHWAY STANDARDS. 2 **GENERAL NOTES & COMMITMENTS**
- SUMMARY OF QUANTITES
- TYPICAL SECTIONS
- SCHEDULES 5
- **TIE POINTS & BENCHMARKS**
- **REMOVAL PLAN**
- 8_10 PLAN SHEETS
- STAGE CONSTRUCTION 11-21
- **PAVEMENT MARKING SHEETS** 22-24
- 25-63 **BRIDGE PLANS**

GENERAL NOTES:

- 1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
- 2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- 3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - * CITY OF BREESE (WATER)
 - * CENTERPOINT ENERGY (GAS)
 - * CHARTER COMMUNICATIONS, INC. • QWEST COMMUNICATIONS
 - * SBC (COMMUNICATIONS)

MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY *. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

- 4. THE CONTRACTOR SHALL PROVIDE TWO SIGNAL HEADS (EACH) FOR THE APPROACHES ON BOTH SIDE ROADS ON THE WEST END OF THE STRUCTURE. THE SIGNALS, DETECTOR LOOPS, THE NUMBER OF TURNS OF WIRE IN THE LOOPS SHALL BE AS DETERMINED BY THE ENGINEER.
- 5. THE CONTRACTOR SHALL FURNISH AND INSTALL WOOD SIGN SUPPORTS IN ACCORDANCE WITH SECTION 730 OF THE STANDARD SPECIFICATIONS; HOWEVER, INSTALLATION BY METHOD 'A' (ARTICLE 730.04(d)) SHALL BE THE ONLY METHOD PERMITTED.
- 6. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT THE BEGINNING AND ENDING OF THE PROJECT AND WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLOURESCENT ORANGE.
- 7. ALL SIGNS THAT INTERFERE WITH CONSTRUCTION OPERATIONS SHALL BE REMOVED, STORED AND RE-ERECTED ACCORDING TO ARTICLE 107.25 OF THE STANDARD SPECIFICATIONS.
- 8. ANY DAMAGE TO SIGNS CAUSED BY CONSTRUCTION ACTIVITIES SHALL BE REPLACED AT THE CONTRACTOR'S
- 9. ALL SAW CUTTING FOR REMOVAL ITEMS SHALL BE FULL DEPTH AND SHALL BE INCLUDED IN THE COST OF THE REMOVAL ITEM.
- 10. NO TRENCHES OR OPEN PITS WILL BE PERMITTED ADJACENT TO A TRAFFIC LANE DURING NON-WORKING HOURS. ALL WIDENING TRENCHES SHALL BE BACKFILLED DURING THE SAME WORKING DAY IT WAS
- 11. THE COST FOR EARTH EXCAVATION AND GRADING AND SHAPING ALONG THE PROPOSED WIDENING SHALL BE INCLUDED IN THE COST OF "PAVED SHOULDER REMOVAL".
- 12. CHANGEABLE MESSAGE SIGNS MUST NOTIFY THE PUBLIC OF THE ROAD CLOSURE TWO WEEKS PRIOR TO
- 13. THE TRAFFIC CONTROL MEASURES SHOWN ON PLANS FOR STAGE II AND III SHALL SUPPLEMENT AND BE IN ACCORDANCE WITH TRAFFIC CONTROL STANDARD 701321.
- 14. THE COST OF "BARRICADES, TYPE III" USED DURING STAGE I SHALL BE INCLUDED IN THE COST OF "TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR". THOSE USED DURING STAGE II AND III SHALL BE INCLUDED IN THE COST OF "TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)".
- 15. THE COST TO REMOVE THE EXISTING TRAFFIC BARRIER TERMINALS ATTACHED TO THE STRUCTURE AND TBT, TYPE 11'S USED DURING STAGE III SHALL BE INCLUDED IN THE COST OF "GUARDRAIL REMOVAL".
- 16. A QUANTITY OF 1162.5 FEET OF "TEMPORARY PAVEMENT MARKING LINE 6 INCHES" WHITE HAS BEEN INCLUDED IN THE PLANS FOR PAINTING THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER.
- 17. THE BARRIER UNIT AT EACH END OF THE TRAFFIC CONTROL INSTALLATION SHALL BE SECURED TO THE PAVEMENT OR SHOULDER USING ALL SIX ANCHORING PINS FOR F-SHAPE BARRIER OR ALL SIX DOWEL BARS FOR NEW JERSEY SHAPE BARRIER.
- 18. THE TEMPORARY CONCRETE BARRIER (STATE OWNED) IS LOCATED AT IL ROUTE 111, NORTH OF 1-55/70. THE CONTRACTOR SHALL PICK UP THE BARRIER AND RETURN THE BARRIER TO THE SAME LOCATION UPON COMPLETEION OF THE PROJECT. ANY DAMAGED BARRIER WILL NOT HAVE TO BE REPLACED. THE CONTRACTOR SHALL DISPOSE OF DAMAGED CONCRETE BARRIER IN AN APPROVED DUMP SITE. THE CONNECTOR PINS SHALL BE FURNISHED BY THE CONTRACTOR AND THE COST SHALL BE INCLUDED WITH THE COST OF "TEMPORARY CONCRETE BARRIER (STATE OWNED)".

EROSION CONTROL PLAN

ANY AREAS DISTURBED DUE TO CONSTRUCTION ACTIVITIES SHALL BE SEEDED (TEMPORARY AND PERMANENT) AT THE CONTRACTOR'S EXPENSE AND NO OTHER COMPENSATION WILL BE PERMITTED.

ALL EROSION CONTROL PRODUCTS FURNISHED SHALL BE SPECIFICALLY RECOMMENDED BY THE MANUFACTURER FOR THE USE SPECIFIED IN THE EROSION CONTROL PLAN. PRIOR TO THE APPROVAL AND USE OF THE PRODUCT. THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A NOTARIZED CERTIFICATION BY THE PRODUCER STATING THE INTENDED USE OF THE PRODUCT AND THAT THE PHYSICAL PROPERTIES REQUIRED FOR THIS APPLICATION ARE MET OR EXCEEDED. THE CONTRACTOR SHALL PROVIDE MANUFACTURER RECOMMENDED INSTALLATION PROCEDURES TO FACILITATE THE ENGINEER IN CONSTRUCTION INSPECTION.

TEMPORARY SEEDING AND MULCH SHALL BE COMPLETED ON A WEEKLY BASIS ON EXPOSED GROUND AND SHALL BE IN ACCORDANCE WITH SECTION 280 OF THE STANDARD SPECIFICATIONS. TEMPORARY EROSION CONTROL SEEDING SHALL BE APPLIED AT A RATE OF 100 LBS/ACRE.

EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.

FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE WITH CLASS 2 SEEDING.

COMMITMENTS

THE BRIDGE WILL BE CLOSED AND A DETOUR IN PLACE FOR STAGE I CONSTRUCTION THIS DETOUR IS LIMITED TO 14 CALENDAR DAYS MAXIMUM.

A STREAM GAUGING SYSTEM IS LOCATED ON THE NORTH SIDE OF SPAN 2. THIS WILL HAVE TO BE REMOVED PRIOR TO THE PARAPET RETROFIT. USGS SHALL BE NOTIFIED ONE WEEK PRIOR TO THE RETROFIT IN THE AREA IN ORDER FOR THEM TO REMOVE IT. THEY SHALL ALSO BE NOTIFIED AFTER CONCRETE IS CURED IN ORDER FOR THEM TO REPLACE IT.

CONTACT INFORMATION IS AS FOLLOWS:

JOHN MAURER US GEOLOGICAL SURVEY FEDERAL BUILDING 105 SOUTH 6TH STREET, ROOM 231 MT. VERNON, IL 62864 OFFICE PHONE (618) 242-4495 CELLULAR PHONE (618) 316-1455

IT IS ANTICIPATED THAT THE CONTRACTOR MAY TEMPORARILY IMPACT WETLANDS LOCATED ON EITHER THE NORTH OR SOUTH SIDE OF THE STRUCTURE WHILE ACCESSING THE PROJECT SITE. UPON DETERMINATION BY THE CONTRACTOR OF HIS ACCESS, A WETLAND SURVEY WILL BE CONDUCTED BY THE DEPARTMENT. IN ORDER TO COMPENSATE FOR THE TEMPORARY IMPACTS, ANY EXPOSED SOIL CAUSED BY THE EQUIPMENT DRIVING OVER THE WETLANDS MUST BE RESEDED WITH AGROSTIS ALBA (REDTOP) AT 10 LBS/ACRE. AT NO TIME WILL THE CONTRACTOR BE PERMITTED TO PLACE ANY PERMANENT MEASURES (ROCK OR HAUL ROAD) IN THE WETLAND AREA. THE MEASURES AS NOTED ABOVE WILL NOT BE PAID FOR SEPERATELY, BUT SHALL BE INCLUDED IN THE COST OF THE CONTRACT.

PERTINENT INFORMATION

ACCESS TO SIDE ROADS SHALL BE MAINTAINED AT ALL TIMES.

REVISIONS	ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME D	ALE !
	INDEX OF SHEETS, HIGHWAY
	STANDARDS, GENERAL NOTES
	AND COMMITMENTS
	FAS ROUTE 1780
ļ	
	SECTION 24-BR-2
	CLINTON COUNTY
	SN 014-0062

HIGHWAY STANDARDS

701311-02

515001-02 701321-08 631031-05 701326-02 631051-01 702001-06

000001-04

635011--01 704001-02 701011-01 780001-01

701301-02 781001-02 701306--01 BLR 21-6

DATE NAME SCALE

SUMMARY OF QUANTITIES


| F.A.S. | SECTION | COUNTY | TOTAL SHEETS | NO. 1780 | 24-BR-2 | CLINTON | 63 | 3 | STA. | TO STA. | FED. ROAD DIST. NO. | ILLINOIS | FED. AID | PROJECT |

	SUMMARY OF QUANTITIES		80% FED 20% STATE	X080-2A	SFTY-3N	
CODE NO	ITEM	UNIT	TOTAL. QUANTITIES			
X0325 ,2 94	PREFORMED JOINT STRIP SEAL	FOOT	378	37.8		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2		
40600300	AGGREGATE (PRIME COAT)	TON	1	1		
40600990	TEMPORARY RAMP	SQ YD	53	53		
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	480	480		
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	693	693		
44004250	PAVED SHOULDER REMOVAL	SQ YD	48	48		
50101600	REMOVAL OF EXISTING SUPERSTRUCTURES	L SUM	1	1		
50102400	CONCRETE REMOVAL	CU YD	9.3	9.3		
50300150	NEOPRENE EXPANSION JOINT 2"	FOOT	33	33		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	230.3	230.3		
50300300	PROTECTIVE COAT	SQ YD	577	577		
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	22028	22028		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1650	1650		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	25590	25590		
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	F00T	159	159		
51401600	TEMPORARY BRIDGE RAIL	FOOT	844	844		
51500100	NAME PLATES	EACH	1	1		
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	2833	2833		
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	6343	6343		
58700200	BRIDGE SEAT SEALER	SQ FT	1299	1299		
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
63100110	TRAFFIC BARRIER TERMINAL, TYPE 11	EACH	2	2		
63200310	GUARDRAIL REMOVAL	F00T	146	146		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	26	26		
67100100	MOBILIZATION	L SUM	1	1		
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LSUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1		
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1		
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1		

Γ		CUMMADY OF QUANTITIES		80% FED	CONS	TRUCTION TYPE C	ODE
		SUMMARY OF QUANTITIES		20% STATE TOTAL	X080-2A	SFTY-3N	
	CODE NO	ITEM	UNIT	QUANTITIES			
	70106600	TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED CONTROLLER)	EACH	. 1	1		
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	128	128		
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3101	3101	*	
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1162.5	1162.5	·	
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1076	1076		
	70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	F00T	1000	1000		
	70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	F00T	162.5	162.5		
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3101	3101		
×	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2		
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	11	11		
*	78100300	REPLACEMENT REFLECTOR	EACH	4	4		
X	78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4		
*	78200520	BARRIER WALL MARKERS, TYPE B	EACH	22	22		
×	78200530	BARRIER WALL MARKERS, TYPE C	EACH	22	22		
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	1034	1034		
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	9	9		
	X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	1110	1110		
	X0321468	PLUG EXISTING DECK DRAINS	EACH	40	40		
	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	356	356		
	X0325356	PREFORMED JOINT STRIP SEAL, 1"	-F00T-	346.5	-346.5-		
	X3560130	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH	SQ YD	127	127		
	X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	385	385		
	X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	4	4		
	X7200200	WIDE LOAD SIGNING	L SUM	1	1		,
	Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	310	310		
	Z0002600	BAR SPLICERS	EACH	88	88		
	Z0015595	DECK DRAIN EXTENSIONS	EACH	26	26		
	Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	70	70		
	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2	
	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2	
	Z0053750	RETROFIT CONCRETE PARAPET	FOOT	450	450	ž.	


E = 5/16/2006

Re



EXISTING TYPICAL SECTION

STA 100+75.0 TO STA 101+28.0 STA 110+10.48 TO STA 111+00.0



PROPOSED TYPICAL SECTION

STA 100+75.0 TO STA 101+28.0 STA 110+10.48 TO STA 111+00.0

** 3'-9" STA 100+75 TO STA 101+28 4'-0" STA 110+10.48 TO STA 111+00

LEGEND

- 1 EXISTING PCC PAVEMENT 9"-6"-9"
- (2) EXISTING RESURFACING 2"
- 3 EXISTING PCC BASE COURSE WIDENING 9"
- 4 EXISTING BITUMINOUS SHOULDER (TBR)
- (5) EXISTING AGGREGATE SHOULDER
- 6 EXISTING GUARDRAIL
- 7 PROPOSED BITUMINOUS SURFACE REMOVAL 1 1/2"
- 8 PROPOSED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE 1 1/2 "
- 9 PROPOSED BITUMINOUS BASE COURSE WIDENING, SUPERPAVE 9"
- 10 PROPOSED PAVED SHOULDER REMOVAL
- (1) PROPOSED BITUMINOUS MATERIALS PRIME COAT
- 12 PROPOSED AGGREGATE (PRIME COAT)

BITUMINOUS MIXTURE CHART

MIXTURE USE	SURFACE	BINDER / BSE CSE	INCIDENTAL SURFACE
AC/PG	PG 64-22	PG 64-22	PG 64-22
RAP % (MAX)	10%	15%	10%
DESIGN AIR VOIDS	4.0% @ Ndes=70	4.0% @ Ndes=70	4.0% @ Ndes=70
MIX COMPOSITION (GRADATION MIXTURE)			
FRICTION AGG	MIXTURE "D"	MIXTURE "B"	MIXTURE "C"

PLAN QUANTITIES FOR BITUMINOUS CONCRETE SURFACE COURSE ITEMS ARE CALCULATED USING A UNIT WEIGHT OF 112 LB/SQ YD/IN (59.8 KG/SQ M/25 MM THICKNESS).

REVISIONS		TI
NAME	DATE	IL.
		ł

ILLINOIS DEPARTMENT OF TRANSPORTATION

TYPICAL SECTION

FAS ROUTE 1780 SECTION 24-BR-2 CLINTON COUNTY SN 014-0062

* 4'-3" STA 100+75 TO STA 101+28

4'-0" STA 110+10.48 TO STA 111+00

EARTHWORK SCHEDULE (FOR INFORMATION ONLY)

	EARTH	EARTH	EARTHWORK
LOCATION	EXCAVATION	EXCAVATION	BALANCE
	(WIDENING)	ADJUSTED FOR	WASTE (+) OR
STATION TO STAT	IN	SHRINKAGE (25%)	SHORTAGE (-)
	CU YD	CU YD	CUYD
STA 100+75.00 TO STA 101	28.00 7.5	5.6	+5.6
STA 110+10.48 TO STA 111	0.00 12.5	9.4	+9.4
SUBTOTAL	20	15	+15

NOTE: EARTHWORK IS INCLUDED IN THE COST OF PAVED SHOULDER REMOVAL

GUARDRAIL SCHEDULE

	GUARDRAIL	TRAFFIC	GUARDRAIL
LOCATION	REMOVAL	BARRIER	MARKERS,
		TERMINAL,	TYPE A
		TYPE 6	
	F00T	EACH	EACH
NW QUADRANT	31.25	1	1
NE QUADRANT	31.25	. 1	1
SW QUADRANT	31.25	1	1
SE QUADRANT	31.25	1	1
TOTAL	125 *	4	4

• GUARDRAIL REMOVAL IS NOT A TOTAL QUANTITY. SEE STAGING SCHEDULE FOR ADDITIONAL QUANTITY.

NOTE: SEE STAGING SCHEDULE FOR TRAFFIC BARRIER TERMINAL, TYPE 11 QUANTITY.

RESURFACING SCHEDULE

	BITUMINOUS	AGGREGATE	BITUMINOUS CONCRETE	BITUMINOUS CONCRETE	BITUMINOUS	PAVED
LOCATION	MATERIALS	(PRIME COAT)	SURFACE COURSE,	BASE COURSE WIDENING	SURFACE	SHOULDER
	(PRIME COAT)		SUPERPAVE	SUPERPAVE 9 INCH	REMOVAL 1 1/2"	REMOVAL
STATION TO STATION	TON	TON	TON	SQ YD	SQ YD	SQ YD
STA 100+75.00 TO STA 101+47.50	0.08	0.4	14.9	47.3	195.7	17.9
BRIDGE OMISSION						
STA 109+91.23 TO STA 111+00.00	0.12	0.6	22.3	79.7	284.3	30.1
TOTAL	0.2	1	37 **	127	480	48

•• BITUMINOUS CONCRETE SURFACE COURSE IS NOT A TOTAL QUANTITY. SEE BRIDGE PLANS FOR ADDITIONAL QUANTITY.

TEMPORARY RAMP SCHEDULE

		WIDTH	LENGTH	TEMPORARY
LOCA	TION			RAMP
		FOOT	FOOT	SQ YD
STA	100+75	24	5	13.3
STA	101+47.50	24	5	13.2
STA	109+91.23	24	5	13.2
STA	111+00	24	5	13.3
TOTA	L			53

PAVEMENT MARKING SCHEDULE

	PAVEMENT MARKING REMOVAL		THERMOPLASTIC PAVEMENT MARKING T			TEMPORARY SHO	SHORT-TERM	M WORK ZONE RAISED REFLECTIVE F	REPLACEMENT	RAISED REFLECTIVE	RAISED REFLECTIVE	BARRIE	R WALL	BARRIE	ER WALL		
LOCATION	SKIP-DASH CENTERLINE	EDGE	LINE	SKIP-DASH CENTERLINE	EDGE	LINE	PAVEMENT	PAVEMENT	PAVEMENT	NT PAVEMENT MARKER	REFLECTOR PAVEMENT MARKE	PAVEMENT MARKER	PAVEMENT MARKER	MARK	KERS,	MARI	KERS,
	4" YELLOW	4" V	VHITE	4" YELLOW	4" W	VHITE	MARKING	MARKING	MARKING	REMOVAL			(BRIDGE)	TYP	E B	TYF	PE C
		LT	RT		LT	RT	LINE - 4"		REMOVAL		2-WAY AMBER	2-WAY AMBER	2-WAY AMBER	LT	RT	LT	RT
STATION TO STATION	SQ FT	SQ FT	SQ FT	FOOT	FOOT	FOOT	F00T	FOOT	SQ FT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
STA 99+07.30 TO STA 103+00.00	33.5	130.9	130.9	100	392.7	392.7	885	36	307	5	2	1	2	2	2	2	2
STA 103+00.00 TO STA 109+00.00	50.0	200.0	200.0	150	600.0	600.0	1350	56	468	1			8	8	8	8	8
STA 109+00.00 TO STA 112+82.90	33.5	127.6	127.6	100	382.8	382.8	866	36	301	3	2	1	1	1	1	1	1
SUB-TOTAL	117	458.5	458.5	350	1375.5	1375.5					-			11	11	11	11
TOTAL	1034	1	-Ar-Louis Limited - Committee	3101			3101	128	1076	9	4	2	11	2	2	2	22

STAGING SCHEDULE

	TRAFFIC CONTROL &	TRAFFIC CONTROL &	TRAFFIC CONTROL &	WIDE	CHANGEABLE	TEMPORARY	TEMPORARY	RELOCATE	TEMPORARY	TRAFFIC	GUARDRAIL	IMPACT	IMPACT
LOCATION	PROTECTION FOR	PROTECTION	PROTECTION	LOAD	MESSAGE	PAVEMENT	CONCRETE	TEMPORARY	BRIDGE	BARRIER	REMOVAL	ATTENUATOR,	ATTENUATOR,
	TEMPORARY	STANDARD 701321	STANDARD 701316	SIGNING	SIGN	MARKING	BARRIER	CONCRETE	RAIL	TERMINAL,		TEMPORARY	RELOCATE
	DETOUR	(SPECIAL)				LINE 6"		BARRIER		TYPE 11		(NON-REDIRECTIVE)	(NON-REDIRECTIVE)
	EACH	EACH	EACH	L SUM	CAL MO	FOOT	FOOT	FOOT	FOOT	EACH	FOOT	EACH	EACH
STAGE I	1				4								
STAGE II		1		1		1000	1000					2	
STAGE III			1			162.5		162.5	844	2	21		2
TOTAL	1	1	1	1	4 .	1162.5	1000	162.5	844	2	21 *	2	2

GUARDRAIL REMOVAL IS NOT A TOTAL QUANTITY.
 SEE GUARDRAIL SCHEDULE FOR ADDITIONAL QUANTITY.

REVISIONS					
NAME	DATE				
	—				

ILLINOIS DEPARTMENT OF TRANSPORTATION

 CONTRACT NO. 76899

 F.A.S. RTE.
 SECTION
 COUNTY SHEETS NO.

 1780
 24-BR-2
 CLINTON
 63
 5

TO STA.


FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT


STA.

SCHEDULE OF QUANTITIES


FAS ROUTE 1780 SECTION 24-BR-2 CLINTON COUNTY SN 014-0062


PLOT DATE = #DATE\$
FILE NAME = #FILEL\$
PLOT SCALE = #SCALE#
REFERENCE = #REF\$





MAG NAIL IN END GUARDRAIL POST (TOP) MAG NAIL IN END GUARDRAIL POST (FACE) ¢ OLD US 50 MAG NAIL IN END GUARDRAIL POST (TOP)






TIE POINT MAG NAIL P.C. STA 96+13.45

TIE POINT MAG NAIL P.T. STA 100+22.71

TIE POINT MAG NAIL STA 102+51.47

TIE POINT MAG NAIL P.O.L. STA 110+00



TIE POINT MAG NAIL P.O.L. STA 115+43.00

BENCHMARK

NGS BM K-152 - BRASS DISK SET IN THE TOP OF NORTH END OF EAST ABUTMENT OF STEEL RR BRIDGE OVER SHOAL CREEK NEAR MILEPOLE 297-19, APPROX 0.4 MILES SOUTH OF BRIDGE SN 014-0062 ON OLD US RTE 50 ELEV = 439.110

TEMPORARY BENCHMARKS

TBM-1 - RR SPIKE IN W. SIDE OF 1ST POWERPOLE IN ROW OF 7 ON EAST SIDE OF DRIVEWAY TO NEW WATER TREATMENT PLANT, APPROX. 200' SOUTH OF WEST END OF BRIDGE SN 014-0062 STA 101+86 OFFSET = 124' RT ELEV = 437.930

TBM-2 - CENTER OF BRASS DISK FOUND ON SW WINGWALL OF SN 014-0062 STA 101+45.2 OFFSET = 19.6' RT ELEV = 442,723


TBM-3 - SQUARE CUT IN TOP OF EAST END OF SE CONCRETE RAILWALL FOR BRIDGE SN 014-0062 STA 110+10.1 OFFSET = 16.2' RT ELEV = 444.140


ILLINOIS DEPARTMENT OF TRANSPORTATION	REVISIONS	
LEEDINGS DEFAITMENT OF TRANSPORTATION	DATE	NAME
TIE POINTS AND BENCHMARKS		
TIE I OTHIS AND DENCHMANK		
FAS ROUTE 1780	T	
SECTION 24-BR-2		
CLINTON COUNTY	ļ	


NOTE:


FIELD ENTRANCE


NOTE: ALL TIES PULLED DIRECT


















T DATE = 5/17/2006 NAME = ci\projects\ed03 F SCALE = 28.0000 / IN. ? NAME = owenbj










DATE = #DATE#
VAME = #FILEL#
SCALE = #SCALE#
ENCE = #SCALE#





DATE VAME SCALE NAME















MIE = #UMIE# NME = #FILEL# CALE = #SCALE# NCE = #REF#

PLOT DATE = \$DAT FILE NAME = \$FIL! PLOT SCALE = \$SCA

 CONTRACT NO. 76899

 F-A.S. RTE.
 SECTION
 COUNTY SHEET NO.
 SHEET NO.

 1780
 24-BR-2
 CLINTON
 63
 23
 STA. 103+00 TO STA. 109+00 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT



SEE STANDARD 635011 FOR BARRIER WALL MARKER DETAILS. "BARRIER WALL MARKERS, TYPE C"
SHALL BE PLACED ON THE TOP OF THE BARRIER WALL. "BARRIER WALL MARKERS, TYPE B" SHALL
BE PLACED ON THE SIDE OF THE BARRIER WALL.


20' 40' ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING

FAS ROUTE 1780 SECTION 24-BR-2 CLINTON COUNTY SN 014-0062

| F.A.S. | SECTION | COUNTY | TOTAL | SHEET | NO. | 1780 | 24-BR-2 | CLINTON | 63 | 24 | STA. | 109+00 | TO STA. | 115+00 | FED. ROAD DIST. NO. | ILLINOIS | FED. AID | PROJECT |





0 20' 40' 50ALE 1"= 20'

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING

FAS ROUTE 1780 SECTION 24-BR-2 CLINTON COUNTY SN 014-0062

SEE STANDARD 635011 FOR BARRIER WALL MARKER DETAILS. "BARRIER WALL MARKERS, TYPE C" SHALL BE PLACED ON THE TOP OF THE BARRIER WALL. "BARRIER WALL MARKERS, TYPE B" SHALL BE PLACED ON THE SIDE OF THE BARRIER WALL.

PLOT DATE = 05/15/2006 FILE NAME = http://25004/technical production/structural/sn 014-0062\final plans\0062-01-gplan. PLOT SCALE = 01.0000 **/ IN. USER NAME = \$USER\$

GENERAL NOTES

Plan dimensions and details relative to existing structure have been taken from existing plans and are subject to nominal construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

The cut strands at each beam end shall be given two coats of zinc dust spray or paint meeting the requirements of ASTM A780. The zinc dust spray or paint shall be applied before corrosion appears and allowed to dry according to the Manufacturers specifications prior to another coat of zinc. A concrete sealer meeting the requirements of Section 587 of the Standard Specifications shall be applied to the exterior face and 9" in on the underside of the fascia beams. The sealer shall be applied after visible crack growth has subsided. This work shall be performed by the producer and is included with the cost of the beam.

All construction joints shall be bonded.

(Stage II & III)

Repair of the substructure shall be completed prior to placement of the new deck beams.

The Contractor is advised that the existing PPC Deck Beams are in a deteriorated condition with reduced load carrying capacity. It is the Contractor's responsibility to account for the condition of the beams when developing construction procedures for removal and replacement of the superstructure. During Stage II traffic, the Field Engineer shall visually inspect the Precast Prestressed Concrete Deck Beam superstructure (top & bottom of the deck beams) on a daily basis. If any evidence of additional deterioration is found, the Department shall be notified immediately.

If the Contractor's procedure for existing beam removal or placement of new beams involves placement of cranes or other heavy equipment on new beams, a detailed procedure shall be submitted to the Engineer for approval. The procedure shall include calculations, prepared and sealed by an Illinois Licensed Structural Engineer, verifying that the equipment and procedure used will not overstress the new beams. To distribute load to multiple beams and protect the concrete, in all cases a double layer mat of heavy timbers shall be used at all times under crane tracks or wheels and any outriggers in the down position. If necessary, shims shall be used under the crane mat to ensure uniform contact with the underlying beams. Prior to placement of the timber mats, the following shall be done: placement and tightening of transverse tie assemblies, grouting and curing the dowel rods 24 hours minimum, and grouting and curing the shear keys. A temporary means of lateral restraint will be required for fascia beams at expansion ends of beams to prevent movement of the beams.

Any damage done to the bridge during beam removal shall be repaired by the Contractor. Cost to be included in the cost of Removal of Existing Superstructures.

The top surface of the beams shall be finished according to Article 504.06 of the Standard Specification except that the surface shall not be roughened by brooming. The finished surface shall be free of depressions or high spots with sharp corners, and the top edge of keys shall be rounded or chamfered a minimum of l_4 ".


Protective Coat shall not be applied to surfaces to which Waterproofing Membrane System is applied.

The thickness of the overlay shall be 2" minimum (I_2^{l} " bituminous + I_2^{l} " waterproofing membrane system) and varies as required to adjust for the profile grade, crown and beam

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

TOTAL BILL OF MATERIAL


ITEM	UNIT	SUPER	SUB	TOTAL
Protective Coat	Sq. Yd.	577		577
Bituminous Concrete Removal (Deck)	Sq. Yd.	693		693
Removal of Existing Superstructures	L. Sum	1		1
Concrete Removal	Cu. Yd.	9.3		9.3
Neoprene Expansion Joint 2"	Foot	33.0		33.0
Concrete Superstructure	Cu. Yd.	230.3		230.3
Structural Repair of Concrete (Depth Equal to or Less Than 5")	Sq. Ft.		356	356
Precast Prestressed Concrete Deck Beams (21" Depth)	Sq. Ft.	22,028		22,028
Furnishing and Erecting Structural Steel	Pound	1,650		1,650
Reinforcement Bars, Epoxy Coated	Pound	25,590		25,590
Removing and Re-Erecting Existing Railing	Foot	159		159
Name Plates	Each	1		1
Waterproofing Membrane System	Sq. Yd.	2,833		2,833
Portland Cement Mortar Fairing Course	Foot	6,343		6,343
Bridge Seat Sealer	Sq. Ft.		1,299	1,299
Removal of Existing Precast Prestressed Concrete Deck Beams	Sq. Ft.	1,110		1,110
Plug Existing Deck Drains	Each	40		40
Asbestos Bearing Pad Removal	Each	310		310
Bar Splicers	Each	88		88
Deck Drain Extensions	Each	26		26
Deck Slab Repair (Partial)	Sq. Yd.	70		70
Retrofit Concrete Parapet	Foot	450	***********	450
Preformed Joint Strip Seal.	Foot	378		378
		1.17	4. (1. 1. 4	25.7
Bituminous Concrete Surface Course Superpave, Mix "D" N7O	Ton	348		348



DRAIN EXTENSION DETAIL




Contract #76899




DRAIN ELIMINATION DETAIL

Eliminate alternate existing deck drains in Spans 1-3 and all deck drains within 10 feet of the substructure (40 required).



SECTION A-A



SECTION B-B

GENERAL NOTES, DETAILS & TOTAL BILL OF MATERIALS OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR-CLINTON COUNTY

STA. 102+51.47 STRUCTURE NO. 014-0062

PLOT FILE PLOT USER

Exterior edge of beam 3'' Radius (Cold bent) Top of Beam

FASCIA BEAM TRANSVERSE TIE DETAIL

Full length of beam except at U bars DECK BEAM REPLACEMENT DETAILS 112' OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR-³₄′′ Chamfer

of beam. Each End

CLINTON COUNTY STA. 102+51.47 STRUCTURE NO. 014-0062

SHEET NO.

29

SHEET NO.

39 **SHEETS**

© 1^l8"¢ hole & © Plate

134"

134"

PLATE A

(12 Required)

TOTAL SHEETS

TYPICAL SECTION REPLACEMENT BEAM b" \$ Strands, Each Strand Stressed to 30,900 Lbs.

10,5

cl.

(7 Required)

6-Strands 1^3 ₄" up, 8-Strands 3^1 ₄" up, 2-Strands 9" up


B B D B DATE NAME SCALE NAME

8 x 3-W2.5 x W5.5 Wire Fabric W2.5 longitudinal STAGE I

6''

LIFTING LOOP DETAIL

6"




.05/15/2006 h:\p\25004\technical p .0:10000 :'\ IN.

PLOT FILE PLOT USER

SHEET NO. TOTAL SHEET NO. 63 *39* **SHEETS** 30

Contract #76899



BEARING PAD LAYOUT

SUPERSTRUCTURE STAGE I BILL OF MATERIAL

Bar	No.	Size	Length	Shape
a(E)	42	#5	3'-0"	
d(E)	6	#4	3'-3"	
d1(E)	6	#5	3'-6"	(
d4(E)	174	#4	2'-10"	
e(E)	36	#4	17'-4"	
e1(E)	12	#8	28'-6"	
e2(E)	18	#5	27'-4"	
Precast Pi Conc. Deci		Sq. Ft.	1,095	
Reinforcement Bars, Epoxy Coated			Pound	2,340
Concrete Superstruc	ture	Cu. Yds.	20.4	
Removing & Re-erecting Existing Railing			Foot	159

(1) All structural steel (except Drain Tubes) shall be shop painted with the inorganic zinc rich primer per AASHTO M300 Type I. Cost included with F. & E. Structural Steel.

(2) Dowel holes shall be filled with non-shrink grout to top of bed and allowed to cure min. 24 hrs. prior to grouting the shear k See sheet 5 of 39 for bearing pad details.

Minimum bar laps: #5 - 2'-2"

#8 - 4'-6".

(5) Expansion guards that are not cast into the precast units shall be fabricated and erected according to Article 503.10(c) of the Standard Specifications and are included with Furnishing and Erecting Structural Steel.


(6) Bars d(E) & d1(E) shall be cast with the PPC Deck Beams. Cost included in the cost of Precast Prestressed Concrete Deck Beams (21" Depth).

(7) Bars d(E) & d1(E) placed in the field are included with Reinforcement Bars, Epoxy Coated.

> STAGE I DECK BEAM REPLACEMENT DETAILS OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR-2


CLINTON COUNTY STA. 102+51.47 STRUCTURE NO. 014-0062


(14 Required)




SHEET NO. TOTAL SHEETS SHEET NO. 8 ROUTE NO. 63 32 *39* **SHEETS**

Contract #76899









STAGE II REMOVAL

(Looking East)

STAGE III REMOVAL


(Looking East)







STAGE II CONSTRUCTION

(Looking East)







STAGE III CONSTRUCTION

(Looking East)


① For quantity of Temporary Bridge Rail and Temporary Concrete Barrier, see roadway plans. ② For details of Temporary Bridge Rail, see sheet 9 & 10 of 39. ③ For details of Temporary Concrete Barrier, see sheet 11 of 39.

See Special Provisions for Stage Construction Precast Prestressed Concrete Deck Beams. Cost of shear key clamps is included with Precast Prestressed Concrete Deck Beams (21" Depth

6 Space clamping plates to miss temporary bridge rail posts.


STAGE CONSTRUCTION DETAILS SPANS 4-15 OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR CLINTON COUNTY STA. 102+51.47

STRUCTURE NO. 014-0062




DUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET NO.	SHEET NO.	10
-	-			43	3A	39 ѕнеетѕ	
. ROAD DIST. NO. 7 ILLINDIS FED. AID PROJECT-							


Contract #76899



RAIL POST SPACING SPANS 1-3



RAIL POST SPACING SPANS 4-14



RAIL POST SPACING SPAN 15


Notoc.

① See sheet 9 of 39 for Temporary Bridge Rail details. ② Spans 4-15 shall have the threaded inserts precast into the PPC Deck Beams. TEMPORARY BRIDGE RAIL POST SPACING OLD U.S. ROUTE 50 OVER

SHOAL CREEK

F.A.S. ROUTE 1780 - SECTION 24-BRCLINTON COUNTY
STA. 102+51.47
STRUCTURE NO. 014-0062

Contract #76899




NEW SLAB

EXISTING SLAB


bars are in place and the concrete is ready to be


SECTIONS THRU SLAB



DETAIL I

The 1"x7"x10" Plate shall not be removed until Stage II Construction forms and reinforcement bars are in place.





NOTES

Detail II - With Extended Reinforcement Bars.

Connect one (1) 1"x7"x10" steel £ to the concrete slab with 2-5g" \$\phi\$ Expansion Anchors

Cost of anchorage is included with Temporary Concrete Barrier.

or cast in place inserts spaced between the

top layer of reinforcement at approximate & of

Detail I - With Bar Splicer or Couplers:

each barrier panel.

each barrier panel.

P 1"x7"x10"

* Required only with Detail II

TEMPORARY CONCRETE BARRIER
FOR STAGE CONSTRUCTION
OLD U.S. ROUTE 50 OVER
SHOAL CREEK

F.A.S. ROUTE 1780 - SECTION 24-BR


CLINTON COUNTY

STA. 102+51.47


STRUCTURE NO. 014-0062

ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET NO.	SHEET NO. 1
-	1	1		63	36	39 ѕнеетѕ
FED. ROAD DIST	NO. 7	ILLINOIS	FED, AID PROJECT-			

Contract #76899



CROSS SECTION SPANS 1-3 (Looking East)



CROSS SECTION SPANS 4-15

(Looking East)

SUPERSTRUCTURE


OLD U.S. ROUTE 50 OVER

SHOAL CREEK


F.A.S. ROUTE 1780 - SECTION 24-BR
CLINTON COUNTY

STA. 102+51.47

STRUCTURE NO. 014-0062




TYPICAL TRANSVERSE TIE ASSEMBLY



ROUTE ND.

(See section thru parapet for additional reinforcement at exterior beams.) ½" ♦ Strands, Each Strand Stressed to 30,900 Lbs. 6-Strands 1^{3}_{4} " up, 8-Strands 3^{l}_{4} " up, 2-Strands 9" up




Dimension


В

23'-512" 23'-512" 52'-7"

4-13 | 23'-2³8" | 23'-2¹4" | 52'-10⁵8 23'-7³8" 23'-7¹4" 52'-10⁵8

TABLE OF BEAM DIMENSIONS





END OF BEAM DETAIL

(Omit block-out at fixed end of beams (Pier 14) for spans 14 & 15.)

NOTES

(1) Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270.
(2) The nominal diameter shall be '2" and the nominal cross-sectional area shall be 0.153 sq. in.
(3) Lifting loops shall be 2 - \frac{1}{2}" \phi -270 ksi strands, as shown.
(4) The 1" \phi rods in the transverse tie assembly shall be transverse to a snug fit and the threads set. Pockets

that receive transverse tie bar on outside shall be filled with grout after transverse tie assembly is in place.

 \bigcirc The bearing seat surfaces shall be adjusted by shimming to assure firm and even bearing. Two $^{\prime}_{8}{}^{\prime\prime}$ fabric adjusting shims of the dimensions of the Exterior Bearing Pad shall be provided for each bearing.

(6) Keyway surfaces shall be cleaned to remove form oil or other bond breaking material prior to shipment of the beams. Cleaning shall be done by sandblasting the keyway areas between top of the beam and the bottom edge of the key.

(7) Corrosion Inhibitor, as covered in the Special Provisions, shall be used in the concrete for precast prestressed concrete deck beams.

- (8) Required Release Strength, f'ci, shall be 4,000 p.s.i.
 (9) Each beam shall have four lifting loops, two cast in each end as shown. Loops shall be burned off after beams have been erected.
- (f) Bridge rail inserts shall be cast in precast beams along Stage Construction Joint. See sheet 10 of 39 for location of rail anchors.
- (11) See Sheet 18 of 39 for details of parapet bars which are to be cast into the fascia beams

SUPERSTRUCTURE DETAILS OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR-


TOTAL SHEETS

COUNTY

SHEET NO.


SHEET NO.


CLINTON COUNTY STA. 102+51.47 STRUCTURE NO. 014-0062





TOTAL SHEETS SHEET NO. ROUTE NO. COUNTY SHEET NO. I38 63 *39* **SHEETS**

Contract #76899










SECTION THRU WEST ABUTMENT


SECTION THRU PIER 3 2

SECTION THRU PIERS 4-13 @

SECTION THRU PIER 14


* 1 gap to be filled with non-shrink grout. Dimensions may vary to accomodate tolerance in beam lengths.





BITUMINOUS OVERLAY PROFILE SPANS 4-15 & ANTICIPATED INITIAL CAMBER DIAGRAM 3

(See Sheet 13 of 39 for Table of Beam Dimensions for dimension C.)



- ① After beams have been erected, holes shall be drilled into substructure and anchor dowels placed at the fixed ends of the beams. Dowel holes shall be filled with non-shrink grout to top of beam and allowed to cure min. 24 hrs. prior to grouting the shear keys.
- Hatched area to be poured after beams are in place.
- 3 Thicknesses shown are for Beams 1 thru 5 and 7 thru 11. Thickness for Beam 6 will vary from those shown at beam edges to 4" additional at @ Roadway.

SUPERSTRUCTURE DETAILS OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR-2 CLINTON COUNTY STA. 102+51.47 STRUCTURE NO. 014-0062


PLOT FILE PLOT USER

PLOT FILE PLOT USER

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION



Contract #76899






TYP. PIER JOINT (PIER 3)

(Looking North)


EAST ABUTMENT



DETAIL A

(1782 Studs Required)

(60 Anchor Plates Required)



TYPICAL END TREATMENT AT PARAPET

GENERAL NOTES


- ① Only the strip seal joint system will be allowed. The strip seal shall be made continuous and shall have a minimum thickness of ${}^{l}_{4}$ ". The configuration of the strip seal shall match the configuration of the Locking Edge Rails.
- 2) The height and thickness of the Locking Edge Rails shown are minimum dimensions. The actual configuration of the Locking Edge Rails and matching strip seal may vary from manufacturer to manufacturer.
- 3 Locking Edge Rails may be spliced at slope discontinuities and stage construction joints.
- 4 The manufacturer's recommended installation methods shall be followed.
- (5) Granular or solid flux filled headed studs conforming to
- Article 1006.32 of the Std. Specs. automatically end welded (a) Joint openings shall be adjusted according to Article 503.10 of the Standard Specifications when the blockouts are pour at an ambient temperature other than 50° F.


SUPERSTRUCTURE DETAILS OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR CLINTON COUNTY


SHEET NO.

39 sheets

Contract #76899








PLAN
(Parapet not shown for clarity.)

RETAINER ANGLE AT EXPANSION JOINT



PLAN

RETAINER ANGLE AT EXPANSION JOINT
ALONG STAGE II CONSTRUCTION JOINT

Approved threaded rod shall be placed in drilled holes and grouted in place. Cost of retainer and accessories are included with Precast

Prestressed Concrete Deck Beams (21" Depth).

(2) Retainer angles are to be used at the expansion ends of deck beams on After block-outs are poured and cured the retainer angles shall be removed. Anchor bolts may be left in place at Beams 1 and 11.

(3) Cost of ½ % Standard pipe shall be included in the cost of the Precast Prestressed Concrete Deck Beams (21" Depth).

SUPERSTRUCTURE DETAILS

OLD U.S. ROUTE 50 OVER

SHOAL CREEK

F.A.S. ROUTE 1780 - SECTION 24-BR
CLINTON COUNTY

STA. 102+51.47

56"Ø BACKER ROD

TOTAL SHEETS SHEET SHEET NO. ROUTE NO. *39* **SHEETS** 41

Contract #76899

GENERAL NOTES

EXISTING

- 1 CLASS SI CONCRETE SHALL BE USED THROUGHOUT FOR CAST-IN-PLACE OPTION.
- 2 CLASS PC CONCRETE SHALL BE USED THROUGHOUT FOR PRECAST OPTION.
- 3 ALL EXPOSED EDGES SHALL BE CHAMFERED 34".
- 4 CLASS SI OR PC CONCRETE; REINFORCEMENT BARS, EPOXY COATED; THREADED ANCHOR RODS; ½" PJF AND ALL OTHER ACCESSORIES NEEDED FOR INSTALLATION AND ERECTION SHALL BE INCLUDED IN THE COST OF "RETROFIT CONCRETE PARAPET".
- 5 THE CONTRACTOR SHALL USE THE CAPSULE OR THE ADHESIVE CARTRIDGE TYPE ANCHOR RODS THAT HAVE BEEN PREVIOUSLY TESTED AND GIVEN A PRIOR APPROVAL BY THE DEPARTMENT. THE CONTRACTOR SHALL INSTALL THESE ANCHOR RODS IN PRE-DRILLED HOLES ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS AND PROCEDURES.
- 6 THE CAPSULE OR THE ADHESIVE CARTRIDGE SHALL BE SEALED GLASS CAPSULE OR A SEALED GLASS ADHESIVE CARTRIDGE CONTAINING PREMEASURED AMOUNT OF ADHESIVE CHEMICAL. THE THREADED ROD STUD WITH NUT & WASHERS SHALL CONFORM TO ASTM A307.
- 7 HOLES FOR THE DOWEL RODS SHALL MISS EXISTING PARAPET JOINTS.
- 8 THE PRECAST SECTIONS MAY BE CAST IN UNITS OF 3', 5', 7',..... ETC. LENGTH AS DESIRED. WHERE THEY OVERLAP THE JOINTS IN THE PARAPET, THE PRECAST UNITS SHALL BE SAW CUT TO LINE UP WITH THE JOINTS IN THE PARAPET. THE SAWOUT FACES OF THE UNITS SHALL BE GIVEN A COAT OF BOILED LINSEED OIL MIXTURE (PROTECTIVE COAT). THE COST OF THE PROTECTIVE COAT SHALL BE INCLUDED IN THE COST FOR "RETROFIT CONCRETE PARAPET".
- 9 THE CONCRETE PARAPET RETROFIT WILL BE MEASURED FOR PAYMENT IN FOOT (FT) ALONG THE TOP OF PARAPET END TO END. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT (FT) OF "RETROFIT CONCRETE PARAPET".
- 10 EPOXY GROUT d(E) BARS IN 1/8" Ø X 6" (MIN.) DRILLED HOLES. THE GROUT AND THE METHOD APPLICATION SHALL BE APPROVED BY THE DEPARTMENT. (SEE SECTION 584 OF THE STANDARD SPECIFICATIONS.) COST INCLUDED WITH RETROFIT CONCRETE PARAPET.
- 11 RETORFIT CONCRETE PARAPET SHALL BE USED ON THE EXISTING PARAPETS IN SPANS 1-3 AND AT THE EXISTING PARAPETS AT THE EAST APPROACH SLAB.


BILL OF MATERIAL


PAY ITEM	UNIT	QUANTITY
RETROFIT CONCRETE		
PARAPET	FOOT	450

SUPERSTRUCTURE DETAILS OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR-CLINTON COUNTY STA. 102+51.47 STRUCTURE NO. 014-0062

leal

₹4′′ 11/2" CL. (TYP.) CAST-IN-PLACE ALTERNATE





(SHOWING SPACING OF 3/4" H.S. THREADED RODS)

61/4"

BAR S(E)

JOINT DETAIL

POLYURETHANE SEALANT MEETING THE REQUIREMENTS OF ASTM C-920, TYPE S, GRADE NS, CLASS 25,

EXPANDING CORK JOINT FILLER

INCLUDED WITH RETROFIT CONCRETE PARAPET.

ACCORDING TO ARTICLE 1051.07 OF THE STD, SPEC, COST

1/2" PREFORMED SELF-

USE T.

1/4" (TYP)

1 %" (TYP)

Superstructure.

DRAIN DETAIL

SUPERSTRUCTURE BILL OF MATERIAL

TOTAL SHEETS

SHEET NO.

42

39 SHEETS

Bar	No.	Size	Length	Shape	
a1(E)	66	#5	14'-9"		
a2(E)	66	#5	17'-9"		
d2(E)	44	#4	4'-0"	ر	
d3(E)	44	#5	4'-1"	ر	
d4(E)	1,392	#4	3′-5"		
e(E)	396	#4	17'-3"		
e1(E)	88	#8	28'-6"		
e2(E)	132	132 #5 36 #4	36 #4 1	27'-4"	
e3(E)	36			17'-2"	
e4(E)	8	#8	28'-4"		
e5(E)	12	#5	27'-2"		
Precast P. Deck Bean			Sq. Ft.	20,933	
Reinforcen Epoxy Cod			Pound	22,100	
Concrete Superstruc			Cu. Yds.	200.6	

4) Bars d2(E) & d3(E) cast with the PPC Deck Beams are included in the cost of Precast Prestressed Concrete Deck Beams (21" Depth).

SUPERSTRUCTURE DETAILS OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR-**CLINTON COUNTY** STA. 102+51.47 STRUCTURE NO. 014-0062

PLOT FILE PLOT USER

Const. Jt.

(Mandatory)

PARAPET JOINT DETAILS

INSTALLATION NOTES

- Install continuous seal in roadway, parapet, curb, and sidewalk.
- Install anchor blocks as indicated.

Maximum spacing of anchor bolts shall be 12" centers.

SKEW LIMITATIONS

The details of the anchor blocks and the elastomeric membrane in the parapet, as shown, are for up to 50° skews. For skews greater than 50°, the anchor blocks and the elastomeric membrane, installed according to dimension "D", might require modifications to insure a minimum clearance of 112" from centerline of anchor studs to edge of parapet opening. The anchor blocks and the elastomeric membrane shall also be installed to the top of the parapet with the

> Anchor Bolts _ in place

> > 10-22-04

Threaded anchor


studs with washers

CURB

anchor studs spaced at ±12" cts.

Threaded Anchor Studs\with Washers

EJ-CS



FORMING BLOCKOUT **SKETCH**

For skews greater than 50°

Std. anchor


Cast in place

AT PARAPET

Rdwv.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION Steel reinforced elastomeric anchor blocks 7,7-14'' Min. steel plate

CROSS SECTION



ANCHOR BLOCK WITH ASPHALT SURFACE

Threaded Anchor

Std. Anchor Bolts

Cast in place

AT WALL

For skews greater than 50°

TOTAL BHEETS SHEET ND. 63 39 sheets

Contract #76899

GENERAL NOTES

Continuous Seal Neoprene Expansion Joint shall consist of molded anchor blocks of elastomer and steel, field assembled over continuous lengths of elastomeric membrane.


The elastomeric membrane shall be premolded with a single or a double upward convolution that will have a "memory" to return to its molded position upon joint closure.

The convolution length shall be such that the extended length will

not be greater than the manufactured length when the joint is fully expanded in its design range and will not protrude above the anchor blocks when the joint is fully compressed. Joint openings shall be adjusted according to Article 503.10(c)

of the Standard Specifications when the deck is poured at an ambient temperature other than 50° F.

The parapet and roadway membrane shall be made continuous by an approved vulcanizing process. Lapping will not be permitted.



clamping nut. Anchor studs should be stainless RECOMMENDED BLOCKOUT DETAIL

– Countersunk hole for top nut —

Temporary Wood Blockout

> Formed Joint Opening

Bottom

Stud needs to b

threaded lower to allow for use of

Clamping Nur

ws greater than 50° Studs with Washers Median Surface Studs with Washers Std. Anchor Bolts Cast in place AT SIDEWALK OR MEDIAN TYPICAL END TREATMENT'S

CONTINUOUS SEAL TYPE NEOPRENE EXPANSION JOINTS OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR-CLINTON COUNTY

TOTAL SHEETS SHEET NO.

PLOT DATE = 05/15/2006 FILE NAME = http:/S5004/technical production/structural/sn 014-0062\final plans\0062-20-neopexpjtssht2 PLOT SCALE = 0:18000 :/ IN. USER NAME = sHISER**

Bar d(E)

Bar d1(E)

Bar x(E)

TOTAL SHEETS

63

Size

#5

STRUCTURE NO. 014-0062

Length Shape

390

2.7

18'-0"

3'-7"

Pound

Cu. Yd.

Cu. Yd.

COUNTY

SHEET NO.

45


39 SHEETS

PLOT FILE I PLOT USER

EXISTING PARTIAL PLAN EAST ABUTMENT

| ROUTE NO. | SECTION | COLATY | SHEET | SHEET NO. 2

Contract #76899



RILL OF MATERIAL

	DILL	JI INTA I	ENIAL	
Bar	No.	Size	Length	Shape
a5(E)	3	#6	15'-2"	
a6(E)	3	#6	18'-2"	
d(E)	2	#4	3'-9"	L
d1(E)	2	#5	3'-7"	L
d7(E)	35	#5	1'-7"	
Reinforce Epoxy Cod	ment Bars, nted	Pound	220	
Concrete Superstru	cture	Cu. Yd.	1.9	
Concrete	Removal		Cu. Yd.	1.9

<u>F.A</u>

Bar d(E)

2'-0"

Bar d1(E)

EAST ABUTMENT EXPANSION JOINT

OLD U.S. ROUTE 50 OVER

SHOAL CREEK

F.A.S. ROUTE 1780 - SECTION 24-BR-2

CLINTON COUNTY


STA. 102+51.47

STRUCTURE NO. 014-0062


-LOI DATE = 05/15/2006 FILE THOME = Ny/SS004/tochnical production\structural\sn 014-0062\final plans\0062-22-aastabutexpjtsht.dgn On Terk = nainana varin

| NOUTE NO. | SECTION | COUNTY | SHEETS | SHEET NO. 2

Contract #76899



PLAN



SECTION A-A

(Looking East)
(Bituminous Surface Course and shim Bearing Pads not shown)

Notes:


① Elevations are taken from existing plans.
Contractor shall verify prior to ordering materials.

PIER 3 LAYOUT
OLD U.S. ROUTE 50 OVER
SHOAL CREEK
F.A.S. ROUTE 1780 - SECTION 24-BR-A
CLINTON COUNTY
STA. 102+51.47
STRUCTURE NO. 014-0062

PLOT DATE = 05/15/2006 FILE NAME = http:/25004technical production\structural\sn 014-0062\final plans\0062-23-pier3layou PLOT SCALE = 01.00000 ':' / IN. USER NAME = \$USER\$

Contract #76899

 $Z \longrightarrow \emptyset \longrightarrow \blacksquare$






TABLE OF ELEVATIONS ①

Pier No.	Elevation A
4	±441.08
5	±441.08
6	±441.06
7	±441.00
8	±440.92
9	±440.81
10	±440.70
11	±440.59
12	±440.48
13	±440.37

SECTION A-A

(Looking East)
(Bituminous Surface Course and shim Bearing Pads not shown)

Notes

(1) Elevations are taken from existing plans. Contractor shall verify prior to ordering materials. PIERS 4-13 LAYOUT


OLD U.S. ROUTE 50 OVER


SHOAL CREEK

F.A.S. ROUTE 1780 - SECTION 24-BRCLINTON COUNTY

Contract #76899








SECTION A-A

(Looking East)
(Bituminous Surface Course and shim Bearing Pads not shown)


Note


 Elevations are taken from existing plans. Contractor shall verify prior to ordering materials. PIER 14 LAYOUT
OLD U.S. ROUTE 50 OVER
SHOAL CREEK
F.A.S. ROUTE 1780 - SECTION 24-BRCLINTON COUNTY





Contract #76899





SECTION A-A

(Looking East)
(Bituminous Surface Course and shim Bearing Pads not shown)

Notes:


(1) Elevations are taken from existing plans.

Contractor shall verify prior to ordering materials.

EAST ABUTMENT LAYOUT
OLD U.S. ROUTE 50 OVER
SHOAL CREEK
F.A.S. ROUTE 1780 - SECTION 24-BR-A

ROUTE NO.	SECTION	cou	COUNTY		SHEET NO.	SHEET NO.	
-	-	-		63	51	39 SHEET	S
FED. RDAG DIST. NO. 7 ILLINOIS		ILLINOIS	FED. ALD PR	DJECT-			

Contract #76899



WEST SIDE PIER 4

(Looking East)

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

EAST SIDE PIER 4 (Looking West)

BILL OF MATERIAL


Structural R	Repair	of	_		
Concrete (<	: Ś")		Sq.	<i>F1.</i>	11


PIER 4 CONCRETE REPAIRS OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR-2 CLINTON COUNTY STA. 102+51.47 STRUCTURE NO. 014-0062

PLOT DATE = 85/15/2006 FILE NAME = h:p\25004\technical production\struc PLOT SCALE = 81.0000 '' / IN. USER NAME = \$USER\$

ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET NO.	SHEET	NO.
-	~	-		63	52	<i>3</i> 9 she	EETS
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID		FED. AID PR	DJECT-				

Contract #76899





WEST SIDE PIER 5

(Looking East)

EAST SIDE PIER 5

(Looking West)

Noto

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

BILL OF MATERIAL

Structural Repair of Concrete (≤ 5") Sq. Ft. 8

PLOT DATE = 05/15/2006 FILE NAME = htp/25004technical production\structural\sn 014-0062\final plans\0062-28-pier5sht.dgn PLOT SCALE = 01.0000 ':' / IN. USER NAME = \$USER\$

PIER 5 CONCRETE REPAIRS

OLD U.S. ROUTE 50 OVER

SHOAL CREEK


F.A.S. ROUTE 1780 - SECTION 24-BR-2

CLINTON COUNTY

STA. 102+51.47

ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	BHEET NO.	SHEET NO. 2
-	-	-		63	53	39 ѕнеетѕ
FED. ROAD DIST. ND. 7 ILLINOIS FED.		FED. AND PRO	OJECT-			

Contract #76899



...

WEST SIDE PIER 6
(Looking East)

Note:
Hatched area indicates approximate area of Structural
Repair of Concrete. Exact repair area to be determined
by Engineer.

EAST SIDE PIER 6

(Looking West)

BILL OF MATERIAL

Structural Repair of	Ca Et	77
Concrete (≤5")	34. FI.	22

PLOT DATE = 05/15/2006 FILE NAWE = http./25004\technical production\s PLOT SCALE = 01:0000 1'/ IN. USER NAME = \$USER\$

PIER 6 CONCRETE REPAIRS

OLD U.S. ROUTE 50 OVER

SHOAL CREEK

F.A.S. ROUTE 1780 - SECTION 24-BR-2


CLINTON COUNTY


STA. 102+51.47

STRUCTURE NO. 014-0062

SHEET NO. TOTAL SHEETS 63 5A *39* **SHEETS**

Contract #76899





WEST SIDE PIER 7

(Looking East)

EAST SIDE PIER 7

(Looking West)

Note:
Hatched area indicates approximate area of Structural
Frant renair area to be determin Repair of Concrete. Exact repair area to be determined by Engineer.

BILL OF MATERIAL


Structural Repair of Concrete (≤ 5") Sq. Ft.


PLOI DATE = 05/15/2006 FILE NAME = h:p\25004\technical production\structural\sn 014-0052\final plans\0062-30-pier7sht.dgn PLOI SCALE = 01.0000 : / IN. USER NAME = \$USER\$

PIER 7 CONCRETE REPAIRS OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR-CLINTON COUNTY STA. 102+51.47

ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET	SHEET NO.
-	-	**		63	55	39 ѕнеетѕ
FED. ROAD DIST. NO. 7 ILLINDIS FED. AID PRI		JECT-				

Contract #76899





WEST SIDE PIER 8

(Looking East)

EAST SIDE PIER 8

(Looking West)

Nota

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

BILL OF MATERIAL

Structural Repair of Sq. Ft. 14

PIER 8 CONCRETE REPAIRS

OLD U.S. ROUTE 50 OVER

SHOAL CREEK


F.A.S. ROUTE 1780 - SECTION 24-BR
CLINTON COUNTY


STA. 102+51.47

STRUCTURE NO. 014-0062

ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET ND,	SHEET	NO.	,
-	-	-		63	56	39 s H	EETS	
FEO. NOAD DIST. NO. 7		ILLINOIS	FED. AID PRO	DJECT-				

Contract #76899





<u>WEST SIDE PIER 9</u>

(Looking East)

EAST SIDE PIER 9

(Looking West)

Noto.

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

BILL OF MATERIAL

Structural Repair of Sq. Ft. 25

PLOT DATE = 05/15/2006 FILE NAME = http:/25004technical production\structural\sn 014-0062\final plans\0062-32-pier9sht.dgn PLOT SCALE = 01.0000 '; / IN. USER NAME = \$USER\$

PIER 9 CONCRETE REPAIRS

OLD U.S. ROUTE 50 OVER


SHOAL CREEK

F.A.S. ROUTE 1780 - SECTION 24-BRCLINTON COUNTY

STA. 102+51.47


ROUTE NO.	BECTION	COUNTY		TOTAL SHEETS	SHEET	SHEET NO.	3
-	-	-		63	51	39 SHEETS	
ED. ROAD DIST. NO. 7 BALINOIS F		FED. AND PROJECT-					

Contract #76899



WEST SIDE PIER 10

(Looking East)



EAST SIDE PIER 10

(Looking West)

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

BILL OF MATERIAL


Structural Repair of	Ca E+	50
Concrete (≤5")	54. F1.	59


PLOT DATE = 05/15/2006 FILE NAME = h:p/25004/technical product PLOT SCALE = 01.0000 '' / IN. USER NAME = \$USER\$

PIER 10 CONCRETE REPAIRS OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR-CLINTON COUNTY

ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET NO.	SHEET NO.	3
-	-	-		63	58	39 ѕнеетѕ	•
FED. ROAD DIST	. NO. 7	ILLINOIS	FEO. AID PROJECT-				

Contract #76899





WEST SIDE PIER 11

(Looking East)

EAST SIDE PIER 11

(Looking West)

Note.

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

BILL OF MATERIAL

Structural Repair of | Sq. Ft. 21

PLOT DATE = 05/15/2006 FILE NAME = h:px/55004/technical production/structural/sn 014-0062\f PLOT SCALE = 01.0000 ''./ IN, INSED NAME = 4 HISTER

PIER 11 CONCRETE REPAIRS

OLD U.S. ROUTE 50 OVER

SHOAL CREEK


F.A.S. ROUTE 1780 - SECTION 24-BR-2


CLINTON COUNTY

STA. 102+51.47

ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET NO.	SHE
-	-	-		63	59	39
FEO. ROAD DIST	. NO. 7	ILL.INOTS	FEO. AID PRO	NECT-		

Contract #76899





WEST SIDE PIER 12

(Looking East)

EAST SIDE PIER 12

(Looking West)

Noto.

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

BILL OF MATERIAL

Structural Repair of	C# 54	71
Concrete (≤ 5")	34. F1.	31

OLD U.S. ROUTE 50 OVER

SHOAL CREEK


F.A.S. ROUTE 1780 - SECTION 24-BR-2


CLINTON COUNTY

PIER 12 CONCRETE REPAIRS

ROUTE NO.	SECTION	co.	INTY	TOTAL SHEETS	SHEET NO.	SHEET NO.
*	-	-		63	60	39 ѕнеетѕ
FED. ROAD DIST	NO. 7	ILLINDIB	FED. AID PRO	JECT-		

Contract #76899





WEST SIDE PIER 13

(Looking East)

EAST SIDE PIER 13

(Looking West)

Note:

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

BILL OF MATERIAL

Structural Repair of	Ca [*	17
Concrete (< 5")	5q. r1.	43

PLOT UATE = MS/15/2006 FILE NAME = h:\p\25004\technical production\structur PLOT SCALE = 0:1,0000 ** / IN. USER NAME = \$USER\$

PIER 13 CONCRETE REPAIRS

OLD U.S. ROUTE 50 OVER

SHOAL CREEK

F.A.S. ROUTE 1780 - SECTION 24-BR-2


CLINTON COUNTY


STA. 102+51.47

STRUCTURE NO. 014-0062

-	ROUTE NO.	SECTION	cou	INTY	TOTAL SHEETS	SHEET NO.	SHEET NO.	3
	-	-	-		63	(e1	<i>39</i> SHEETS	
	FED. ROAD DIST	. NO. 7	ILLINOIS	PED. AID PROJECT-				

Contract #76899





EAST SIDE PIER 14

(Looking West)

WEST SIDE PIER 14
(Looking East)

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

BILL OF MATERIAL

Structural Repair of Concrete (≤ 5") Sq. Ft. 11

PLOT DATE = 06/15/2006
FILE NAME = h:V25004\technical production\stru PLOT SCALE = 01.0000 '!' / IN.
USER NAME = 81SER\$

PIER 14 CONCRETE REPAIRS

OLD U.S. ROUTE 50 OVER

SHOAL CREEK


F.A.S. ROUTE 1780 - SECTION 24-BR-2


CLINTON COUNTY

STA. 102+51.47

ROUTE NO.	SECTION	coi	JNTY	TOTAL SHEETS	SHEET	SHEET NO	o. 3
-	-	-		63	62	39 SHEE	TS
FED. ROAD DIST	. NO. 7	ILLINOIS	FED. AID PRO	DJECY-			

Contract #76899





EAST SIDE PIER 3
(Looking West)

EAST ABUTMENT
(Looking East)

Note.

Hatched area indicates approximate area of Structural Repair of Concrete. Exact repair area to be determined by Engineer.

BILL OF MATERIAL

Structural Repair of Concrete (≤5") Sq. Ft. 39

EAST ABUTMENT & PIER 3

CONCRETE REPAIRS

OLD U.S. ROUTE 50 OVER

SHOAL CREEK

F.A.S. ROUTE 1780 - SECTION 24-BR-A

CLINTON COUNTY

STA. 102+51.47

STRUCTURE NO. 014-0062

PLOT DATE = 06/15/2006 FILE NAME = http://25004/technical production\structural\sn @14-0062\final plans\@062-38-pier3 & E Abu PLOT SCALE = 06.10000 ** / IN. USER NAME = \$USER\$

Contract #76899

NOTES

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars.

Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length. All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars.

Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars.

Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:

Minimum Capacity (Tension in kips) = $1.25 \times fy \times A_t$


Minimum *Pull-out Strength = 1.25 x fs_{allow} x A_f

Where fy = Yield strength of lapped reinforcement bars in ksi.

 $fs_{\it allow}$ = Allowable tensile stress in lapped reinforcement bars in ksi (Service Load) A_t = Tensile stress area of lapped reinforcement bars. * = 28 day concrete

	545.654.76		
	BAR SPLIC	ER ASSEMBLI	
D C 4.	6-6	Strengt	h Requirements
Bar Size to be Spliced	Splicer Rod or Dowel Bar Length	Min. Capacity kips - tension	Min. Pull-Out Strength kips - tension
#4	1'-8''	14.7	5.9
#5	2'-0"	23.0	9.2
#6	2'-7"	33.1	13.3
#7	3′-5″	45.1	18.0
#8	4'-6''	<i>58.9</i>	<i>23</i> .6
#9	5′-9′′	75.0	30.0
#10	7′-3′′	95.0	38.0
#11	9′-0′′	117.4	46.8

Bar splicer assemblies shall be according to Section 508 of the Standard Specifications, except as noted. The furnishing and installation of bar splicer assemblies will be measured and paid for at the contract unit price each for "BAR SPLICERS."





STANDARD


Bar Size	No. Assemblies Required	Location
#5	8	W. Abut. Exp. Jt.
#6	3	W. Abut. Exp. Jt.
#5	8	Pier 3 Exp. Jt.
#6	3	E. Abut. Exp. Jt.
#5	66	Exp. Jt. Blockouts Beams @ Piers 3-13 & E. Abut.

BAR SPLICER ASSEMBLY DETAILS OLD U.S. ROUTE 50 OVER SHOAL CREEK F.A.S. ROUTE 1780 - SECTION 24-BR-

CLINTON COUNTY STA. 102+51.47 STRUCTURE NO. 014-0062









BAR SPLICER ASSEMBLY ALTERNATIVES

** Heavy Hex Nuts conforming to ASTM A 563, Grade C, D or DH may be used.



INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt. "B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms. (E): Indicates epoxy coating.



FOR INTEGRAL OR SEMI-INTEGRAL ABUTMENTS

	Bar	Splicer	foi	r #£	5 bar		
Min.	Capacity	= 23.0	kip	s -	tensi	on	
Min.	Pull-out	Strength	=	9.2	kips	-	tension
No.	Required	-					

