F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3753	04-00037-00-WR	WILL	92	8
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

83858

SIDEWALK

LOCATION (STATION)		OFFSET	42400200 PORTLAND CEMENT CONCRETE SIDEWALK 5"	42400300 PORTLAND CEMENT CONCRETE SIDEWALK 6"	42400800 DETECTABLE WARNINGS
FROM	TO		SQ FT	SQ FT	SQ FT
05+22	05+26	LT	29		7
05+37	06+62	RT	686		38
06+39	07+21	LT	371		10
06+62	06+81	RT		92	
06+81	08+84	RT	1063		30
07+21	07+45	LT		116	
07+45	08+60	LT	609		36
09+00	09+24	LT	99		10
09+33	16+29	RT	3567		40
12+77	12+86	LT	56		10
13+32	13+60	LT	29		10
13+60	13+45	LT	48		10
16+29	16+44	RT		72	
16+44	20+17	RT	2008		40
16+59	16+65	LT	31		23
17+12	17+20	LT	32		10
17+21	17+26	LT	64		10
18+70	18+81				
20+17	20+38	RT		105	
20+24	20+35	LT	73		35
20+38	21+76	RT	760		30
20+74	20+86	LT	97		18
21+76	21+94	RT		89	
21+94	23+31	RT	687		20
23+31	23+53	RT		108	
23+53	23+69	RT	78		20
23+69	23+86	RT		85	
23+86	24+47	RT	384		30
24+19	24+26	LT	30		22
24+47	24+60	RT		63	
24+60	24+92	RT	229		30
24+62	24+69	LT	20		8
24+72	24+77	LT	56		10
24+92	25+06	RT		70	
25+06	26+37	RT	664		20
26+37	26+56	RT		93	
26+56	26+91	RT	168		20
26+91	27+07	RT		81	
27+07	27+74	RT	336		20
27+69	27+73	LT	19		8
27+74	27+87	RT		63	
27+76	27+81	LT	22		8
27+87	28+40	RT	264		20
28+17	28+22	LT	19		8
28+29	28+33	LT	27		8
28+40	28+55	RT		80	
28+55	28+60	RT	25		10
TOTAL			13881	1229	650

CURB AND GUTTER

LOCATION (CENTERLINE STATION)		OFFSET	60603800 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	44000500 COMBINATION CONCRETE CURB AND GUTTER REMOVAL
FROM	TO		FOOT	FOOT
05+04	08+61	LT	391.0	
05+04	05+35	LT		40.5
05+35	08+88	RT	397.5	
05+35	05+42	RT		49.5
08+48	08+61	LT		44
08+56	08+86	RT		39
08+95	09+31	LT		51
09+27	09+58	RT		46
08+90	12+86	LT	456.0	
09+27	29+13	RT	2015.0	
13+23	16+66	LT	400.0	
16+65	16+70	LT		18.5
17+02	20+38	LT	387.5	
20+21	20+37	LT		43.5
20+66	24+29	LT	406.0	
20+74	20+95	LT		28.5
24+05	24+28	LT		39.0
24+58	27+85	LT	361.5	
24+59	24+86	LT		42.0
27+60	27+83	LT		38.0
28+13	29+24	LT	133.5	
28+14	28+40	LT		39.0
TOTAL			5422	565

PAVEMENT REMOVAL

LOCATION (STATION)		OFFSET	44000100 PAVEMENT REMOVAL
			SQ YD
49+57	50+23	RT	27
50+37	51+02	LT	24
50+38	50+74	RT	13
51+10	51+34	LT	8
Sewer Crossings			
6+38			11
7+67			11
10+42			11
11+68			11
13+56			21
14+90			11
15+91			11
17+50			11
20+00			11
22+32			11
24+11			11
25+80			11
27+42			11
29+13			24
TOTAL			252

SIGNS

LOCATION (CENTERLINE)	LATERAL OFFSET	72000100 SIGN PANEL - TYPE 1	73000100 WOOD SIGN SUPPORT	SIGN CLASS
	FT	SQ FT	FT	
SAUK				
04+69	18 RT	6	9	R1-1
04+69	18 RT	3	--	W4-4p
05+31	23.5 LT	6	9	R1-1
05+31	23.5 LT	3	--	W4-4p
19+49	22.5 RT	6	8	W14-3
21+05	22.5 RT	8	8	R3-5b
27+50	22.5 LT	8	8	R3-5b
28+70	17.5 LT	5	8	R2-1
28+70	17.5 LT	5	8	R2-1
28+70	17.5 LT	6	8	W14-3
46+52	16 RT	9	8	W10-1
46+52	16 LT	7	8	W14-3
46+52	16 LT	6	8	W3-5a
54+75	16 LT	7	8	W10-1
LINDEN				
10+40	24.5 LT	6	8	R1-1
10+50	20.5 LT	6	8	R1-1
EVERGREEN				
10+50	24.5 LT	6	8	R1-1
SYCAMORE				
10+52	26.5 LT	6	8	R1-1
LUTHER				
10+52	22.5 LT	6	8	R1-1
CHESTNUT				
10+45	21 LT	6	8	R1-1
PFEIFFER				
10+33	29 LT	13	8	R1-1
10+33	28 LT	13	8	R1-1
TOTAL		149	153	

BITUMINOUS SURFACE REMOVAL - BUTT JOINT

LOCATION (STATION AT CENTERLINE OF SAUK TRAIL AND SIDE STREET)	OFFSET	40600980 BITUMINOUS SURFACE REMOVAL - BUTT JOINT
		SQ YD
05+16		193
08+90	LT	42
09+05	RT	47
13+20	LT	44
17+02	LT	46
20+67	LT	36
24+47	LT	37
28+02	LT	36
35+79	RT	16
37+16	RT	20
49+97		75
51+49		73
52+40	RT	50
57+78	RT	30
60+17	LT	66
60+17	RT	66
65+82		76
TOTAL		988

PAVEMENT STRUCTURE

LOCATION/STATION		X3550500 BITUMINOUS BASE COURSE SUPERPAVE 8"	X4066614 BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19, N50	X4066414 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	31101400 SUB-BASE GRANULAR MATERIAL, TYPE B, 6"	40300100 BITUMINOUS MATERIALS (PRIME COAT)	X4066765 LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50
FROM	TO	SQ YD	TON	TON	SQ YD	GALLON	TON
05+71	28+72	3349	422	715	3324	2210	160
28+72	31+65	231	29	76	211	153	
31+65	54+38			428			
54+38	57+31	231	29	78	211	153	
57+31	63+04	849	107	182	829	560	
63+04	65+97	231	29	83	211	153	
TOTALS		5478	680	1718	5265	3550	160

STRAND ASSOCIATES, INC. ENGINEERS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAU 3753
SAUK TRAIL

SCHEDULES

SCALE: VERT. N.T.S.
HORIZ.
DATE 6/19/2006

DRAWN BY JBH
CHECKED BY JRM

FILENAME: S:\04\037-00\450\620\PLS\Warrens\Std. and Schedule\schedules_R36F.dgn
DATE: 6/19/2006
TIME: 09:49:49 PM