

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEET SHEETS	SHEET NO.
1373 00-00058-00-RS		COOK	113	5
STA. N/A	TO STA. N/A			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT No: 83861				

CODE NUMBER	ITEMS	UNIT	TOTAL QUANTITY	PARTICIPATING QUANTITY	NONPARTICIPATING QUANTITY	ROADWAY RESURFACING AND WIDENING 1000-2A	ROADWAY RECONSTRUCTION J000	PAVEMENT MARKING SFTY-ID	TRAFFIC SIGNS Y002-1C	LANDSCAPING Y003	RAILROAD PROTECTIVE DEVICES SFTY-5A
60500040	REMOVING MANHOLES	EACH	8	8	0	2	6				
60500050	REMOVING CATCH BASINS	EACH	16	16	0		16				
60600605	CONCRETE CURB, TYPE B	FOOT	855	855	0		855				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	7,323	7,328	0		7,328				
* 66900205	SPECIAL WASTE DISPOSAL	CU. YD.	2,100	2,100	0		2,100				
67100100	MOBILIZATION	L SUM	1	1	0		1				
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	0	0.1	0.9				
70300100	SHORT TERM PAVEMENT MARKINGS	FOOT	510	510	0	510					
70300200	TEMPORARY PAVEMENT MARKING	FOOT	21,300	21,300	0			21,300			
72000100	SIGN PANEL-TYPE 1	SQ. FT.	25	25	0				25		
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	8	8	0				8		
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	8	8	0				8		
72900100	METAL POST - TYPE A	FOOT	81	81	0				81		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ. FT.	123	123	0						123
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,185	2,185	0			1,838			347
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	382	382	0			382			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	186	186	0			108			78
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	51	51	0			45			6
* XX001386	SANITARY SEWERS, PVC, 8"	FOOT	373	0	373						
XX005690	STORM SEWER, DUCTILE IRON PIPE, CLASS 52, 12"	FOOT	554	554	0		554				
XX005691	STORM SEWER, DUCTILE IRON PIPE, CLASS 52, 18"	FOOT	1,084	1,084	0		1,084				
XX005692	STORM SEWER, DUCTILE IRON PIPE, CLASS 52, 24"	FOOT	608	608	0	440	168				
* XX006247	SANITARY SEWER REMOVAL	FOOT	370	0	370						
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	79	79	0		79				
* X0324330	WATER MAIN REMOVAL, 4"	FOOT	1,000	0	1000						
X0712400	TEMPORARY PAVEMENT	SQ. YD.	1,920	1,920	0	1,920					
* X0811100	RAILROAD CROSSING	L SUM	1	1	0						1
X3550310	BITUMINOUS BASE COURSE SUPERPAVE 6 1/2"	SQ. YD.	12,032	12,032	0	12,032					
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	265	265	0	265					
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	18	18	0	18					
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	722	722	0		722				
Z0001050	AGGREGATE SUBGRADE 12"	SQ. YD.	14,286	14,286	0		14,286				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	0		1				
* Z0048400	RAILROAD CROSSING REMOVAL	EACH	1	1	0						1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	0	1					
Δ Z0076600	TRAINEES	HOUR	500	500	0		500				
* XX006625	DUCTILE IRON WATERMAIN, CLASS 52, 6"	FOOT	1,000	0	1000						
XX006626	STORM SEWER, DUCTILE IRON PIPE, CLASS 52, 30"	FOOT	125	125	0	60	65				
XX006627	BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH), SUPERPAVE, 4 1/4"	SQ. YD.	12,032	12,032	0	12,032					

* INDICATES A SPECIALTY ITEM

Y080

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>SUMMARY OF QUANTITIES SHEET 2 OF 2</p> <p>SCALE: VERT. DRAWN BY: MJK HORIZ. CHECKED BY: BJC DATE: 4/6/06</p>