

SUMMARY OF QUANTITIES

F.A.U. ROUTE	CONTRACT NO.	COUNTY	TOTAL SHEETS
5348	87330	DEKALB	140
STATE SECTION			3
09-00160-00-WR			
SUMMARY OF QUANTITIES			
F.H.W.A. REG.5 ILLINOIS		PROJECT	HPP-2295(001)

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE								
				1000-2A ROADWAY	X028-2A BOX CULVERT	Y003 LANDSCAPING ORNAMENTAL	Y030-1E LIGHTING	Y030-1F SIGNALS S. MALTA RD./TAYLOR ST.	Y031-1F SIGNALS INTERCONNECT	Y080 TRAINING	Y000 NON-PART.	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	88	88								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	56	56								
20200100	EARTH EXCAVATION	CU YD	24,977	24,907	70							
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	16,540	16,520	1,020							
20400800	FURNISHED EXCAVATION	CU YD	2,000	2,000								
20600110	GRANULAR EMBANKMENT, SPECIAL	TON	1,870		1,870							
20700110	POROUS GRANULAR EMBANKMENT	TON	880		880							
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	15,520	15,520								
20800150	TRENCH BACKFILL	CU YD	4,946	3,586							1,360	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	32,398	31,630	768							
21301084	EXPLORATION TRENCH 84" DEPTH	FOOT	200	200								
* 25000210	SEEDING, CLASS 2A	ACRE	7.6	7.8								
* 25000312	SEEDING, CLASS 4A	ACRE	6.1	6.1								
* 25000314	SEEDING, CLASS 4B	ACRE	0.7	0.7								
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,394	1,394								
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,394	1,394								
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,394	1,394								
* 25100115	MULCH, METHOD 2	ACRE	30.0	30.0								
* 25100630	EROSION CONTROL BLANKET	SQ YD	10,764	10,764								
* 25200110	SODDING, SALT TOLERANT	SQ YD	7,863	7,863								
25200200	SUPPLEMENTAL WATERING	UNIT	120	120								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,781	1,781								
28000300	TEMPORARY DITCH CHECKS	EACH	51	51								
28000400	PERIMETER EROSION BARRIER	FOOT	1,715	1,715								
28000500	INLET AND PIPE PROTECTION	EACH	35	35								
28000510	INLET FILTERS	EACH	37	37								
28100105	STONE RIPRAP, CLASS A3	SQ YD	105	105								
28100107	STONE RIPRAP, CLASS A4	SQ YD	198	198								
28100111	STONE RIPRAP, CLASS A6	SQ YD	200	200								
28200200	FILTER FABRIC	SQ YD	398	398								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	34	34								
40600300	AGGREGATE (PRIME COAT)	TON	81	81								
40600980	BITUMINOUS SURFACE REMOVAL - BUT JOINT	SQ YD	416	416								
42001300	PROTECTIVE COAT	SQ YD	8,951	8,951								
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	149	149								
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	35,045	35,045								
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	1,110	1,110								
42400800	DETECTABLE WARNINGS	SQ FT	412	412								
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	203	203								
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	4,270	4,270								
44000300	CURB REMOVAL	FOOT	148	148								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,601	1,601								
44000600	SIDEWALK REMOVAL	SQ FT	10,499	10,499								
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	920	920								
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	8	8								
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	51	51								
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	19	19								
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	8	8								
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	14	14								
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	95	95								
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	340	340								
44300300	AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	SQ YD	10,744	10,744								
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	575	575								
* 50800300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1	1								
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	24,290		24,290							
50900500	ALUMINUM RAILING	FOOT	128		128							
51100300	SLOPE WALL 8 INCH	SQ YD	44		44							

* SPECIALTY ITEM